

1 GENERAL

1.01 DESCRIPTION

- .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
- .2 Demolition and removal will consist of, but not necessarily be limited to, the following:
 - .1 Mobilization and Demobilization of all equipment necessary to make work progress for the duration of this contract.
 - .2 Submittal of environmental mitigation plan and its implementation(s). One submittal for all three locations.
 - .3 Submittal of a Health and Safety Plan, including provision for Covid-19. One submittal for all three locations. Protection and its implementation (s).
 - .4 Gain access to the construction zone.
 - .5 Disconnection, removal and disposal of existing electrical on the existing floats and gangway as indicated on the drawings.
 - .6 Disconnection of existing floating wharves from the steel pipe pile anchor system, as indicated on the drawings.
 - .7 Contractor must block the entrances to the gangways, prior to removing the gangway, for safety purposes, and then remove the blockage once the gangway and new floating wharves have been installed.
 - .1 This must be included in the Health and Safety portion of this contract.
- .3 Removal of all other items required for the progress of the work.
- .4 Mobilization and demobilization of all necessary equipment for the duration of this contract.

1.02 GENERAL REQUIREMENTS

- .1 A Notice to Shipping is to be issued prior to commencement and upon completion of work.
- .2 During construction, any vessels or barges utilized must be marked in accordance with the provisions of the Canada Shipping Act Collision Regulations.
- .3 Upon completion of the project, a written Notice to Mariners must be issued.

1.03 PROTECTION

- .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.
- .2 Remove all floating debris from water on a routine and timely basis.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 EXECUTION

- .1 Inspect site and verify with Departmental Representative objects designated for removal.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

3.02 REMOVAL

- .1 Remove in their entirety all materials and objects specified for removal.
- .2 Do not disturb adjacent work designated to remain in place.

3.03 DISPOSAL OF MATERIAL

- .1 All demolished materials, except materials designated to be reused, will become property of contractor and will be removed from site and disposed of, to the satisfaction of Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the contractor to dispose of all demolished materials at an approved disposal site. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site.
- .2 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.

3.04 RESTORATION

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.

END OF SECTION