



SPECIFICATIONS

SOLICITATION #: 22-58040

BUILDING: S-77,
100 Sussex Drive,
Ottawa, Ontario

PROJECT: S-77 Heating Modifications Steam to Hot
Water

PROJECT #: 6032

Date: August 2022



SPECIFICATION

TABLE OF CONTENTS

Construction Tender Form

Buy and Sell Notice

Instructions to Bidders

Ontario Sales Tax

Acceptable Bonding Companies

Articles of Agreement

Plans and Specifications **A**

Terms of Payment **B**

General Conditions **C**

Labour Conditions and Fair Wage Schedule **D**

Insurance Conditions **E**

Contract Security Conditions **F**

Security Requirement Check List **G**

Construction Tender Form

Project Identification **S-77 Heating Modifications Steam to Hot Water**

Tender No.: **22-58040**

1.2 Business Name and Address of Tenderer

Name _____

Address _____

Contact Person(Print Name) _____

Telephone (_____) _____ **Fax:** (_____) _____

1.3 Offer

I/We the Tenderer, hereby offer to Her Majesty the Queen in Right of Canada (hereinafter referred to as "Her Majesty") represented by the National Research Council Canada to perform and complete the work for the above named project in accordance with the Plans and Specifications and other Tender Documents, at the place and in the manner set out therein for the Total Tender Amount (to be expressed in numbers only) of: \$_____. _____
in lawful money of Canada (excluding GST/HST)

The above amount is inclusive of all applicable (*) Federal, Provincial and Municipal taxes except that in the event of a change in any tax imposed under the Excise Act, the Excise Tax Act, the Old Age Security Act, the Customs Act, the Customs Tariff or any provincial sales tax legislation imposing a retail sales tax on the purchase of tangible personal property incorporated into Real Property, that occurs

- .1 after the date this tender was mailed or delivered, or
- .2 if this tender is revised, after the date of the last revision

the amount of this offer shall be decreased or decreased in the manner provided for in GC22 of the General Conditions of the Contract Documents.

National Research Council Canada	Conseil national de recherches Canada
Finance and Procurement Services Branch	Direction des services financiers et d'approvisionnement

1.3.1 Offer (continued)

(*) For the purpose of this tender, the Goods and Services Tax (GST) is not to be considered as an applicable tax.

In the province of Quebec, the Quebec Sales Tax is not to be included in the tender amount because the Federal Government is exempt from this tax. Tenderers shall make arrangements directly with the provincial Revenue Department to recover any tax they may pay on good and services acquired in the performance of this contract. However, tenderers should include in their tender amount Quebec Sales Tax for which an Input Tax Refund is not available.

1.4 Acceptance and Entry into Contract

I/We undertake, within fourteen (14) days of notification of acceptance of my/our offer, to sign a contract for the performance of the work provided I/we are notified, by the Department, of the acceptance of my/our offer within 30 days of the tender closing date.

1.5 Construction Time

I/We Agree to complete the work within the time stipulated in the specification from the date of notification of acceptance of my/our offer.

1.6 Bid Security

I/We herewith enclose tender security in accordance with Article 5 of the General Instruction to Tenderers.

I/We understand that if a security deposit is furnished as tender security and if I/we refuse to enter into a contract when called upon to do so, my/our security deposit shall be forfeited but the Minister may, if it is in the public interest, waive the right of Her Majesty to forfeit the security deposit.

I/We understand that if the security furnished is not in the approved form as described in Article 5 of the General Instructions to Tenderers, my/our tender is subject to disqualification.

National Research Council Conseil national de recherches
Canada Canada

Finance and Procurement Direction des services financiers
Services Branch et d’approvisionnement

1.7 Contract Security

Within fourteen (14) days after receipt of written notification of the acceptance of my/our offer, I/we will furnish contract security in accordance with the Contract Conditions “F” of the Contract Documents.

I/We understand that the contract security referred to herein, if provided in the form of a bill of exchange, will be deposited into the Consolidated Revenue Fund of Canada.

1.8 Appendices

This Tender Form includes Appendix No. _____N/A_____.

1.9 Addenda

The Total Tender Amount provides for the Work described in the following Addenda:

NUMBER	DATE	NUMBER	DATE

(Tenderers shall enter numbers and dates of addenda)

National Research Council Canada	Conseil national de recherches Canada
Finance and Procurement Services Branch	Direction des services financiers et d'approvisionnement

1.10 Execution of Tender

The Tenderer shall refer to Article 2 of the General Instructions to Tenderers.

**SIGNED, ATTESTED TO AND DELIVERED on the _____ day of
_____ on behalf of**

(Type or print the business name of the Tenderer)

AUTHORIZED SIGNATORY (IES)

(Signature of Signatory)

(Print name & Title of Signatory)

(Signature of Signatory)

(Print name & Title of Signatory)

SEAL

BUY AND SELL NOTICE

S77 Heating Modifications Steam to Hot Water

The National Research Council Canada, 100 Sussex Drive, has a requirement for a project that includes:

Work under this contract covers Modifications to the existing Heating System and converting it from Steam to Hot Water of Building S77 located at 100 Sussex Dr Ottawa of the National Research Council of Canada.

1. GENERAL

Questions regarding any aspect of the project are to be addressed to and answered only by the Departmental Representative (or his designate) or the Contracting Authority.

Any information received other than from the Departmental Representative (or his designate) or the Contracting Authority will be disregarded when awarding the contract and during construction.

Firms intending to submit tenders on this project should obtain tender documents through the Buyandsell.gc.ca TMA services provider. Addenda, when issued, will be available from the Buyandsell.gc.ca TMA service provider. Firms that elect to base their bids on tender documents obtained from other sources do so at their own risk and will be solely responsible to inform the tender calling authority of their intention to bid. Tender packages are not available for distribution on the actual day of tender closing.

2. MANDATORY SITE VISIT

It is mandatory that the bidder attends one of the site visits at the designated date and time. At least one representative from proponents that intend to bid must attend. The site visits will be held on August 25th and August 26th, 2022 at 9:00am. Meet Allan Smith at Building S-77, Main Entrance, 100 Sussex Drive, Ottawa, ON. Bidders who, for any reason, cannot attend one of the specified dates and time will not be given an alternative appointment to view the site and their tenders, therefore, will be considered as non-responsive. **NO EXCEPTIONS WILL BE MADE.**

* Due to COVID-19, we are taking additional measures to protect you and our employees at the site visits.

- At the site visit, to limit contact and risks:
 - o The proponents will sanitize their hands at the hand sanitizing station.
 - o The proponents will be asked to sign the Attendance Form. It is the responsibility of all proponents to verify information on the Attendance Form.
 - o The site visit will proceed with a maximum of four (4) proponents at a time. Each group will have approximately 20 minutes to review the site. The site visit will continue with the next group of four (4) proponents until each one has had a chance to review the site.
 - o The site visits could take longer than usual, therefore anticipate a longer meeting duration.

- Physical distancing: keeping a distance of at least 2 arms-length (approximately 2 metres) from others may not be possible at all times, therefore the use of NRC issued disposable face coverings to reduce the risk of transmission of COVID-19 is mandatory.
 - The proponents shall not impede safe access to and from the facility.
- Depending on the anticipated amount of pre-registration, the NRC may decide to schedule time slots for every group of four (4) proponents. The time slot for your site visit will be confirmed by the NRC Departmental Representative by email upon pre-registration. That time will supersede the site visit meeting time specified above.
 - Proposals submitted by bidders who have not attended the site visit or failed to submit their identification and contact information at the site visit will be deemed non-responsive.

3. CLOSING DATE

Closing date is September 16, 2022, 14:00

4. TENDER RESULTS

Following the Tender closing, the tender results will be sent by email to all Contractors who submitted a tender.

5. SECURITY REQUIREMENT FOR CANADIAN CONTRACTORS

5.1 MANDATORY SECURITY REQUIREMENT:

This procurement contains a mandatory security requirement as follows:

1. The Contractor must, at all times during the performance of the Contract, hold a valid Designated Organization Screening (DOS), issued by the Canadian Industrial Security Director (CISD), Public Works Government Services Canada.
2. The Contractor personnel requiring access to sensitive work site(s) must EACH hold a valid RELIABILITY STATUS, granted or approved by CISD/PWGSC.
3. The Contractor must comply with the provisions of the:
 - a. Security Requirements Checklist attached at Appendix "D"
 - b. Industrial Security Manual (Latest Edition) available at: <https://www.tpsgc-pwgsc.gc.ca/esc-src/msi-ism/index-eng.html>

5.2 VERIFICATION OF SECURITY CLEARANCE AT BID CLOSING

1. The Bidder must hold a valid Designated Organization Screening (DOS) issued by the Canadian Industrial Security Directorate (CISD), Public Works and Government Services Canada (PWGSC), **TO BE INCLUDED WITH THEIR TENDER OR PROVIDED WITHIN 48 HOURS FROM THE DATE AND TIME OF TENDER CLOSING.** Verifications will be made through CISD to confirm the security clearance status of the Bidder. Failure to comply with this requirement will render the bid non-compliant and no further consideration will be given to the bid.

2. Within 72 hours of tender closing, the General Contractor must name all of his sub-contractors, each of whom must hold a valid **RELIABILITY STATUS**, granted or approved by CISD/PWGSC, or any other Federal Department or Agency along with the names and birthdates or security clearance certificate numbers of all personnel who will be assigned to the project.
3. It is to be noted that any subcontractor required to perform any part of the work during the performance of the subsequent contract must also adhere to the mandatory security requirement of the contract. As well, no personnel without the required level of security will be allowed on site. It will be the responsibility of the successful bidder to ensure that the security requirement is met throughout the performance of the contract. The Crown will not be held liable or accountable for any delays or additional costs associated with the contractor's non-compliance to the mandatory security requirement. Failure to comply with the mandatory security requirement will be grounds for being declared in default of contract.
4. For any enquiries concerning the project security requirement during the bidding period, the Bidder/Tenderer must contact the Security Officer @ 613-993-8956.

6. WSIB (WORKPLACE SAFETY AND INSURANCE BOARD)

All Bidders must provide a valid WSIB certificate with their Tender or prior to contract award.

7. OFFICE OF THE PROCUREMENT OMBUDSMAN

1. Clause for solicitation documents and regret letters for unsuccessful bidders

The Office of the Procurement Ombudsman (OPO) was established by the Government of Canada to provide an independent venue for Canadian bidders to raise complaints regarding the award of federal contracts under \$25,300 for goods and under \$101,100 for services. Should you have any issues or concerns regarding the award of a federal contract below these dollar amounts, contact OPO by e-mail at boa.opo@boa-opo.gc.ca, by telephone at 1-866-734-5169, or by web at www.opo-boa.gc.ca. For more information about OPO, including the available services, please visit the OPO website.

2. Contract Administration

The parties understand that the Procurement Ombudsman appointed pursuant to Subsection 22.1 (1) of the Department of Public Works and Government Services Act will review a complaint filed by the complainant respecting the administration of the Contract if the requirements of Subsection 22.2(1) of the Department of Public Works and Government Services Act and Sections 15 and 16 of the Procurement Ombudsman Regulations have been met.

To file a complaint, the Office of the Procurement Ombudsman may be contacted by e-mail at boa.opo@boa-opo.gc.ca, by telephone at 1-866-734-5169, or by web at www.opo-boa.gc.ca.

3. Dispute Resolution

The Parties agree to make every reasonable effort, in good faith, to settle amicably all disputes or claims relating to or arising from the Contract, through negotiations between the Parties' representatives authorized to settle. If the Parties do not reach a settlement within 10 working days, each party hereby consents to fully participate in and bear the cost of mediation led by the Procurement Ombudsman pursuant to Subsection 22.1(3)(d) of the Department of Public Work and Government Services Act and Section 23 of the Procurement Ombudsman Regulations.

The Office of the Procurement Ombudsman may be contacted by telephone at 1-866-734-5169, by e-mail at boa.opo@boa-opo.gc.ca, or by web at www.opo-boa.gc.ca.

The Departmental Representative or his designate for this project is:

Allan Smith

Telephone: 613-852-1357

Contracting Authority for this project is: Tania Backes

Tania.Backes@nrc-cnrc.gc.ca

INSTRUCTIONS TO BIDDERS

Article 1 – Receipt of Tender

- 1a) Tender must be received **by email only** not later than the specified tender closing time. Electronic bids received after the indicated closing time - NRC servers received time - will be irrevocably rejected. Bidders are urged to send their proposal sufficient time in advance of the closing time to prevent any technical issues. NRC will not be held responsible for bids sent before closing time but received by the NRC servers after the closing time. Tenders received after this time are invalid and shall not be considered, regardless of any reason for their late arrival.
- 1b) A letter of printed telecommunication from a bidder quoting a price shall not be considered as a valid tender unless a formal tender has been received on the prescribed Tender Form.
- 1c) Bidders may amend their tenders by **email only** provided that such amendments are received not later than the specified tender closing time.
- 1d) Any amendments to the tender which are transmitted by **email only** must be signed and must clearly identify the tenderer.

All such amendments are to be addressed to:
National Research Council of Canada
Tania Backes, Senior Procurement Officer

Tania.Backes@nrc-cnrc.gc.ca

Article 2 – Tender Form & Qualifications

- 1) All tenders must be submitted on the Construction Tender Form and the tender must be signed in compliance with the following requirements:
 - a) Limited Company: The full names of the Company and the name(s) and status of the authorized signing officer(s) must be printed in the space provided for that purpose. The signature(s) of the authorized officer(s) and the corporate seal must be affixed.
 - b) Partnership: The firm name and the name(s) of the person(s) signing must be printed in the space provided. One or more of the partners must sign in the presence of a witness who must also sign. An adhesive colored seal must be affixed beside each signature.
 - c) Sole Proprietorship: The business name and the name of the sole proprietor must be printed in the space provided. The sole proprietor must sign in the presence of a witness who must also sign. An adhesive coloured seal must be affixed beside each signature.
- 2) Any alterations in the printed part of the Construction Tender Form or failure to provide the information requested therein, may render the tender invalid.
- 3) All space in the Construction Tender Form must be completed and any handwritten or typewritten corrections to the parts so completed must be initialed immediately to the side of the corrections by the person or persons executing the tender on behalf of the tenderer.
- 4) Tenders must be based on the plans, specifications and tender documents provided.

- 5) A proposal submitted by a bidder who's Board of Directors or proprietor (s) are in majority the same as a former vendor who has declared bankruptcy while performing work for NRC over the last 7-years from the date of issuance of this RFP may be rejected and not eligible for award at NRC's sole discretion. In such case, NRC will advise the ineligible proponent(s).
- 6) A proposal submitted by a bidder who has had a previous contracts cancelled by NRC due to lack of performance within 3 years from the issuance date of this RFP may be rejected and not eligible for award at NRC's sole discretion. In such case, NRC will advise the ineligible proponent (s).
- 7) If there is discrepancy between the English version and the French version of this document and any of the attachments and amendments, the English version will takes precedence.

Article 3 - Contract

- 1) The Contractor will be required to sign a contract similar to the Standard Contract Form for Fixed Price Construction Contracts, a blank specimen of which is enclosed in the package for reference purposes.

Article 4 – Tender Destination

- 1a) Tenders are to be submitted **by email only**:
National Research Council Canada

Tania.Backes@nrc-cnrc.gc.ca

Endorsed "Tender for (insert title of work as it appears in the drawings and specifications)" and must bear the name and address of the tenderer.

- 1b) Unless otherwise specified, the only documents required to be submitted with the tender are the Tender form and the Bid Security.

Article 5 - Security

- 1a) Bid Security is required and must be submitted in one of the following forms:
 - i) bonds of the Government of Canada, or bonds unconditionally guaranteed as to principal and interest by the Government of Canada; **OR**
 - ii) a bid bond.
- 1b) Regardless of the Bid Security submitted, it should never be more than \$250,000 maximum, calculated at 10% of the first \$250,000 of the tendered price, plus 5% of any amount in excess of \$250,000.
- 1c) Bid Security shall accompany each tender or, if forwarded separately from the tender, shall be provided not later than the specified tender closing time. Bid bond or E-bond Security must be in the ORIGINAL form. PDF via email is acceptable. **FAILURE TO PROVIDE THE REQUIRED BID SECURITY SHALL INVALIDATE THE TENDER.**
- 1d) The successful tenderer is required to provide security within 14 days of receiving notice of tender acceptance. The tenderer must furnish EITHER:

- i) a Security Deposit as described in 1(b) above together with a Labour and Material Payment Bond in the amount of at least 50% of the amount payable under the contract, OR
 - ii) a Performance Bond and a Labour and Material Payment Bond – each in the amount of 50% of the amount payable under the contract.
- 1e) Bonds must be in an approved form and from the companies whose

bonds are acceptable to the Government of Canada. Samples of the approved form of Bid Bond, Performance Bond and Labour and Material Payment Bond and a list of acceptable Bonding Companies may be obtained from the Contracting Officer, National Research Council, Building M-58, Montreal Road, Ottawa, Ontario, K1A 0R6.

Article 7 – Sales Tax

- 1) The amount of the tender shall include all taxes as levied under the Excise Act, the Excise Tax Act, the Old Age Security Act, the Customs Act or the Customs Tariff, in force or applicable at the time.
- 1) In Quebec, the Provincial Sales Tax should not be included in the Tender Price as the Federal Government is exempt. Tenderers should contact the Provincial Revenue Minister to recover all taxes paid for goods and services rendered under this contract.

Tenderers must include in their Tender Price the amount of Provincial Sales Tax for which the exemption does not apply.

Article 8 – Examination of Site

- 1) All parties tendering shall examine the sites of the proposed work before sending in their tender and make themselves thoroughly acquainted with the same and obtain for themselves any and all information that may be necessary for the proper carrying out of the Contract. No after claim will be allowed or entertained for any work or material that may be requisite and necessary for the proper execution and completion of this Contract with the exception of that provided for under GC 35 in the General Conditions of the General Specification.

Article 9 – Discrepancies, Omissions, Etc.

- 1a) Bidders finding discrepancies in, or omissions from, drawings, specifications or other documents, or having any doubt as to the meaning or intent of any part thereof, should at once notify the Engineer who will send written instructions or explanation to all bidders.
- 1b) Neither the Engineer nor the Council will be responsible for oral instructions.
- 1c) Addenda or corrections issued during the time of the bidding shall be covered in the proposal. However, the contract supersedes all communications, negotiations and agreements, either written or oral, relating to the work and made prior to the date of the contract.

Article 10 – No additional Payments for Increased Costs

- 1) The only other adjustments in the contract price allowed are those specified in the General Conditions of the General Specification. The contract price will not be amended for change in freight rates, exchange rates, wage rates or cost of materials, plant or services.

Article 11 – Awards

- 1a) The Council reserves the power and right to reject tenders received from parties who cannot show a reasonable acquaintance with and preparation for the proper performance of the class of work herein specified and shown on plans. Evidence of such competence must be furnished by the tenderers if required to do so.
- 1b) A tenderer may be required to furnish to the Contracting Office, National Research Council of Canada, Building M-58, 1200 Montreal Road, Ottawa, Ontario, K1A 0R6, Canada, unsigned copies of the insurance requirements as covered by the Insurance Conditions of the General Specification.
- 1c) The Council does not bind itself to accept the lowest or any tender.

Article 12 – Harmonized Sales Tax

- 1) The Harmonized Sales Tax (HST) which is now in effect shall be considered an applicable tax for the purpose of this tender. However, the bidder shall NOT include any amount in the bid price for said HST. The successful contractor will indicate on each application for payment as a separate amount the appropriate HST the Owner is legally obliged to pay. This amount will be paid to the Contractor in addition to the amount certified for payment under the Contract in addition to the amount certified for payment under the Contract and will therefore not affect the Contract Price. The Contractor agrees to remit any HST collected or due to Revenue Canada.

Non-resident contractors

RST guide 804

Published August 2006

ISBN: 1-4249-2007-8 (Print), **1-4249-2009-4 (PDF)**, **1-4249-2008-6 (HTML)**

Publication Archived

Notice to the reader: For Retail Sales Tax (RST) – On July 1, 2010 the 13 per cent Harmonized Sales Tax (HST) took effect in Ontario replacing the existing provincial Retail Sales Tax (RST) and combining it with the federal Goods and Services Tax (GST). As a result, RST provisions described on this page and in other publications ended on June 30, 2010.

Effective July 1, 2010 this publication was archived for RST purposes **only**. Use caution when you refer to it, since it reflects the law in force for RST at the time it was released and may no longer apply.

- The information in this Guide explains the Retail Sales Tax (RST) responsibilities of a non-resident contractor who is awarded a construction contract to perform work in Ontario and their Ontario customers. Please note that this Guide replaces the previous version dated March 2001.

Non-Resident Contractor Defined

A non-resident contractor is a contractor located outside Ontario who has been awarded a construction contract to perform work in Ontario, and who has not maintained a permanent place of business in Ontario continuously for twelve months immediately prior to signing the contract, or which is not a company incorporated under the laws of Ontario. A construction contract is a contract for the erection, remodelling or repair of a building or other structure on land.

A contractor is a person who is in the business of constructing, altering, repairing or improving real property and includes, but is not limited to,

1. a general contractor and subcontractor,
2. a carpenter, bricklayer, stonemason, electrician, plasterer, plumber, painter, decorator, paver, and bridge builder,
3. a sheet metal, tile and terrazzo, heating, air conditioning, insulation, ventilating, papering, road, roofing and cement contractor, who installs or incorporates items into real property. (See RST [Guide 206 - Real Property and Fixtures](#)).

Registration and Guarantee Deposit

Non-resident contractors who are awarded a construction contract in Ontario are required to register with the Ministry of Finance (ministry), Centralized Programs Unit and post a guarantee equal to 4 per cent of the total of each Ontario contract. The guarantee can be paid in cash, by certified cheque (payable to the Minister of Finance), letter of credit or by a guarantee bond.

To register with the ministry and to obtain further information on posting a guarantee, contractors should contact the ministry's Centralized Programs Unit, 33 King Street West, PO Box 623, Oshawa, Ontario, L1H 8H7, toll-free 1 866 ONT-TAXS (1 866 668-8297) or fax to 905 435-3617.

Non-resident contractors who sell taxable goods on a supply only basis to Ontario customers, or provide taxable services in Ontario, may obtain a regular Vendor Permit to collect and remit RST on their sales. Non-resident contractors who have been issued a regular Vendor Permit must still register separately with the ministry and post a guarantee if they are awarded a construction contract in Ontario.

Letter of Compliance

After receiving the guarantee, the ministry mails out two copies of a "letter of compliance" to the contractor certifying the Retail Sales Tax (RST) requirements have been met. Contractors must give a copy of the letter to their customers.

If a copy of the compliance letter is not provided, the customer must withhold 4 per cent of all amounts payable to the non resident contractor and pay the withheld amounts to the Minister of Finance (minister). Details relating to the contract should be sent along with the payments to the Centralized Programs Unit. Customers may give the minister a guarantee bond equal to 4 per cent of the total contract price instead of making the 4 per cent payments.

Note: Customers who do not follow these requirements may be held liable for 4 per cent of all amounts payable to the non resident contractor or any other amount that the Ministry deems to be the RST payable resulting from the performance of the contract.

Calculation of RST

Fair Value

RST is payable on the "fair value" of materials, purchased or brought into Ontario, to be used for work performed in Ontario. "Fair value" includes:

- the purchase price in Canadian funds;
- all charges by the supplier for handling and delivery, and
- any federal customs duties and excise taxes paid (but not the federal Goods and Services Tax (GST)).

Contractors are also required to pay RST to Ontario suppliers on the purchase, rental or lease of taxable services, materials, machinery, or equipment.

Machinery and Equipment - Leased

If machinery or equipment is leased from a supplier outside Ontario and brought into the province, RST is payable on the lease payments for the period the machinery or equipment is in Ontario.

Machinery and Equipment - Owned by Contractor

If machinery or equipment is owned by the contractor, RST may be calculated in one of the following ways:

- a. If a contractor brings machinery and equipment into Ontario for less than 12 months' use, RST is to be calculated using the following formula:

$$1/36 \times \text{net book value at date of import} \times \text{number of months in Ontario} \times \text{tax rate}$$

For the purpose of this formula, RST is payable for each month or part of a month that the goods are in Ontario. A month is considered 31 consecutive days and a part month is considered more than 12 days. The RST payable is based on the number of days the machinery and equipment are located in Ontario and not the number of days the items are actually used.

Example: Equipment is brought into Ontario on March 28 and taken out on May 8. The items were in the province for 41 days. RST is payable on the first 31 days' temporary stay in Ontario vs. use of the equipment. Since the remainder (10 days) is not considered part of a month, no RST is payable on this portion.

- b. If, at the time the goods are brought into Ontario, it is expected that the machinery or equipment will be in Ontario for more than twelve months, contractors must pay Retail Sales Tax (RST) on the following basis:

net book value at date of import x tax rate

If, at the time of import, the length of time is not known, vendors may use the formula under (a). If they later find it necessary to keep the machinery and equipment in Ontario for more than 12 months, the RST paid under (a) may be deducted from the RST payable under (b).

Using formula (a) or (b) above, contractors will calculate and remit the RST payable on the return that is filed when the contract is finished.

(See Completion of Contract section)

M a n u f a c t u r i n g f o r O w n U s e

Contractors may need to manufacture items, such as doors and windows, for their construction contracts. Manufacturing is work done in a factory away from a construction site, or in a mobile unit or workshop that is on or near the construction site. Manufacturing occurs when raw materials are changed into manufactured goods for use in real property contracts.

Contractors are considered to be manufacturing contractors if they produce goods:

1. for their own use in real property contracts, and
2. the manufactured cost of the goods is more than \$50,000 a year.

(See RST Guide 401 - Manufacturing Contractors)

C o n t r a c t s w i t h t h e F e d e r a l G o v e r n m e n t

Where a non-resident contractor enters into a construction contract with the federal government, for the construction of a building and/or the installation of equipment, the nature of the equipment will determine whether the contract should be let on a tax-included or tax excluded basis.

Contracts for the construction of a building and the installation of equipment that directly services that building (i.e., elevators, escalators, light fixtures, central heating and air conditioning, etc.) should be tendered on a tax -included basis. Contractors are the consumers of the materials used in fulfilling these contracts and must pay or account for RST on the materials used to complete the contracts. There is NO exemption just because the contract is with the federal government.

Contracts for the installation of equipment that becomes a fixture and does not directly service a building (i.e., material handling equipment, production machinery, communication equipment, training equipment) may be tendered on a tax-excluded basis. Contractors engaged in contracts of this nature are permitted to make tax exempt purchases of such equipment by issuing a valid Purchase Exemption Certificate (PEC) to their supplier. Only non-resident contractors who have registered with the ministry and posted a guarantee may issue a PEC.

E x e m p t i o n s

Contractors may supply and install equipment or materials for certain customers that may be entitled to an exemption from RST (e.g., manufacturers, Indian band councils, farmers and diplomatic organizations). The equipment or materials, when installed, becomes real property if it is permanently attached to land, or a fixture if it is permanently attached to a building or real property structure. Since

contractors are liable for RST, they should contact the ministry to find out if the customer qualifies for exemption before tendering the contract on a tax-excluded basis.

Status Indians, Indian Bands and Band Councils

Non-resident contractors may purchase building materials exempt from Retail Sales Tax (RST) for certain buildings and structures situated on reserves. The cost of such projects must be paid by the band council, and the buildings must provide a community service for the reserve. Contracts for the construction of an exempt community building project should be made on an RST-excluded basis. Non-resident contractors may purchase the materials exempt from RST by providing suppliers with a valid Purchase Exemption Certificate (PEC). As noted previously, only non-resident contractors who have registered with the ministry and posted a guarantee may issue a PEC. (See RST Guide [204 - Purchase Exemption Certificates](#)).

Non-resident contractors must pay RST on items purchased for incorporation into a building or structure built for individual status Indians on a reserve. (See RST [Guide 808 - Status Indians, Indian Bands and Band Councils](#)).

Completion of Contract

When a contract is completed, non-resident contractors who were required to post a guarantee must complete a [Non-Resident Contractor Retail Sales Tax Return \[PDF - 92 KB\]](#) that is provided by the ministry.

If a contractor's guarantee was given in cash or by certified cheque, the amount of the deposit can be deducted from the RST liability owed by the contractor. If the liability is greater than the deposit, the amount remaining must be paid by the contractor. If the deposit is more than the liability, the contractor will receive a refund.

If a guarantee bond was posted instead of cash, the bond will be discharged once the RST liability is paid in full.

All returns are subject to audit.

Legislative References

- Retail Sales Tax Act, Subsections 19(2) and 39(3)(4) and (5)
- Regulation 1012 under the Act, Subsections 15.3(1)(2)(5)(6) and (7)
- Regulation 1013 under the Act, Sections 1 and 3

For More Information

The information contained in this publication is only a guideline. For more information, please contact the Ontario Ministry of Finance at 1 866 ONT-TAXS (1 866 668-8297) or visit our website at ontario.ca/finance.

Acceptable Bonding Companies

Published September 2010

The following is a list of insurance companies whose bonds may be accepted as security by the government.

1. Canadian Companies

- ACE INA Insurance
- Allstate Insurance Company of Canada
- Ascentus Insurance Ltd. (Surety only)
- Aviva Insurance Company of Canada
- AXA Insurance (Canada)
- AXA Pacific Insurance Company
- Canadian Northern Shield Insurance Company
- Certas Direct Insurance Company (Surety only)
- Chartis Insurance Company of Canada (formerly AIG Commercial Insurance Company of Canada)
- Chubb Insurance Company of Canada
- Commonwealth Insurance Company
- Co-operators General Insurance Company
- CUMIS General Insurance Company
- The Dominion of Canada General Insurance Company
- Echelon General Insurance Company (Surety only)
- Economical Mutual Insurance Company
- Elite Insurance Company
- Everest Insurance Company of Canada
- Federated Insurance Company of Canada
- Federation Insurance Company of Canada
- Gore Mutual Insurance Company
- Grain Insurance and Guarantee Company
- The Guarantee Company of North America
- Industrial Alliance Pacific General Insurance Corporation
- Intact Insurance Company
- Jevco Insurance Company (Surety only)
- Lombard General Insurance Company of Canada
- Lombard Insurance Company
- Markel Insurance Company of Canada
- The Missisquoi Insurance Company
- The Nordic Insurance Company of Canada
- The North Waterloo Farmers Mutual Insurance Company (Fidelity only)
- Novex Insurance Company (Fidelity only)
- The Personal Insurance Company
- Pilot Insurance Company
- Quebec Assurance Company
- Royal & Sun Alliance Insurance Company of Canada
- Saskatchewan Mutual Insurance Company
- Scottish & York Insurance Co. Limited
- The Sovereign General Insurance Company
- TD General Insurance Company
- Temple Insurance Company
- Traders General Insurance Company

- Travelers Guarantee Company of Canada
- Trisura Guarantee Insurance Company
- The Wawanesa Mutual Insurance Company
- Waterloo Insurance Company
- Western Assurance Company
- Western Surety Company

2. Provincial Companies

Surety bonds issued by the following companies may be accepted provided that the contract of suretyship was executed in a province in which the company is licensed to do business as indicated in brackets.

- AXA Boreal Insurance Company (P.E.I., N.B., Que., Ont., Man., B.C.)
- AXA Boreal Insurance Company (P.E.I., N.B., Que., Ont., Man., B.C.)
- ALPHA, Compagnie d'Assurances Inc. (Que.)
- Canada West Insurance Company (Ont., Man., Sask, Alta., B.C., N.W.T.) (Surety only)
- The Canadian Union Assurance Company (Que.)
- La Capitale General Insurance Inc. (Nfld. & Lab., N.S., P.E.I., Que.(Surety only), Man., Sask., Alta., B.C., Nun., N.W.T., Yuk.)
- Coachman Insurance Company (Ont.)
- Continental Casualty Company (Nfld. & Lab., N.S., P.E.I., N.B., Que., Ont., Man., Sask., Alta., B.C., Nun., N.W.T., Yuk.)
- GCAN Insurance Company (Nfld. & Lab., N.S., P.E.I., N.B., Que., Ont., Man., Sask., Alta., B.C., Nun., N.W.T., Yuk.)
- The Insurance Company of Prince Edward Island (N.S., P.E.I., N.B.)
- Kingsway General Insurance Company (N.S., N.B., Que., Ont., Man., Sask., Alta., and B.C.)
- Liberty Mutual Insurance Company (Nfld. & Lab., N.S., P.E.I., N.B., Que., Ont., Man., Sask., Alta., B.C., Nun., N.W.T., Yuk.)
- Manitoba Public Insurance Corporation (Man.)
- Norgroupe Assurance Générales Inc.
- Orleans General Insurance Company (N.B., Que., Ont.)
- Saskatchewan Government Insurance Office (Sask.)
- SGI CANADA Insurance Services Ltd. (Ont., Man., Sask., Alta.)
- L'Unique General Insurance Inc. (Nfld. & Lab., N.S., P.E.I., N.B., Que.(Surety only), Ont.(Surety only), Man., Sask., Alta., B.C.(Surety only), Nun., N.W.T., Yuk.)

3. Foreign Companies

- Aspen Insurance UK Limited
- Compagnie Française d'Assurance pour le Commerce Extérieur (Fidelity only)
- Eagle Star Insurance Company Limited
- Ecclesiastical Insurance Office Public Limited Company (Fidelity only)
- Lloyd's Underwriters
- Mitsui Sumitomo Insurance Company, Limited
- NIPPONKOA Insurance Company, Limited
- Sompo Japan Insurance Inc.
- Tokio Marine & Nichido Fire Insurance Co., Ltd.
- XL Insurance Company Limited (Surety only)
- Zurich Insurance Company Ltd

Articles of Agreement

Standard Construction Contract – Articles of Agreement
(23/01/2002)

- A1 Contract Documents
- A2 Date of Completion of Work and Description of Work
- A3 Contract Amount
- A4 Contractor's Address
- A5 Unit Price Table

Articles of Agreement

These Articles of Agreement made in duplicate this day of .

Between

Her Majesty the Queen, in right of Canada (referred to in the contract documents as “ Her Majesty”) represented by the National Research Council Canada (referred to in the contract documents as the “Council”)

and

(referred to in the contract documents as the “Contractor”)

Witness that in consideration for the mutual promises and obligations contained in the contract, Her Majesty and the Contractor covenant and agree as follows:

A1 Contract Documents

(23/01/2002)

1.1 Subject to A1.4 and A1.5, the documents forming the contract between Her Majesty and the Contractor, referred to herein as the contract documents, are

1.1.1 these Articles of Agreement,

1.1.2 the document attached hereto, marked “A” and entitled “Plans and Specifications”, referred to herein as the Plans and Specifications,

1.1.3 the document attached hereto, marked “B” and entitled “Terms of Payment”, referred to herein as the Terms of Payment,

1.1.4 the document attached hereto, marked “C” and entitled “General Conditions”, referred to herein as the General Conditions,

1.1.5 the document attached hereto, marked “D” and entitled “Labour Conditions”, referred to herein as the Labour Conditions,

1.1.6 the document attached hereto, marked “E” and entitled “Insurance Conditions”, referred to herein as the Insurance Conditions,

1.1.7 the document attached hereto, marked “F” and entitled “Contract Security Conditions”, referred to herein as the Contract Security Conditions, and

1.1.8 any amendment or variation of the contract documents that is made in accordance with the General Conditions.

1.1.9 the document entitled Fair Wage Schedules for Federal Construction Contracts referred to herein as Fair Wage Schedules

Articles of Agreement

The Council hereby designates _____ of _____ of the Government of Canada as the Engineer for the purposes of the contract, and for all purposes of or incidental to the contract, the Engineer's address shall be deemed to be:

1.2 In the contract

1.3.1 "Fixed Price Arrangement" means that part of the contract that prescribes a lump sum as payment for performance of the work to which it relates; and

1.3.2 "Unit Price Arrangement" means that part of the contract that prescribes the product of a price multiplied by a number of units of measurement of a class as payment for performance of the work to which it relates.

1.3 Any of the provisions of the contract that are expressly stipulated to be applicable only to a Unit Price Arrangement are not applicable to any part of the work to which a Fixed Price Arrangement is applicable.

1.4 Any of the provisions of the contract that are expressly stipulated to be applicable only to a Fixed Price Arrangement are not applicable to any part of the work to which a Unit Price Arrangement is applicable.

A2 Date of Completion of Work and Description of Work

(23/01/2002)

2.1 The contractor shall, between the date of these Articles of Agreement and the _____, _____, in the careful and workmanlike manner, diligently perform and complete the following work:

which work is more particularly described in the Plans and Specifications.

Articles of Agreement

A3 Contract Amount

(23/01/2002)

- 3.1 Subject to any increase, decrease, deduction, reduction or set-off that may be made under the Contract, Her Majesty shall pay the Contractor at the times and in the manner that is set out or referred to in the Terms of Payment
- 3.1.1 the sum of _____ (GST/HST extra), in consideration for the performance of the work or the part thereof that is subject to Fixed Price Arrangement, and
- 3.1.2 a sum that is equal to the aggregate of the products of the number of units of Measurement of each class of labour, plant and material that is set out in a Final Certificate of Measurement referred to in GC44.8 multiplied in each case by the appropriate unit price that is set out in the Unit Price Table in consideration for the performance of the work or the part thereof that is subject to a Unit Price Arrangement.
- 3.2 For the information and guidance of the Contractor and the persons administering the contract on behalf of Her Majesty, but not so as to constitute a warranty, representation or undertaking of any nature by either party, it is estimated that the total amount payable by Her Majesty to the Contractor for the part of the work to which a Unit Price Arrangement is applicable will be approximately \$N/A
- 3.3 A3.1.1 is applicable only to a Fixed Price Arrangement.
- 3.4 A3.1.2 and A3.2 applicable only to a Unit Price Arrangement.

A4 Contractor's Address

(23/01/2002)

- 4.1 For all purposes of or incidental to the contract, the Contractor's address shall be deemed to be:

Articles of Agreement

A5 Unit Price Table

(23/01/2002)

5.1 Her Majesty and the Contractor agree that the following table is the Unit Price Table for the purposes of the contract.

Column 1 Item	Column 2 Class of Labour Plant Or Material	Column 3 Unit of Measurement	Column 4 Estimated Total Quantity	Column 5 Price per Unit	Column 6 Estimated Total Price
		N/A			

5.2 The Unit Price Table that is set out in A5.1 designates the part of the work to which a Unit Price Arrangement is applicable.

5.3 The part of the work that is not designated in the Unit Price Table referred to in A5.2 is the part of the work to which a Fixed Price Arrangement is applicable.

Articles of Agreement

Signed on behalf of Her Majesty by

as Senior Contracting Officer

and _____

as _____

of the **National Research Council Canada**

on the _____

day of _____

Signed, sealed and delivered by

as _____ and
Position

by _____

as _____ and
Position

of _____

on the _____

day of _____

Seal

	Pages
Division 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS	
Section 00 01 10 - Table of Contents	2
Section 00 10 00 – General Instructions.....	11
Section 00 15 45 – General and Fire Safety Requirements.....	6
Division 01 - GENERAL REQUIREMENTS	
Section 01 74 19 – Waste Management and Disposal.....	7
Section 01 91 13 – General Commissioning (CX) Requirements.....	10
Section 01 91 31 – Commissioning (CX) Plan.....	9
Section 01 91 33 – Commissioning Forms.....	3
Section 01 91 41 – Commissioning: Training.....	3
Division 2 – EXISTING CONDITIONS	
Section 02 42 00 – Removal and Salvage of Construction Materials.....	3
Division 22 - PLUMBING	
Section 22 05 05 – Selective Demolition for Plumbing	4
Division 23 - HEATING, VENTILATING AND AIR CONDITIONING (HVAC)	
Section 23 05 00 – Common Work Results for HVAC	5
Section 23 05 05 – Installation of Pipework	6
Section 23 05 05.01 – Selective Demolition for HVAC-R Equipment	5
Section 23 05 17 – Pipe Welding	3
Section 23 05 23.01 – Valves – Bronze	3
Section 23 05 29 – Hangers and Supports for HVAC Piping and Equipment.....	7
Section 23 05 48 – Vibration and Seismic Controls for HVAC Piping and Equipment.....	5
Section 23 05 53.01 – Mechanical Identification	5
Section 23 05 93 – Testing, Adjusting and Balancing for HVAC.....	5
Section 23 07 15 – Thermal Insulation for Piping	5
Section 23 21 13.02 – Hydronic Systems: Steel	5
Section 23 21 14 – Hydronic Specialties	3
Section 23 55 01 – Duct Heaters.....	3
Section 23 82 36 – Finned Tube Radiation Heaters	3
Section 23 82 39 – Unit Heaters	3
Division 25 - INTEGRATED AUTOMATION	
Section 25 01 11 – EMCS: Start-Up, Verification and Commissioning.....	6
Section 25 05 01 – EMCS: General Requirements.....	6
Section 25 05 02 – EMCS: Submittals and Review Process.....	4
Section 25 05 03 – EMCS: Project Record Documents.....	3
Section 25 05 54 – EMCS: Identification.....	3

Section 25 08 20 – EMCS: Warranty and Maintenance.....	4
Section 25 10 01 – EMCS: Local Area Network (LAN).....	3
Section 25 30 01 – EMCS: Building Controllers.....	4
Section 25 30 02 – EMCS: Field Control Devices.....	5
Section 25 90 01 – EMCS: Site Requirements, Applications and Systems Sequence of Operation.....	2
Division 26 – ELECTRICAL	
Section 26 05 00 – Common Work Results - Electrical.....	6
Section 26 05 05 – Selective Demolition for Electrical	5
Section 26 05 21 – Wires and Cables (0-1000V).....	2
Section 26 05 22 – Connectors and Terminations.....	2
APPENDIX	35

END OF TABLE

1. SCOPE OF WORK

- .1 Work under this contract covers the conversion of existing steam equipment to hot water in the Council's Building S77 of the National Research Council.

2. COMPLETION

- .1 Complete all work within 12 weeks after receipt of notification of acceptance of tender.

3. GENERAL

- .1 The word "provide" in this Specification means to supply and install.
- .2 Provide items mentioned in either the drawings or the specification.

4. SPECIFIED ACCEPTABLE & ALTERNATIVE EQUIPMENT & MATERIALS

- .1 Materials and equipment scheduled and/or specified on the drawings or in the specifications have been selected to establish a performance and quality standard. In most cases, acceptable manufacturers are stated for any material or equipment specified by manufacturer's name and model number. Contractors may base their tender price on materials and equipment supplied by any of the manufacturers' names as acceptable for the particular material or equipment.
- .2 In addition to the manufacturers specified or named as acceptable, you may propose alternative manufacturers of materials or equipment to the Departmental Representative for acceptance. For a product to be considered as an alternative product substitute, make a written application to the Departmental Representative during the tender period, not later than ten (10) working days before tender closing.
- .3 Certify in writing that the alternative meets all requirements of the specified material or equipment. In addition, it shall be understood that all costs required by or as a result of acceptance or proposed alternatives, will be borne by the Contractor.
- .4 Approval of alternatives will be signified by issue of an Addendum to the Tender Documents.
- .5 Any alternative manufacturers or materials submitted which are incomplete and cannot be evaluated, or are later than ten (10) working days before tender closing date or after the tender period, will not be considered.

5. MINIMUM STANDARDS

- .1 Conform to or exceed minimum acceptable standards of the various applicable federal, provincial and municipal codes such as The National Building Code, The National Fire Code, Canadian Plumbing Code, Canadian Electrical Code, Canadian Code for Construction Safety and the Provincial Construction Safety Act.
- .2 Work to conform to referenced standards and codes as reaffirmed or revised to date of specification.

6. WORKPLACE HAZARDOUS MATERIAL INFORMATION SYSTEM (WHMIS)

- .1 The General Contractor shall comply with Federal and Provincial legislation regarding the WHMIS. The Contractor's responsibilities include, but are not limited to the following:
 - .1 To ensure that any controlled product brought on site by the Contractor or sub-contractor is labeled;
 - .2 To make available to the workers and the Departmental Representative, Material Safety Data Sheets (MSDS) for these controlled products;
 - .3 To train own workers about WHMIS, and about the controlled products that they use on site;
 - .4 To inform other Contractors, sub-contractors, the Departmental Representative, authorized visitors and outside inspection agency personnel about the presence and use of such products on the site.
 - .5 The site foreman or superintendent must be able to demonstrate, to the satisfaction of the Departmental Representative, that he/she has had WHMIS training and is knowledgeable in its requirements. The Departmental Representative can require replacement of this person if this condition or implementation of WHMIS is not satisfactory

7. REQUIREMENTS OF BILL 208, SECTION 18(a)

Under the requirements of Bill 208 of the Ontario Ministry of Labour Occupational Health & Safety Act, the following designated substances may be encountered while performing the work described in these contract documents:

- .1 Acrylonitrile, Isocyanates, Arsenic, Lead, Asbestos, Mercury, Benzene, Silica, Coke Oven Emissions, Vinyl Chloride, and Ethylene Oxide
 - .1 It is the responsibility of the General Contractor to ensure that each prospective sub-contractor for this project has received a copy of the above list.

8. COST BREAKDOWN

- .1 Submit, for approval by the Departmental Representative, a cost breakdown of tender 72 hours after the contract is awarded.
- .2 Use the approved cost breakdown as the basis for submitting all claims.
- .3 Request Departmental Representative's verbal approval to amount of claim prior to preparing and submitting the claim in its final form.
- .4 Contractor costs associated with compliance with occupational health and safety requirements (Canada Labour Code) related to the Coronavirus/COVID-19 pandemic must be included in the initial bid price. These costs may include, but are not limited to, the provision of additional personal protective equipment (PPE) and social distancing requirements as required to complete the project. Contractor must review and incorporate into initial bid pricing compliance with any Coronavirus/COVID-19 related health and safety guidance issued by the local Medical Officer of Health (applicable in the jurisdiction of the project), the Public Health Agency of Canada, Health Canada and/or the provincial Ministry of Health, as applicable.

9. SUB-TRADES

- .1 Submit no later than 72 hours after tender closing, a complete list of sub trades for the Departmental Representative's review.

10. PERSONNEL SECURITY AND IDENTIFICATION

- .1 All persons employed by the Contractor, or by any sub-contractor and present on the site must be security cleared in accordance with the requirements of the Section entitled Special Instructions to Tenderers.
- .2 All such persons must wear and keep visible identification badges as issued by the Security Office of NRC.

11. WORKING HOURS AND SECURITY

- .1 Normal working hours on the NRC property are from 8:00 a.m. until 4:30 p.m., Monday to Friday inclusive, except statutory holidays.
- .2 At all other times, special written passes are required for access to the building site.
- .3 Before scheduling any work outside normal working hours, obtain permission from the Departmental Representative to perform the specific tasks.
- .4 An escort may be required whenever working outside normal hours. Contractor to bear the associated costs.

12. SCHEDULE

- .1 The Contractor shall prepare a detailed schedule, fixing the date for commencement and completion of the various parts of the work and update the said schedule. Such schedule shall be made available to the Departmental Representative not later than two weeks after the award of the contract and prior to commencement of any work on site.
- .2 Notify Departmental Representative in writing of any changes in the schedule.
- .3 Seven (7) days before the scheduled completion date, arrange to do an interim inspection with the Departmental Representative.

13. PROJECT MEETINGS

- .1 Hold regular project meetings at times and locations approved by the Departmental Representative.
- .2 Notify all parties concerned of meetings to ensure proper coordination of work.
- .3 Departmental Representative will set times for project meetings and assumes responsibility for recording and distributing minutes.

14. SHOP DRAWINGS

- .1 Submit to Departmental Representative for review, shop drawings, product data and samples specified within two (2) weeks after contract award.
- .2 Submit to Departmental Representative for review a complete list of all shop drawings, product data and samples specified and written confirmation of corresponding delivery dates within one (1) week after shop drawings, product data and samples approval date. This list shall be updated on a weekly basis and any changes to the list shall be immediately notified in writing to the Departmental Representative.
- .3 Review shop drawings, data sheets and samples prior to submission.
- .4 Submit one (1) electronic copy of all shop drawings and product data and samples for review, unless otherwise specified.
- .5 Review of shop drawings and product data by the Departmental Representative does not relieve the Contractor of the responsibility for errors and omissions and for the conformity with contract documents.

15. MATERIALS AND WORKMANSHIP

- .1 Install only new materials on this project unless specifically noted otherwise.
- .2 Only first class workmanship will be accepted, not only with regard to safety, efficiency, durability, but also with regard to neatness of detail and performance.

16. WORK & MATERIALS SUPPLIED BY OWNER

- .1 Work and materials not included in this contract are described on drawings and in this specification.
- .2 Deliver to a storage place, as directed by the Departmental Representative, all materials returned to the Owner.
- .3 Unless otherwise specified, accept owner-supplied materials at their storage location and provide all transportation as required.
- .4 General Contractor's duties:
 - .1 Unload at site.
 - .2 Promptly inspect products and report damaged or defective items.
 - .3 Give written notification to the Departmental Representative for items accepted in good order.
 - .4 Handle at site, including uncrating and storage.
 - .5 Repair or replace items damaged on site.
 - .6 Install, connect finished products as specified.

17. SITE ACCESS

- .1 Make prior arrangements with the Departmental Representative before starting work or moving materials and equipment on site.
- .2 Obtain approval of Departmental Representative for regular means of access during the construction period.
- .3 Obtain approval of Departmental Representative before temporarily suspending operations on site; before returning to the site and before leaving the site at the end of the job.
- .4 Provide and maintain access to site.
- .5 Make good any damage and clean up dirt, debris, etc., resulting from Contractor's use of existing roads.

18. USE OF SITE

- .1 Restrict operations on the site to the areas approved by the Departmental Representative
- .2 Locate all temporary structures, equipment, storage, etc., to the designated areas.
- .3 Restrict parking to the designated areas.

19. ACCEPTANCE OF SITE

- .1 Inspect the site before commencing work, review any unexpected conditions with the Departmental Representative.
- .2 Commencement of work will imply acceptance of existing conditions.

20. SITE OFFICE & TELEPHONE

- .1 Contractor to erect a temporary site office at his own expense.
- .2 Install and maintain a telephone, if necessary.
- .3 Use of NRC phones is not permitted unless in the case of an emergency.

21. SANITARY FACILITIES

- .1 Obtain permission from the Departmental Representative to use the existing washroom facilities in the building or provide sanitary facilities, and bear all associated costs.

22. TEMPORARY SERVICES

- .1 A source of temporary power will be made available in the area. Bear all costs to make connections to the power source and perform distribution on site.

- .2 Provide all load centres, breakers, conduit, wiring, disconnects, extension cords, transformers, as required from the source of power.
- .3 Power is to be used only for power tools, lighting, controls, motors, and not for space heating.
- .4 A source of temporary water will be made available if required.
- .5 Bear all costs associated with distributing the water to the required locations.
- .6 Comply with NRC requirements when connecting to existing systems in accordance with the articles entitled "Co-operation" and "Service Interruptions" of this section.

23. DOCUMENTS REQUIRED AT WORK SITE

- .1 The Contractor shall keep on the site, one (1) up-to-date copy of all contract documents, including specifications, drawings, addenda, shop drawings, change notices, schedule and any reports or bulletins pertaining to the work, in good order, available to the Departmental Representative and to his / her representatives at all times.
- .2 At least one (1) copy of specifications and drawings shall be marked by the Contractor to show all work "As Built" and shall be provided to the Departmental Representative with the Application for Payment and for the Final Certificate of Completion.

24. CO-OPERATION

- .1 Co-operate with NRC staff in order to keep disruption of normal research work to an absolute minimum.
- .2 Work out in advance, a schedule for all work which might disrupt normal work in the building.
- .3 Have schedule approved by the Departmental Representative.
- .4 Notify the Departmental Representative in writing, 72 hours prior to any intended interruption of facilities, areas, corridors, mechanical or electrical services and obtain requisite permission.

25. PROTECTION AND WARNING NOTICES

- .1 Provide all materials required to protect existing equipment.
- .2 Erect dust barriers to prevent dust and debris from spreading through the building.
- .3 Place dust protection in the form of cover sheets over equipment and furniture and tape these sheets to floors, to ensure no dust infiltration.
- .4 Repair or replace any and all damage to Owner's property caused during construction, at no cost to the Owner and to the satisfaction of the Departmental Representative.
- .5 Protect the buildings, roads, lawns, services, etc. from damage which might occur as a result of this work.

- .6 Plan and co-ordinate the work to protect the buildings from the leakage of water, dust, etc.
- .7 Ensure that all doors, windows, etc., that could allow transfer of dust, noise, fumes, etc., to other areas of the building are kept closed.
- .8 Be responsible for security of all areas affected by the work under the Contract until acceptance by NRC. Take all necessary precautions to prevent entry to the work area by unauthorized persons and guard against theft, fire and damage by any cause. Secure working area at the end of each day's work and be responsible for same.
- .9 Provide and maintain adequate safety barricades around the work sites to protect NRC personnel and the public from injury during the construction.
- .10 Post warnings, in all instances where possible injury could occur such as Work Overhead, Hard Hat Areas, etc. or as required by the Departmental Representative.
- .11 Provide temporary protective enclosures over building entrances and exits to protect pedestrians. All enclosures to be structurally sound against weather and falling debris.

26. BILINGUALISM

- .1 Ensure that all signs, notices, etc. are posted in both official languages.
- .2 Ensure that all identification of services called for by under this contract are bilingual.

27. LAYOUT OF WORK

- .1 Location of equipment, fixtures, outlets and openings indicated on drawings or specified are to be considered as approximate.
- .2 Locate equipment, fixtures and distribution systems to provide minimum interference and maximum usable space and in accordance with the manufacturer's recommendations for safety, access and maintenance.
- .3 Employ competent person to lay out work in accordance with the contract documents.

28. DISCREPANCIES & INTERFERENCES

- .1 Prior to the start of the work, examine drawings and specifications. Report at once to the Departmental Representative, any defects, discrepancies, omissions or interferences affecting the work.
- .2 Contractor to immediately inform the Departmental Representative in writing, of any discrepancies between the plans and the physical conditions so the Departmental Representative may promptly verify same.
- .3 Any work done after such a discovery, until authorized, is at the Contractor's risk.
- .4 Where minor interferences as determined by the Departmental Representative are encountered on the job and they have not been pointed out on the original tender or on the plans and

specifications, provide offsets, bends or reroute the services to suit job conditions at no extra cost.

- .5 Arrange all work so as not to interfere in any way with other work being carried out.

29. MANUFACTURER'S INSTRUCTIONS

- .1 Unless otherwise specified, comply with manufacturer's latest printed instructions for materials and installation methods.
- .2 Notify the Departmental Representative in writing of any conflict between these specifications and manufacturer's instruction. Departmental Representative will designate which document is to be followed.

30. CONNECTIONS TO AND INTERRUPTIONS TO EXISTING SERVICES

- .1 Where work involves breaking into or connecting to existing services, carry out work at times and in the manner agreed to by the Departmental Representative and by authorities having jurisdiction, with minimum disruption to NRC Personnel and vehicular traffic and minimum service interruption. Do not operate any NRC equipment or plant.
- .2 Before commencing work, establish location and extent of service lines in area of work and notify Departmental Representative of findings.
- .3 Submit a schedule to and obtain approval from the Departmental Representative for any shut-down or closure of active service or facility; allow minimum 72 hours notice. Adhere to approved schedule and provide notice to the Departmental Representative.
- .4 Where unknown services are encountered, immediately advise Departmental Representative and confirm findings in writing.
- .5 Provide detours, bridges, alternate feeds, etc., as required to minimize disruptions.
- .6 Protect existing services as required and immediately make repairs if damage occurs.
- .7 Remove any abandoned service lines as indicated on the contract documents and as approved by the Departmental Representative; cap or otherwise seal lines at cut-off points. Record and provide a copy to the Departmental Representative of locations of maintained, re-routed and abandoned service lines.

31. CUTTING AND PATCHING

- .1 Cut existing surfaces as required to accommodate new work.
- .2 Remove all items as shown or specified.
- .3 Patch and make good with identical materials, the surfaces that have been disturbed, cut or damaged, to the satisfaction of the Departmental Representative.

- .4 Where new pipes pass through existing construction, core drill an opening. Size openings to leave 12mm (1/2") clearance around the pipes or pipe insulation. Do not drill or cut any surface without the approval of the Departmental Representative.
- .5 Obtain written approval of the Departmental Representative before cutting openings through existing or new structural members.
- .6 Seal all openings where cables, conduits or pipes pass through walls with an acoustic sealant conforming to CAN/CGSB-19.21-M87.
- .7 Where cables, conduits and pipes pass through fire rated walls and floors, pack space between with compressed glass fibres and seal with fire stop caulking in accordance with CAN/CGSB-19.13-M87 AND NBC 3.1.7.

32. FASTENING DEVICES

- .1 Do not use explosive actuated tools, without first obtaining permission from the Departmental Representative.
- .2 Comply with the requirements of CSA A-166 (Safety Code for Explosive Actuated Tools).
- .3 Do not use any kind of impact or percussion tool without first obtaining permission from the Departmental Representative.

33. OVERLOADING

- .1 Ensure that no part of the building or work is subjected to a load which will endanger safety or cause permanent deformation or structural damage.

34. STORAGE

- .1 Provide storage as required to protect all tools, materials, etc., from damage or theft and be responsible for the same.
- .2 Do not store flammable or explosive materials on site without the authorization of the Departmental Representative.

35. GENERAL REVIEW

- .1 Periodic review of the Contractor's work by the Departmental Representative does not relieve the Contractor of the responsibility of making the work in accordance with contract documents. Contractor shall carry out his own quality control to ensure that the construction work is in accordance with contract documents.
- .2 Inform the Departmental Representative of any impediments to the installation and obtain his / her approval for actual location.

36. INSPECTION OF BURIED OR CONCEALED SERVICES

- .1 Prior to concealing any services that are installed, ensure that all inspection bodies concerned, including NRC, have inspected the work and have witnessed all tests. Failure to do so may result in exposing the services again at the Contractor's expense.

37. TESTING

- .1 On completion, or as required by local authority inspectors and/or Departmental Representative during progress of work and before any services are covered up and flushing is complete, test all installations in the presence of the Departmental Representative.
- .2 Obtain and hand to the Departmental Representative all acceptance certificates or test reports from authority having jurisdiction. The project will be considered incomplete without the same.

38. PARTIAL OCCUPANCY

- .1 NRC may request partial occupancy of the facility if the contract extends beyond the expected completion date.
- .2 Do not restrict access to the building, routes, and services.
- .3 Do not encumber the site with materials or equipment.

39. DISPOSAL OF WASTES

- .1 Dispose of waste materials including volatiles, safely off NRC property. Refer to the section entitled "General and Fire Safety Requirements" included as part of this specification.

40. CLEAN-UP DURING CONSTRUCTION

- .1 On a daily basis, maintain project site and adjacent area of campus including roofs, free from debris and waste materials.
- .2 Provide on-site dump containers for collection of waste materials and rubbish.

41. FINAL CLEAN-UP

- .1 Upon completion do a final clean-up to the satisfaction of the Departmental Representative.
- .2 Clean all new surfaces, lights, existing surfaces affected by this work, replace filters, etc.
- .3 Clean all resilient flooring and prepare to receive protective finish. Protective finish applied by NRC.

42. WARRANTY AND RECTIFICATION OF DEFECTS IN WORK

- .1 Refer to General Conditions "C", section GC32.

- .2 Ensure that all manufacturers' guarantees and warranties are issued in the name of the **General Contractor** and the National Research Council.

43. MAINTENANCE MANUALS

- .1 Provide two (2) bilingual copies of maintenance manuals or two (2) English and two (2) French maintenance manuals and one (1) electronic copy of same immediately upon completion of the work and prior to release of holdbacks.
- .2 Manuals to be neatly bound in hard cover loose leaf binders.
- .3 Manuals to include operating and maintenance instructions, all guarantees and warranties, shop drawings, technical data, etc., for the material and apparatus supplied under this contract.

44. EXAMINATION OF THE SITE

- .1 Carefully examine conditions at the site which the site will or may affect your work, and become familiar with both the new and existing construction, finishes, and other work associated with your work in order that your tender price include for everything necessary for completion of your work within the proposed project schedule.

45. COORDINATION & COOPERATION WITH OTHER TRADES

- .1 Co-ordinate your work with the work of all trades to ensure a proper and complete installation. Notify all trades concerned of the requirement for openings, sleeves, inserts and other hardware necessary in their work for the installation of your work.
- .2 The exact locations and routing of mechanical and electrical services must be properly planned, coordinated and established with all affected trades prior to installation such that they will clear each other as well as any obstructions. Generally, piping requiring uniform pitch shall be given the right of way, with other services located and arranged to suit.

END OF SECTION

1. GENERAL CONSTRUCTION SAFETY REQUIREMENTS

- .1 The Contractor shall take all necessary steps to protect personnel (workers, visitors, general public, etc.) and property from any harm during the course of the contract.
- .2 The Contractor shall be solely responsible for the construction safety of both its employees and those of its sub-contractors at the work site, and for initiating, maintaining and supervising safety precautions, programs and procedures in connection with the performance of the work.
- .3 The Contractor shall comply with all Federal, Provincial and Municipal safety codes and regulations and the Occupational Health and Safety Act and the Workplace Safety and Insurance Board. In the event of any conflict between any provisions in legislation or codes, the most stringent provisions shall apply.
- .4 Periodic review of the Contractor's work by the Departmental Representative, using the criteria of the contract documents, does not relieve the Contractor of his safety responsibilities in carrying out the work in accordance with the contract documents. The Contractor shall consult with the Departmental Representative to ensure that this responsibility is carried out.
- .5 The Contractor shall ensure that only competent personnel are permitted to work on site. Throughout the term of the contract, any person will be removed from the site who is not observing or complying with the safety requirements.
- .6 All equipment shall be in safe operating condition and appropriate to the task.
- .7 Following a project and site hazard assessment, the Contractor shall develop a Site Specific Safety Plan based on the following minimum requirements. Site Specific Safety Plans must also be robust enough to address any abnormal occurrences, such as, but not limited to: pandemics (COVID-19 or a similar), fire, flooding, inclement weather or other environmental anomalies.
 - .1 Provide a safety board mounted in a visible location on the project site, with the following information included thereon:
 - .1 Notice of Project.
 - .2 Site specific Safety Policy.
 - .3 Copy of Ontario Health and Safety Act.
 - .4 Building Schematic showing emergency exits.
 - .5 Building emergency procedures.
 - .6 Contact list for NRC, Contractor and all involved sub-contractors.
 - .7 Any related MSDS sheets.
 - .8 NRC Emergency phone number.
- .8 The Contractor shall provide competent personnel to implement its safety program and those of any Health and Safety Act legislation applicable at this project location, and to ensure they are being complied with.
- .9 The Contractor shall provide safety orientation to all its employees as well as those of any sub-contractors under its jurisdiction.

- .10 The Departmental Representative will monitor to ensure that safety requirements are met and that safety records are properly kept and maintained. Continued disregard for safety standards can cause the contract to be cancelled and the Contractor or sub-contractors removed from the site.
- .11 The Contractor will report to the Departmental Representative and jurisdictional authorities, any accident or incident involving Contractor or NRC personnel or the public and/or property arising from the Contractor's execution of the work.
- .12 If entry to a laboratory is required as part of the work of the Contractor, a safety orientation shall be provided to all his employees as well as those of any sub-contractors regarding lab safety requirements and procedures, as provided by the Researcher or the Departmental Representative.

2. FIRE SAFETY REQUIREMENTS

.1 Authorities

1. The Fire Commissioner of Canada (FC) is the authority for fire safety at NRC.
2. For the purpose of this document, "Departmental Representative" will be deemed as the NRC person in charge of the project and who will enforce these Fire Safety Requirements.
3. Comply with the following standards as published by the Office of the Fire Commissioner of Canada:
 - a. Standard No. 301 - June 1982 "Standard for Construction Operations";
 - b. Standard No. 302 - June 1982 "Standard for Welding and Cutting".

.2 Smoking

- .1 Smoking is prohibited inside all NRC buildings, as well as roof areas.
- .2 Obey all "NO SMOKING" signs on NRC premises.

.3 Hot Work

- .1 Prior to commencement of any "Hot Work" involving welding, soldering, burning, heating, use of torches or salamanders or any open flame, obtain a Hot Work Permit from the Departmental Representative.
- .2 Prior to commencement of "Hot Work", review the area of hot work with the Departmental Representative to determine the level of fire safety precautions to be taken.

.4 Reporting Fires

- .1 Know the exact location of the nearest Fire Alarm Pull Station and telephone, including the emergency phone number.
- .2 REPORT immediately, all fire incidents as follows:
 1. Activate nearest fire alarm pull station; and

- .4 Carbon Dioxide (CO₂) extinguishers will not be considered as substitutes for the above.

.7 Roofing Operations

.1 Kettles:

- .1 Arrange for the location of asphalt kettles and material storage with the Departmental Representative before moving on site. Do not locate kettles on any roof or structure and keep them at least 10m (30 feet) away from a building.
- .2 Equip kettles with two (2) thermometers or gauges in good working order; a hand held and a kettle-mounted model.
- .3 Do not operate kettles at temperatures in excess of 232°C (450°F).
- .4 Maintain continuous supervision while kettles are in operation and provide metal covers for the kettles to smother any flames in case of fire. Provide fire extinguishers as required in article 2.6.
- .5 Demonstrate container capacities to Departmental Representative prior to start of work.
- .6 Store materials a minimum of 6m (20 feet) from the kettle.

.2 Mops:

- .1 Use only glass fibre roofing mops.
- .2 Remove used mops from the roof site at the end of each working day.

.3 Torch Applied Systems:

- .1 DO NOT USE TORCHES NEXT TO WALLS.
- .2 DO NOT TORCH MEMBRANES TO EXPOSED WOOD OR CAVITY.
- .3 Provide a Fire Watch as required by article 2.9 of this section.

- .4 Store all combustible roofing materials at least 3m (10 feet) away from any structure.

- .5 Keep compressed gas cylinders a minimum of 6m (20 feet) away from the kettle, protected from mechanical damage and secured in an upright position.

.8 Welding / Grinding Operations

- .1 Contractor to provide fire blankets, portable fume extraction devices, screens or similar equipment to prevent exposure to welding flash, or sparks from grinding.

.9 Fire Watch

- .1 Provide a fire watch for a minimum of one hour after the termination of any hot work operation.
- .2 For temporary heating, refer to General Instructions Section 00 010 00.
- .3 Equip fire watch personnel with fire extinguishers as required by article 2.6.

.10 Obstruction of access/egress routes-roadways, halls, doors, or elevators

- .1 Advise the Departmental Representative in advance of any work that would impede the response of Fire Department personnel and their apparatus. This includes violation of minimum overhead clearance, erection of barricades and the digging of trenches.
- .2 Building exit routes must not be obstructed in any way without special permission from the Departmental Representative, who will ensure that adequate alternative routes are maintained.
- .3 The Departmental Representative will advise the FPO of any obstruction that may warrant advanced planning and communication to ensure the safety of building occupants and the effectiveness of the Fire Department.

.11 Rubbish and Waste Materials

- .1 Keep rubbish and waste materials to a minimum and a minimum distance of 6m (20 feet) from any kettle or torches.
- .2 Do not burn rubbish on site.
- .3 Rubbish Containers:
 - .1 Consult with the Departmental Representative to determine an acceptable safe location for any containers and the arrangement of chutes etc. prior to bringing the containers on site.
 - .2 Do not overfill the containers and keep area around the perimeter free and clear of any debris.
- .4 Storage:
 - .1 Exercise extreme care when storing combustible waste materials in work areas. Ensure maximum possible cleanliness, ventilation and that all safety standards are adhered to when storing any combustible materials.
 - .2 Deposit greasy or oily rags or materials subject to spontaneous combustion in CSA or ULC approved receptacles and remove at the end of the work day or shift, or as directed.

.12 Flammable Liquids

- .1 The handling, storage and use of flammable liquids is governed by the current National Fire Code of Canada.
- .2 Flammable Liquids such as gasoline, kerosene and naphtha may be kept for ready use in quantities not exceeding 45 litres (10 imp gal), provided they are stored in approved safety cans bearing the ULC seal of approval and kept away from buildings, stockpiled combustible materials etc. Storage of quantities of flammable liquids exceeding 45

litres (10 imp gal) for work purposes, require the permission of the Departmental Representative.

- .3 Flammable liquids are not to be left on any roof areas after normal working hours.
- .4 Transfer of flammable liquids is prohibited within buildings.
- .5 Do not transfer flammable liquids in the vicinity of open flames or any type of heat producing device.
- .6 Do not use flammable liquids having a flash point below 38°C (100°F) such as naphtha or gasoline as solvents or cleaning agents.
- .7 Store flammable waste liquids for disposal in approved container located in a safe, ventilated area. Waste flammable liquids are to be removed from the site on a regular basis.
- .8 Where flammable liquids, such as lacquers or urethane are used, ensure proper ventilation and eliminate all sources of ignition. Inform the Departmental Representative prior to, and at the cessation of such work.

3. QUESTIONS OR CLARIFICATIONS

- .1 Direct any questions or clarification on Fire or General Safety, in addition to the above requirements, to the Departmental Representative.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 This Section includes requirements for management of construction waste and disposal, which forms the Contractor's commitment to reduce and divert waste materials from landfill and includes the following:
 - .1 Preparation of a Draft Construction Waste Management Plan that will be used to track the success of the Construction Waste Management Plan against actual waste diversion from landfill.
 - .2 Preparation of monthly progress reports indicating cumulative totals representing progress towards achieving diversion and reduction goals of waste materials away from landfill and identifying any special programs, landfill options or alternatives to landfill used during construction.
 - .3 Preparation of a Construction Waste Management Report containing detailed information indicating total waste produced by the project, types of waste material and quantity of each material, and total waste diverted and diversion rates indicated as a percentage of the total waste produced.
- .2 Owner has established that this project shall generate the least amount of waste possible and that processes that ensure the generation of as little waste as possible due to error, poor planning, breakage, mishandling, contamination, or other factors be employed by the Contractor.

1.2 RELATED REQUIREMENTS

- .1 Section 00 10 00 – General Instructions
- .2 Section 22 05 05 – Selective Demolition for Plumbing
- .3 Section 23 05 05 – Selective Demolition for HVAC-R Equipment

1.3 REFERENCE STANDARDS

- .1 ASTM International (ASTM)
 - .1 ASTM E1609 01, Standard Guide for Development and Implementation of a Pollution Prevention Program
- .2 Canada Green Building Council (CaGBC)
 - .1 LEED Reference Guide for Building Design and Construction, Version 4
- .3 Recycling Certification Institute (RCI):
 - .1 RCI Certification Construction and Demolition Materials Recycling

1.4 DEFINITIONS

- .1 Clean Waste: Untreated and unpainted; not contaminated with oils, solvents, sealants or similar materials.
- .2 Construction and Demolition Waste: Solid wastes typically including building materials, packaging, trash, debris, and rubble resulting from construction, re-modeling, repair and demolition operations.
- .3 Hazardous: Exhibiting the characteristics of hazardous substances including properties such as ignitability, corrosiveness, toxicity or reactivity.
- .4 Non-hazardous: Exhibiting none of the characteristics of hazardous substances, including properties such as ignitability, corrosiveness, toxicity, or reactivity.
- .5 Non-toxic: Not poisonous to humans either immediately or after a long period of exposure.
- .6 Recyclable: The ability of a product or material to be recovered at the end of its life cycle and remanufactured into a new product for reuse by others.
- .7 Recycle: To remove a waste material from the project site to another site for remanufacture into a new product for reuse by others.
- .8 Recycling: The process of sorting, cleansing, treating and reconstituting solid waste and other discarded materials for the purpose of using the altered form; recycling does not include burning, incinerating, or thermally destroying waste.
- .9 Return: To give back reusable items or unused products to vendors for credit.
- .10 Reuse: To reuse a construction waste material in some manner on the project site.
- .11 Salvage: To remove a waste material from the project site to another site for resale or reuse by others.
- .12 Sediment: Soil and other debris that has been eroded and transported by storm or well production run off water.
- .13 Source Separation: The act of keeping different types of waste materials separate beginning from the first time they become waste.
- .14 Toxic: Poisonous to humans either immediately or after a long period of exposure.
- .15 Trash: Any product or material unable to be reused, returned, recycled, or salvaged.
- .16 Volatile Organic Compounds (VOC's): Chemical compounds common in and emitted by many building products over time through outgassing:
 - .1 Solvents in paints and other coatings;
 - .2 Wood preservatives; strippers and household cleaners;
 - .3 Adhesives in particleboard, fiberboard, and some plywood; and foam insulation.

- .4 When released, VOC's can contribute to the formation of smog and can cause respiratory tract problems, headaches, eye irritations, nausea, damage to the liver, kidneys, and central nervous system, and possibly cancer.
- .17 Waste: Extra material or material that has reached the end of its useful life in its intended use. Waste includes salvageable, returnable, recyclable, and reusable material.
- .18 Construction Waste Management Plan: A project related plan for the collection, transportation, and disposal of the waste generated at the construction site; the purpose of the plan is to ultimately reduce the amount of material being landfilled.

1.5 ADMINISTRATIVE REQUIREMENTS

- .1 Coordination: Coordinate waste management requirements with all Divisions of the Work for the project, and ensure that requirements of the Construction Waste Management Plan are followed.
- .2 Preconstruction Meeting: Arrange a pre-construction meeting in accordance with Section 01 10 00 – General Instructions before starting any Work of the Contract attended by the Owner, Contractor, affected Subcontractor's and Departmental Representative to discuss the Contractor's Construction Waste Management Plan and to develop mutual understanding of the requirements for a consistent policy towards waste reduction and recycling.

1.6 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide required information in accordance with Section 01 10 00 – General Instructions.
- .2 Action Submittals: Provide the following submittals before starting any work of this Section:
 - .1 Draft Construction Waste Management Plan (Draft CWM Plan): Submit to Departmental Representative a preliminary analysis of anticipated site generated waste by listing a minimum of five (5) construction or demolition waste streams that have potential to generate the most volume of material indicating methods that will be used to divert construction waste from landfill and source reduction strategies; Departmental Representative will provide commentary before development of Contractor's Construction Waste Management Plan.
 - .2 Construction Waste Management Plan (CWM Plan): Submit a CWM Plan for this project prior to any waste removal from site and that includes the following information:
 - .1 Material Streams: Analysis of the proposed jobsite waste being generated, including material types and quantities forming a part of identified material streams in the Draft CWM Plan; materials removed from site destined for alternative daily cover at landfill sites and land clearing debris cannot be considered as contributing to waste diversion and will be included as a component of the total waste generated for the site.
 - .2 Recycling Haulers and Markets: Investigate local haulers and markets for recyclable materials, and incorporate into CWM Plan.
 - .3 Alternative Waste Disposal: Prepare a listing of each material proposed to be salvaged, reused, recycled or composted during the course of the project, and the proposed local market for each material.

- .4 Landfill Materials: Identify materials that cannot be recycled, reused or composted and provide explanation or justification; energy will be considered as a viable alternative diversion strategy for these materials where facilities exist and are operated in accordance with LEED Construction and Demolition Waste Management requirements.
- .5 Landfill Options: The name of the landfill where trash will be disposed of; landfill materials will form a part of the total waste generated by the project.
- .6 Materials Handling Procedures: A description of the means by which any recycled waste materials will be protected from contamination, and a description of the means to be employed in recycling the above materials consistent with requirements for acceptance by designated facilities.
- .7 Transportation: A description of the means of transportation of the recyclable materials, whether materials will be site separated and self-hauled to designated centers, or whether mixed materials will be collected by a waste hauler and removed from the site, and destination of materials.

1.7 PROJECT CLOSEOUT SUBMISSIONS

- .1 Record Documentation: Submit as constructed information in accordance with Section 01 10 00 – General Instructions as follows:
 - .1 Construction Waste Management Report (CWM Report): Submit a CWM Report for this project in a format that includes the following information:
 - .1 Accounting: Submit information indicating total waste produced by the project.
 - .2 Composition: Submit information indicating types of waste material and quantity of each material.
 - .3 Diversion Rate: Submit information indicating total waste diverted from landfill as a percentage of the total waste produced by the project.
 - .4 Transportation Documentation and Diversion Documentation: Submit copies of transportation documents or shipping manifests indicating weights of materials, and other evidence of disposal indicating final location of waste diverted from landfill and waste sent to landfill.
 - .5 Multiple Waste Hauling: Compile all information into a single CWM Report where multiple waste hauling and diversion strategies were used for the project.

1.8 QUALITY ASSURANCE

- .1 Resources for Development of Construction Waste Management Report (CWM Report): The following sources may be useful in developing the Draft Construction Waste Management Plan:
 - .1 Recycling Haulers and Markets: Investigate local haulers and markets for recyclable materials, and incorporate into CWM Plan.
 - .2 Waste-to-Energy Systems: Investigate local waste-to-energy incentives where systems for diverting materials from landfill for reuse or recycling are not available.
 - .3 Municipal Garbage & Recycling Waste Websites:
 - .1 Ontario
 - .1 National Capital Region (City of Ottawa)
<https://app06.ottawa.ca/cgi-bin/search/recycle/q.pl?q=&lang=en>

1.9 DELIVERY, STORAGE AND HANDLING

- .1 Storage Requirements: Implement a recycling/reuse program that includes separate collection of waste materials as appropriate to the project waste and the available recycling and reuse programs in the project area.
- .2 Handling Requirements: Clean materials that are contaminated before placing in collection containers and ensure that waste destined for landfill does not get mixed in with recycled materials:
 - .1 Deliver materials free of dirt, adhesives, solvents, petroleum contamination, and other substances deleterious to recycling process.
 - .2 Arrange for collection by or delivery to the appropriate recycling or reuse facility.
- .3 Hazardous Waste and Hazardous Materials: Handle in accordance with applicable regulations.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 OBJECTIVE

- .1 The Federal Sustainable Development Strategy (FSDS) presents the Government of Canada's sustainable development goals and targets, as required by the *Federal Sustainable Development Act*. In keeping with the purpose of this Act – to provide the legal framework for developing and implementing a Federal Sustainable Development Strategy that will make environmental decision-making more transparent and accountable to Parliament – National Research Council (NRC) supports the goals laid out in the FSDS through the activities described in our

Departmental Sustainable Development Strategy (DSDS). NRC's DSDS waste management target is as follows:

- .1 Divert at least 90% (by weight) of all construction and demolition waste from landfills (striving to achieve 100% by 2030).
- .2 Project Waste Diversion Target: 90%.

3.2 (CWM PLAN) IMPLEMENTATION

- .1 Manager: Contractor is responsible for designating an on-site party or parties responsible for instructing workers and overseeing and documenting results of the CWM Plan for the project.
- .2 Distribution: Distribute copies of the CWM Plan to the job site foreman, each Subcontractor, the Owner, the Departmental Representative and other site personnel as required to maintain CWM Plan.
- .3 Instruction: Provide on-site instruction of appropriate separation, handling, and recycling, salvage, reuse, composting and return methods being used for the project to Subcontractor's at appropriate stages of the project.
- .4 Separation Facilities: Lay out and label a specific area to facilitate separation of materials for potential recycling, salvage, reuse, composting and return:
 - .1 Recycling and waste bin areas are to be kept neat and clean and clearly marked in order to avoid contamination of materials.
 - .2 Hazardous wastes shall be separated, stored, and disposed of in accordance with local regulations.
- .5 Progressive Documentation: Submit a monthly summary of waste generated by the project to ensure that waste diversion goals are on track with project requirements:
 - .1 Submission of waste summary can coincide with application for progress payment, or similar milestone event as agreed upon between the Contractor and Departmental Representative.
 - .2 Monthly waste summary shall contain the following information:
 - .1 The amount in tonnes or m3 and location of material landfilled;
 - .2 The amount in tonnes or m3 and location of materials diverted from landfill; and
 - .3 Indication of progress based on total waste generated by the project with materials diverted from landfill as a percentage.

3.3 SUBCONTRACTOR'S RESPONSIBILITY

- .1 Subcontractor's shall cooperate fully with the Contractor to implement the CWM Plan.
- .2 Failure to cooperate may result in the Owner not achieving their environmental goals, and may result in penalties being assessed by the Contractor to the responsible Subcontractor's.

3.4 CONSTRUCTION WASTE MANAGEMENT FORMS

- .1 Departmental Representative will provide Contractor will NRC Waste Management and Disposal Tracking Forms (sample provided below) for recording management of construction waste.
- .2 Contractor shall utilize these forms for all waste management and disposal tracking for the duration of the project, and is responsible for maintaining current up to date records at all times during construction.
- .3 Contractor is responsible to ensure all waste management tracking forms, weigh-bills, donation receipts, and summary information are incorporated into Operational and Maintenance Manuals upon construction completion in accordance with 01 10 00 – General Instructions.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 General requirements relating to commissioning of project's components and systems, specifying general requirements to PV of components, equipment, sub-systems, systems, and integrated systems.
- .2 Acronyms:
 - .1 AFD - Alternate Forms of Delivery, service provider.
 - .2 BMM - Building Management Manual.
 - .3 Cx - Commissioning.
 - .4 EMCS - Energy Monitoring and Control Systems.
 - .5 O&M - Operation and Maintenance.
 - .6 PI - Product Information.
 - .7 PV - Performance Verification.
 - .8 TAB - Testing, Adjusting and Balancing.

1.2 GENERAL

- .1 Cx is a planned program of tests, procedures and checks carried out systematically on systems and integrated systems of the finished Project. Cx is performed after systems and integrated systems are completely installed, functional and Contractor's Performance Verification responsibilities have been completed and approved. Objectives:
 - .1 Verify installed equipment, systems and integrated systems operate in accordance with contract documents and design criteria and intent.
 - .2 Ensure appropriate documentation is compiled into the BMM.
 - .3 Effectively train O&M staff.
- .2 Contractor assists in Cx process, operating equipment and systems, troubleshooting and making adjustments as required.
 - .1 Systems to be operated at full capacity under various modes to determine if they function correctly and consistently at peak efficiency. Systems to be interactively with each other as intended in accordance with Contract Documents and design criteria.
 - .2 During these checks, adjustments to be made to enhance performance to meet environmental or user requirements.
- .3 Design Criteria: as per client's requirements or determined by designer. To meet Project functional and operational requirements.
- .4 AFD managed projects the term NRC Representative in Cx specifications to be interpreted as AFD Service Provider.

1.3 COMMISSIONING OVERVIEW

- .1 Section 01 91 31 - Commissioning (Cx) Plan.
- .2 For Cx responsibilities refer to Section 01 91 31 - Commissioning (Cx) Plan.
- .3 Cx to be a line item of Contractor's cost breakdown.
- .4 Cx activities supplement field quality and testing procedures described in relevant technical sections.
- .5 Cx is conducted in concert with activities performed during stage of project delivery. Cx identifies issues in Planning and Design stages which are addressed during Construction and Cx stages to ensure the built systems are constructed and proven to operate satisfactorily under weather, environmental and occupancy conditions to meet functional and operational requirements. Cx activities includes transfer of critical knowledge to facility operational personnel.
- .6 NRC Representative will issue Interim Acceptance Certificate when:
 - .1 Completed Cx documentation has been received, reviewed for suitability and approved by NRC Representative.
 - .2 Equipment, components and systems have been commissioned.
 - .3 O&M training has been completed.

1.4 NON-CONFORMANCE TO PERFORMANCE VERIFICATION REQUIREMENTS

- .1 Should equipment, system components, and associated controls be incorrectly installed or malfunction during Cx, correct deficiencies, re-verify equipment and components within the un-functional system, including related systems as deemed required by NRC Representative, to ensure effective performance.
- .2 Costs for corrective work, additional tests, inspections, to determine acceptability and proper performance of such items to be borne by Contractor. Above costs to be in form of progress payment reductions or hold-back assessments.

1.5 PRE-CX REVIEW

- .1 Before Construction:
 - .1 Review contract documents, confirm by writing to NRC Representative.
 - .1 Adequacy of provisions for Cx.
 - .2 Aspects of design and installation pertinent to success of Cx.
- .2 During Construction:
 - .1 Co-ordinate provision, location and installation of provisions for Cx.
- .3 Before start of Cx:
 - .1 Have completed Cx Plan up-to-date.
 - .2 Ensure installation of related components, equipment, sub-systems and systems are complete.
 - .3 Fully understand Cx requirements and procedures.

- .4 Have Cx documentation shelf-ready.
 - .5 Understand completely design criteria and intent and special features.
 - .6 Submit complete start-up documentation to NRC Representative.
 - .7 Have Cx schedules up-to-date.
 - .8 Ensure systems have been cleaned thoroughly.
 - .9 Complete TAB procedures on systems, submit TAB reports to NRC Representative for review and approval.
 - .10 Ensure "As-Built" system schematics are available.
- .4 Inform NRC Representative in writing of discrepancies and deficiencies on finished works.

1.6 CONFLICTS

- .1 Report conflicts between requirements of this section and other sections to NRC Representative before start-up and obtain clarification.
- .2 Failure to report conflict and obtain clarification will result in application of most stringent requirement.

1.7 SUBMITTALS

- .1 Submittals: in accordance with Section 00 10 00 – General Instructions and 01 33 00 - Submittal Procedures.
 - .1 Submit no later than 2 weeks after award of Contract:
 - .1 Name of Contractor's Cx agent.
 - .2 Draft Cx documentation.
 - .3 Preliminary Cx schedule.
 - .2 Request in writing to NRC Representative for changes to submittals and obtain written approval at least 1 week prior to start of Cx.
 - .3 Submit proposed Cx procedures to NRC Representative where not specified and obtain written approval at least 1 week prior to start of Cx.
 - .4 Provide additional documentation relating to Cx process required by NRC Representative.

1.8 COMMISSIONING DOCUMENTATION

- .1 Refer to Section 01 91 33 - Commissioning (Cx) Forms: Installation Check Lists and Product Information (PI) / Performance Verification (PV) Forms for requirements and instructions for use.
- .2 NRC Representative to review and approve Cx documentation.
- .3 Provide completed and approved Cx documentation to NRC Representative.

1.9 COMMISSIONING SCHEDULE

- .1 Provide detailed Cx schedule as part of construction schedule.

- .2 Provide adequate time for Cx activities prescribed in technical sections and commissioning sections including:
 - .1 Approval of Cx reports.
 - .2 Verification of reported results.
 - .3 Repairs, retesting, re-commissioning, re-verification.
 - .4 Training.

1.10 COMMISSIONING MEETINGS

- .1 Convene Cx meetings following project meetings:and as specified herein.
- .2 Purpose: to resolve issues, monitor progress, identify deficiencies, relating to Cx.
- .3 Continue Cx meetings on regular basis until commissioning deliverables have been addressed.
- .4 At 80% construction completion stage. NRC Representative to call a separate Cx scope meeting to review progress, discuss schedule of equipment start-up activities and prepare for Cx. Issues at meeting to include:
 - .1 Review duties and responsibilities of Contractor and subcontractors, addressing delays and potential problems.
 - .2 Determine the degree of involvement of trades and manufacturer's representatives in the commissioning process.
- .5 Thereafter Cx meetings to be held until project completion and as required during equipment start-up and functional testing period.
- .6 Meeting will be chaired by NRC Project Manager, who will record and distribute minutes.
- .7 Ensure subcontractors and relevant manufacturer representatives are present at 60% and subsequent Cx meetings and as required.

1.11 STARTING AND TESTING

- .1 Contractor assumes liabilities and costs for inspections. Including disassembly and re-assembly after approval, starting, testing and adjusting, including supply of testing equipment.

1.12 WITNESSING OF STARTING AND TESTING

- .1 Provide 5 days notice prior to commencement.
- .2 NRC Representative to witness of start-up and testing.
- .3 Contractor's Cx Agent to be present at tests performed and documented by sub-trades, suppliers and equipment manufacturers.

1.13 MANUFACTURER'S INVOLVEMENT

- .1 Factory testing: manufacturer to:

- .1 Coordinate time and location of testing.
 - .2 Provide testing documentation for approval by NRC Representative.
 - .3 Arrange for NRC Representative to witness tests.
 - .4 Obtain written approval of test results and documentation from NRC Representative before delivery to site.
- .2 Obtain manufacturers installation, start-up and operations instructions prior to start-up of components, equipment and systems and review with NRC Representative.
 - .1 Compare completed installation with manufacturer's published data, record discrepancies, and review with manufacturer.
 - .2 Modify procedures detrimental to equipment performance and review same with manufacturer before start-up.
 - .3 Integrity of warranties:
 - .1 Use manufacturer's trained start-up personnel where specified elsewhere in other divisions or required to maintain integrity of warranty.
 - .2 Verify with manufacturer that testing as specified will not void warranties.
 - .4 Qualifications of manufacturer's personnel:
 - .1 Experienced in design, installation and operation of equipment and systems.
 - .2 Ability to interpret test results accurately.
 - .3 To report results in clear, concise, logical manner.

1.14 PROCEDURES

- .1 Verify that equipment and systems are complete, clean, and operating in normal and safe manner prior to conducting start-up, testing and Cx.
- .2 Conduct start-up and testing in following distinct phases:
 - .1 Included in delivery and installation:
 - .1 Verification of conformity to specification, approved shop drawings and completion of PI report forms.
 - .2 Visual inspection of quality of installation.
 - .2 Start-up: follow accepted start-up procedures.
 - .3 Operational testing: document equipment performance.
 - .4 System PV: include repetition of tests after correcting deficiencies.
 - .5 Post-substantial performance verification: to include fine-tuning.
- .3 Correct deficiencies and obtain approval from NRC Representative after distinct phases have been completed and before commencing next phase.
- .4 Document require tests on approved PV forms.

1.15 START-UP DOCUMENTATION

- .1 Assemble start-up documentation and submit to NRC Representative for approval before commencement of commissioning.

- .2 Start-up documentation to include:
 - .1 Factory and on-site test certificates for specified equipment.
 - .2 Pre-start-up inspection reports.
 - .3 Signed installation/start-up check lists.
 - .4 Start-up reports,
 - .5 Step-by-step description of complete start-up procedures, to permit NRC Representative to repeat start-up at any time.

1.16 OPERATION AND MAINTENANCE OF EQUIPMENT AND SYSTEMS

- .1 After start-up, operate and maintain equipment and systems as directed by equipment/system manufacturer.
- .2 With assistance of manufacturer develop written maintenance program and submit NRC Representative for approval before implementation.
- .3 Operate and maintain systems for length of time required for commissioning to be completed.
- .4 After completion of commissioning, operate and maintain systems until issuance of certificate of interim acceptance.

1.17 TEST RESULTS

- .1 If start-up, testing and/or PV produce unacceptable results, repair, replace or repeat specified starting and/or PV procedures until acceptable results are achieved.
- .2 Provide manpower and materials, assume costs for re-commissioning.

1.18 START OF COMMISSIONING

- .1 Notify NRC Representative at least 3 days prior to start of Cx.
- .2 Start Cx after elements of building affecting start-up and performance verification of systems have been completed.

1.19 INSTRUMENTS / EQUIPMENT

- .1 Submit to NRC Representative for review and approval:
 - .1 Complete list of instruments proposed to be used.
 - .2 Listed data including, serial number, current calibration certificate, calibration date, calibration expiry date and calibration accuracy.
- .2 Provide the following equipment as required:
 - .1 2-way radios.
 - .2 Ladders.
 - .3 Equipment as required to complete work.

1.20 COMMISSIONING PERFORMANCE VERIFICATION

- .1 Carry out Cx:
 - .1 Under [actual] [accepted simulated] operating conditions, over entire operating range, in all modes.
 - .2 On independent systems and interacting systems.
- .2 Cx procedures to be repeatable and reported results are to be verifiable.
- .3 Follow equipment manufacturer's operating instructions.
- .4 EMCS trending to be available as supporting documentation for performance verification.

1.21 WITNESSING COMMISSIONING

- .1 NRC Representative to witness activities and verify results.

1.22 AUTHORITIES HAVING JURISDICTION

- .1 Where specified start-up, testing or commissioning procedures duplicate verification requirements of authority having jurisdiction, arrange for authority to witness procedures so as to avoid duplication of tests and to facilitate expedient acceptance of facility.
- .2 Obtain certificates of approval, acceptance and compliance with rules and regulation of authority having jurisdiction.
- .3 Provide copies to NRC Representative within 3 days of test and with Cx report.

1.23 COMMISSIONING CONSTRAINTS

- .1 Since access into secure or sensitive areas will be very difficult after occupancy it is necessary to complete Cx of occupancy, weather, and seasonal sensitive equipment and systems in these areas before issuance of the Interim Certificate, using, if necessary, simulated thermal loads.

1.24 EXTRAPOLATION OF RESULTS

- .1 Where Cx of weather, occupancy, or seasonal-sensitive equipment or systems cannot be conducted under near-rated or near-design conditions, extrapolate part-load results to design conditions when approved by NRC Representative in accordance with equipment manufacturer's instructions, using manufacturer's data, with manufacturer's assistance and using approved formulae.

1.25 EXTENT OF VERIFICATION

- .1 Laboratory areas:
 - .1 Provide manpower and instrumentation to verify 100 % of reported results.
- .2 Critical systems:
 - .1 Provide manpower and instrumentation to verify 100 % of reported results.
- .3 Elsewhere:

- .1 Provide manpower and instrumentation to verify 30 % of reported results, unless specified otherwise in other sections.
- .4 Number and location to be at discretion of NRC Representative.
- .5 Conduct tests repeated during verification under same conditions as original tests, using same test equipment, instrumentation.
- .6 Review and repeat commissioning of systems if inconsistencies found in more than 20 % of reported results. Repeat verifications shall be performed in accordance to the following unless otherwise specified.
 - .1 Laboratory areas:
 - .1 Second and subsequent verifications:
 - .1 Provide manpower and instrumentation to verify 100 % of reported results.
 - .2 Critical systems:
 - .1 Second and subsequent verifications:
 - .1 Provide manpower and instrumentation to verify 100 % of reported results.
 - .3 Elsewhere:
 - .1 Second verification:
 - .1 Provide manpower and instrumentation to verify 100 % of all failed tests results.
 - .2 Provide manpower and instrumentation to verify an additional 20% of reported results, locations to be at the discretion of the NRC Representative.
 - .2 Third and subsequent verifications:
 - .1 Provide manpower and instrumentation to verify 100 % of reported results.
 - .7 Perform additional commissioning until results are acceptable to NRC Representative.

1.26 REPEAT VERIFICATIONS

- .1 Assume costs incurred by NRC Representative for third and subsequent verifications where:
 - .1 Verification of reported results fail to receive NRC Representative's approval.
 - .2 Repetition of second verification again fails to receive approval.
 - .3 NRC Representative deems Contractor's request for second verification was premature.

1.27 SUNDRY CHECKS AND ADJUSTMENTS

- .1 Make adjustments and changes which become apparent as Cx proceeds.
- .2 Perform static and operational checks as applicable and as required.

1.28 DEFICIENCIES, FAULTS, DEFECTS

- .1 Correct deficiencies found during start-up and Cx to satisfaction of NRC Representative.

- .2 Report problems, faults or defects affecting Cx to NRC Representative in writing. Stop Cx until problems are rectified. Proceed with written approval from NRC Representative.

1.29 COMPLETION OF COMMISSIONING

- .1 Upon completion of Cx leave systems in normal operating mode.
- .2 Except for warranty and seasonal verification activities specified in Cx specifications, complete Cx prior to issuance of Interim Certificate of Completion.
- .3 Cx to be considered complete when contract Cx deliverables have been submitted and accepted by NRC Representative.

1.30 ACTIVITIES UPON COMPLETION OF COMMISSIONING

- .1 When changes are made to baseline components or system settings established during Cx process, provide updated Cx form for affected item.

1.31 TRAINING

- .1 In accordance with Section 01 91 41 - Commissioning (Cx) - Training.

1.32 MAINTENANCE MATERIALS, SPARE PARTS, SPECIAL TOOLS

- .1 Supply, deliver, and document maintenance materials, spare parts, and special tools as specified in contract.

1.33 OCCUPANCY

- .1 Cooperate fully with NRC Representative during stages of acceptance and occupancy of facility.

1.34 INSTALLED INSTRUMENTATION

- .1 Use instruments installed under Contract for TAB and PV if:
 - .1 Accuracy complies with these specifications.
 - .2 Calibration certificates have been deposited with NRC Representative.
- .2 Calibrated EMCS sensors may be used to obtain performance data provided that sensor calibration has been completed and accepted.

1.35 PERFORMANCE VERIFICATION TOLERANCES

- .1 Application tolerances:
 - .1 Specified range of acceptable deviations of measured values from specified values or specified design criteria. Except for special areas, to be within +/- 10% of specified values.
- .2 Instrument accuracy tolerances:
 - .1 To be of higher order of magnitude than equipment or system being tested.
- .3 Measurement tolerances during verification:

.1 Unless otherwise specified actual values to be within +/- 2% of recorded values.

1.36 OWNER'S PERFORMANCE TESTING

.1 Performance testing of equipment or system by [Departmental Representative] [Engineer] [Consultant] [____] will not relieve Contractor from compliance with specified start-up and testing procedures.

Part 2 Products

2.1 NOT USED

.1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Description of overall structure of Cx Plan and roles and responsibilities of Cx team.
- .2 Related Sections:
 - .1 Section 00 10 00 – General Instructions.

1.2 REFERENCES

- .1 American Water Works Association (AWWA)
- .2 National Fire Protection Association (NFPA)
 - .1 NFPA-13, Installation of Sprinkler Systems Handbook.
 - .2 NFPA-14, Automatic Sprinkler Systems Handbook.
 - .3 NFPA-20, Standard for the Installation of Stationary Fire Pumps for Fire Protection.
- .3 Public Works and Government Services Canada (PWGSC)
 - .1 PWGSC - Commissioning Guidelines CP.4 -3rd edition-[03].
- .4 Underwriters' Laboratories of Canada (ULC)

1.3 GENERAL

- .1 Provide fully functional systems:
 - .1 Systems, equipment and components meet user's functional requirements before date of acceptance, and operate consistently at peak efficiencies and within specified energy budgets under normal loads.
 - .2 O&M personnel have been fully trained in aspects of installed systems.
 - .3 Optimized life cycle costs.
 - .4 Complete documentation relating to installed equipment and systems.
- .2 Term "Cx" in this section means "Commissioning".
- .3 Use this Cx Plan as master planning document for Cx:
 - .1 Outlines organization, scheduling, allocation of resources, documentation, pertaining to implementation of Cx.
 - .2 Communicates responsibilities of team members involved in Cx Scheduling, documentation requirements, and verification procedures.
 - .3 Sets out deliverables relating to O&M, process and administration of Cx.
 - .4 Describes process of verification of how built works meet [Owner/Investor's] [design] requirements.

- .5 Produces a complete functional system prior to issuance of Certificate of Occupancy.
- .6 Management tool that sets out scope, standards, roles and responsibilities, expectations, deliverables, and provides:
 - .1 Overview of Cx.
 - .2 General description of elements that make up Cx Plan.
 - .3 Process and methodology for successful Cx.
- .4 Acronyms:
 - .1 Cx - Commissioning.
 - .2 BMM - Building Management Manual.
 - .3 EMCS - Energy Monitoring and Control Systems.
 - .4 MSDS - Material Safety Data Sheets.
 - .5 PI - Product Information.
 - .6 PV - Performance Verification.
 - .7 TAB - Testing, Adjusting and Balancing.
 - .8 WHMIS - Workplace Hazardous Materials Information System.
- .5 Commissioning terms used in this Section:
 - .1 Bumping: short term start-up to prove ability to start and prove correct rotation.
 - .2 Deferred Cx - Cx activities delayed for reasons beyond Contractor's control due to lack of occupancy, weather conditions, need for heating/cooling loads.

1.4 DEVELOPMENT OF 100% CX PLAN

- .1 Cx Plan to be 95% completed before added into Project Specifications.
- .2 Cx Plan to be 100% completed within 2 weeks of award of contract to take into account:
 - .1 Approved shop drawings and product data.
 - .2 Approved changes to contract.
 - .3 Contractor's project schedule.
 - .4 Cx schedule.
 - .5 Contractor's, sub-contractor's, suppliers' requirements.
 - .6 Project construction team's and Cx team's requirements.
- .3 Submit completed Cx Plan to NRC Representative and obtain written approval.

1.5 REFINEMENT OF CX PLAN

- .1 During construction phase, revise, refine and update Cx Plan to include:
 - .1 Changes resulting from Client program modifications.
 - .2 Approved design and construction changes.
- .2 Revise, refine and update every week during construction phase. At each revision, indicate revision number and date.
- .3 Submit each revised Cx Plan to NRC Representative for review and obtain written approval.

- .4 Include testing parameters at full range of operating conditions and check responses of equipment and systems.

1.6 COMPOSITION, ROLES AND RESPONSIBILITIES OF CX TEAM

- .1 NRC Representative to maintain overall responsibility for project and is sole point of contact between members of commissioning team.
- .2 Project Manager will select Cx Team consisting of following members:
 - .1 PWGSC Design Quality Review Team: during construction, will conduct periodic site reviews to observe general progress.
 - .2 PWGSC Quality Assurance Commissioning Manager: ensures Cx activities are carried out to ensure delivery of a fully operational project including:
 - .1 Review of Cx documentation from operational perspective.
 - .2 Review for performance, reliability, durability of operation, accessibility, maintainability, operational efficiency under conditions of operation.
 - .3 Protection of health, safety and comfort of occupants and O&M personnel.
 - .4 Monitoring of Cx activities, training, development of Cx documentation.
 - .5 Work closely with members of Cx Team.
 - .3 NRC Representative is responsible for:
 - .1 Organizing Cx.
 - .2 Monitoring operations Cx activities.
 - .3 Witnessing, certifying accuracy of reported results.
 - .4 Witnessing and certifying TAB and other tests.
 - .5 Developing BMM.
 - .6 Ensuring implementation of final Cx Plan.
 - .7 Performing verification of performance of installed systems and equipment.
 - .8 Implementation of Training Plan.
 - .4 Construction Team: contractor, sub-contractors, suppliers and support disciplines, is responsible for construction/installation in accordance with contract documents, including:
 - .1 Testing.
 - .2 TAB.
 - .3 Performance of Cx activities.
 - .4 Delivery of training and Cx documentation.
 - .5 Assigning one person as point of contact with Consultant and PWGSC Cx Manager for administrative and coordination purposes.
 - .5 Contractor's Cx agent implements specified Cx activities including:
 - .1 Demonstrations.
 - .2 Training.
 - .3 Testing.
 - .4 Preparation, submission of test reports.
 - .6 Property Manager: represents lead role in Operation Phase and onwards and is responsible for:

- .1 Receiving facility.
- .2 Day-To-Day operation and maintenance of facility.

1.7 CX PARTICIPANTS

- .1 Employ the following Cx participants to verify performance of equipment and systems:
 - .1 Installation contractor/subcontractor:
 - .1 Equipment and systems except as noted.
 - .2 Equipment manufacturer: equipment specified to be installed and started by manufacturer.
 - .1 To include performance verification.
 - .3 Specialist subcontractor: equipment and systems supplied and installed by specialist subcontractor.
 - .4 Specialist Cx agency:
 - .1 Possessing specialist qualifications and installations providing environments essential to client's program but are outside scope or expertise of Cx specialists on this project.
 - .5 Client: responsible for intrusion and access security systems.
 - .6 Ensure that Cx participant:
 - .1 Could complete work within scheduled time frame.
 - .2 Available for emergency and troubleshooting service during first year of occupancy by user for adjustments and modifications outside responsibility of O&M personnel, including:
 - .1 Modify ventilation rates to meet changes in off-gassing.
 - .2 Changes to heating or cooling loads beyond scope of EMCS.
 - .3 Changes to EMCS control strategies beyond level of training provided to O&M personnel.
 - .4 Redistribution of electrical services.
 - .5 Modifications of fire alarm systems.
 - .6 Modifications to voice communications systems.
 - .7 Provide names of participants to NRC Representative and details of instruments and procedures to be followed for Cx 1 week prior to starting date of Cx for review and approval.

1.8 EXTENT OF CX

- .1 Commission mechanical systems and associated equipment:
 - .1 HVAC and exhaust systems:
 - .1 HVAC systems.

1.9 DELIVERABLES RELATING TO O&M PERSPECTIVES

- .1 General requirements:

- .1 Compile English and French documentation.
- .2 Documentation to be computer-compatible format ready for inputting for data management.
- .2 Provide deliverables:
 - .1 Warranties.
 - .2 Project record documentation.
 - .3 Inventory of spare parts, special tools and maintenance materials.
 - .4 Maintenance Management System (MMS) identification system used.
 - .5 WHMIS information.
 - .6 MSDS data sheets.
 - .7 Electrical Panel inventory containing detailed inventory of electrical circuitry for each panel board. Duplicate of inventory inside each panel.

1.10 DELIVERABLES RELATING TO THE CX PROCESS

- .1 General:
 - .1 Start-up, testing and Cx requirements, conditions for acceptance and specifications form part of relevant technical sections of these specifications.
- .2 Definitions:
 - .1 Cx as used in this section includes:
 - .1 Cx of components, equipment, systems, subsystems, and integrated systems.
 - .2 Factory inspections and performance verification tests.
- .3 Deliverables: provide:
 - .1 Cx Specifications.
 - .2 Startup, pre-Cx activities and documentation for systems, and equipment.
 - .3 Completed installation checklists (ICL).
 - .4 Completed product information (PI) report forms.
 - .5 Completed performance verification (PV) report forms.
 - .6 Results of Performance Verification Tests and Inspections.
 - .7 Description of Cx activities and documentation.
 - .8 Description of Cx of integrated systems and documentation.
 - .9 Tests performed by Contractor.
 - .10 Training Plans.
 - .11 Cx Reports.
 - .12 Prescribed activities during warranty period.
- .4 Contractor to witness and certify tests and reports of results provided to NRC Representative.
- .5 NRC Representative to participate.

1.11 PRE-CX ACTIVITIES AND RELATED DOCUMENTATION

- .1 Items listed in this Cx Plan include the following:
 - .1 Contractor to use approved check lists.
 - .2 Include completed documentation with Cx report.
 - .3 Conduct pre-start-up tests: conduct pressure, static, flushing, cleaning, and "bumping" during construction as specified in technical sections. To be witnessed and certified by NRC Representative and does not form part of Cx specifications.
 - .4 NRC Representative will monitor some of these inspections and tests.
 - .5 Include completed documentation in Cx report.
- .2 Pre-Cx activities - MECHANICAL:
 - .1 HVAC equipment and systems:
 - .1 "Bump" each item of equipment in its "stand-alone" mode.
 - .2 At this time, complete pre-start-up checks and complete relevant documentation.
 - .3 After equipment has been started, test related systems in conjunction with control systems on a system-by-system basis.
 - .4 Perform TAB on systems. TAB reports to be approved by NRC Representative.

1.12 START-UP

- .1 Start up components, equipment and systems.
- .2 NRC Representative to monitor some of these start-up activities.
 - .1 Rectify start-up deficiencies to satisfaction of NRC Representative.
- .3 Performance Verification (PV):
 - .1 Approved Cx Agent to perform.
 - .1 Repeat when necessary until results are acceptable to NRC Representative.
 - .2 Use procedures modified generic procedures to suit project requirements.
 - .3 NRC Representative to witness and certify reported results using approved PI and PV forms.
 - .4 Contractor to completed PV reports and provide to NRC Representative.
 - .5 NRC Representative reserves right to verify up to 30% of reported results at random.
 - .6 Failure of randomly selected item shall result in rejection of PV report or report of system startup and testing.

1.13 CX ACTIVITIES AND RELATED DOCUMENTATION

- .1 Perform Cx using procedures developed by and approved by NRC Representative.
- .2 NRC Representative to monitor Cx activities.
- .3 Upon satisfactory completion, Cx agency performing tests to prepare Cx Report using approved PV forms.

- .4 NRC Representative to witness, certify reported results of, Cx activities and forward to Project Manager.
- .5 NRC Representative reserves right to verify a percentage of reported results at no cost to contract.

1.14 CX OF INTEGRATED SYSTEMS AND RELATED DOCUMENTATION

- .1 Cx to be performed by contractor, using procedures developed and approved by NRC Representative.
- .2 Tests to be witnessed by NRC Representative and documented on approved report forms.
- .3 NRC Representative reserves right to verify percentage of reported results.
- .4 Integrated systems to include:
 - .1 HVAC and associated systems forming part of integrated HVAC systems.

1.15 INSTALLATION CHECK LISTS (ICL)

- .1 Refer to Section 01 91 33 - Commissioning (Cx) Forms: Installation Check Lists and Product Information (PI) / Performance Verification (PV) Forms.

1.16 PRODUCT INFORMATION (PI) REPORT FORMS

- .1 Refer to Section 01 91 33 - Commissioning (Cx) Forms: Installation Check Lists and Product Information (PI) / Performance Verification (PV) Forms.

1.17 PERFORMANCE VERIFICATION (PV) REPORT

- .1 Refer to Section 01 91 33 - Commissioning (Cx) Forms: Installation Check Lists and Product Information (PI) / Performance Verification (PV) Forms.

1.18 DELIVERABLES RELATING TO ADMINISTRATION OF CX

- .1 General:
 - .1 Because of risk assessment, complete Cx of occupancy, weather and seasonal-sensitive equipment and systems in these areas before building is occupied.

1.19 CX SCHEDULES

- .1 Prepare detailed Cx Schedule and submit to NRC Representative for review and approval same time as project Construction Schedule. Include:
 - .1 Milestones, testing, documentation, training and Cx activities of components, equipment, subsystems, systems and integrated systems, including:
 - .1 Design criteria, design intents.
 - .2 Submission of list of instrumentation with relevant certificates: 21 days before start of Cx.
 - .3 Notification of intention to start TAB: 5 days before start of TAB.

- .4 TAB: after successful start-up, correction of deficiencies and verification of normal and safe operation.
- .5 Notification of intention to start Cx: 3 days before start of Cx.
- .6 Notification of intention to start Cx of integrated systems: after Cx of related systems is completed 3 days before start of integrated system Cx.
- .7 Identification of deferred Cx.
- .8 Implementation of training plans.
- .9 Cx reports: immediately upon successful completion of Cx.
- .2 Detailed training schedule to demonstrate no conflicts with testing, completion of project and hand-over to NRC Representative.
- .2 After approval, incorporate Cx Schedule into Construction Schedule.
- .3 Consultant, Contractor, Contractor's Cx agent, and NRC Representative will monitor progress of Cx against this schedule.

1.20 CX REPORTS

- .1 Submit reports of tests, witnessed and certified by Departmental Representative to mechanical designer who will verify reported results.
- .2 Include completed and certified PV reports in properly formatted Cx Reports.
- .3 Before reports are accepted, reported results to be subject to verification by NRC Representative.

1.21 ACTIVITIES DURING WARRANTY PERIOD

- .1 Cx activities must be completed before issuance of Interim Certificate, it is anticipated that certain Cx activities may be necessary during Warranty Period, including:
 - .1 Fine tuning of HVAC systems.
 - .2 Adjustment of ventilation rates to promote good indoor air quality and reduce deleterious effects of VOCs generated by off-gassing from construction materials and furnishings.
 - .3 Full-scale emergency evacuation exercises.

1.22 TESTS TO BE PERFORMED BY OWNER/USER

- .1 None is anticipated on this project.

1.23 TRAINING PLANS

- .1 Refer to Section 01 91 41 - Commissioning (Cx) - Training.

1.24 FINAL SETTINGS

- .1 Upon completion of Cx to satisfaction of NRC Representative lock control devices in their final positions, indelibly mark settings marked and include in Cx Reports.

Part 2 Products

2.1 NOT USED

.1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Commissioning forms to be completed for equipment, system and integrated system.
- .2 Related Sections:
 - .1 Section 00 10 00 – General Instructions.

1.2 INSTALLATION/START-UP CHECK LISTS

- .1 Include the following data:
 - .1 Product manufacturer's installation instructions and recommended checks.
 - .2 Special procedures as specified in relevant technical sections.
 - .3 Items considered good installation and engineering industry practices deemed appropriate for proper and efficient operation.
- .2 Equipment manufacturer's installation/start-up check lists are acceptable for use. As deemed necessary by NRC Representative supplemental additional data lists will be required for specific project conditions.
- .3 Use check lists for equipment installation. Document check list verifying checks have been made, indicate deficiencies and corrective action taken.
- .4 Installer to sign check lists upon completion, certifying stated checks and inspections have been performed. Return completed check lists to NRC Representative. Check lists will be required during Commissioning and will be included in Building Maintenance Manual (BMM) at completion of project.
- .5 Use of check lists will not be considered part of commissioning process but will be stringently used for equipment pre-start and start-up procedures.

1.3 PRODUCT INFORMATION (PI) REPORT FORMS

- .1 Product Information (PI) forms compiles gathered data on items of equipment produced by equipment manufacturer, includes nameplate information, parts list, operating instructions, maintenance guidelines and pertinent technical data and recommended checks that is necessary to prepare for start-up and functional testing and used during operation and maintenance of equipment. This documentation is included in the BMM at completion of work.
- .2 Prior to Performance Verification (PV) of systems complete items on PI forms related to systems and obtain NRC Representative's approval.

1.4 PERFORMANCE VERIFICATION (PV) FORMS

- .1 PV forms to be used for checks, running dynamic tests and adjustments carried out on equipment and systems to ensure correct operation, efficiently and function independently and interactively with other systems as intended with project requirements.
- .2 PV report forms include those developed by Contractor records measured data and readings taken during functional testing and Performance Verification procedures.
- .3 Prior to PV of integrated system, complete PV forms of related systems and obtain NRC Representative's approval.

1.5 SAMPLES OF COMMISSIONING FORMS

- .1 NRC Representative will develop and provide to Contractor required project-specific Commissioning forms in electronic format complete with specification data.
- .2 Revise items on Commissioning forms to suit project requirements.
- .3 Samples of Commissioning forms and a complete index of produced to date will be attached to this section.

1.6 CHANGES AND DEVELOPMENT OF NEW REPORT FORMS

- .1 When additional forms are required, but are not available from NRC Representative develop appropriate verification forms and submit to NRC Representative for approval prior to use.
 - .1 Additional commissioning forms to be in same format as provided by NRC Representative.

1.7 COMMISSIONING FORMS

- .1 Use Commissioning forms to verify installation and record performance when starting equipment and systems.
- .2 Strategy for Use:
 - .1 NRC Representative provides Contractor project-specific Commissioning forms with Specification data included.
 - .2 Contractor will provide required shop drawings information and verify correct installation and operation of items indicated on these forms.
 - .3 Confirm operation as per design criteria and intent.
 - .4 Identify variances between design and operation and reasons for variances.
 - .5 Verify operation in specified normal and emergency modes and under specified load conditions.
 - .6 Record analytical and substantiating data.
 - .7 Verify reported results.
 - .8 Form to bear signatures of recording technician and reviewed and signed off by NRC Representative.
 - .9 Submit immediately after tests are performed.
 - .10 Reported results in true measured SI unit values.

- .11 Provide NRC Representative with originals of completed forms.
- .12 Maintain copy on site during start-up, testing and commissioning period.
- .13 Forms to be both hard copy and electronic format with typed written results in Building Management Manual in accordance with Section 00 10 00 – General Instructions.

1.8 LANGUAGE

- .1 To suit the language profile of the awarded contract.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 This Section specifies roles and responsibilities of Commissioning Training.
- .2 Related Sections:
 - .1 Section 00 10 00 – General Instructions.

1.2 TRAINEES

- .1 Trainees: personnel selected for operating and maintaining this facility. Includes [Property] [Facility] Manager, building operators, maintenance staff, security staff, and technical specialists as required.
- .2 Trainees will be available for training during later stages of construction for purposes of familiarization with systems.

1.3 INSTRUCTORS

- .1 NRC Representative will provide:
 - .1 Descriptions of systems.
 - .2 Instruction on design philosophy, design criteria, and design intent.
- .2 Contractor and certified factory-trained manufacturers' personnel: to provide instruction on the following:
 - .1 Start-Up, operation, shut-down of equipment, components and systems.
 - .2 Control features, reasons for, results of, implications on associated systems of, adjustment of set points of control and safety devices.
 - .3 Instructions on servicing, maintenance and adjustment of systems, equipment and components.
- .3 Contractor and equipment manufacturer to provide instruction on:
 - .1 Start-up, operation, maintenance and shut-down of equipment they have certified installation, started up and carried out PV tests.

1.4 TRAINING OBJECTIVES

- .1 Training to be detailed and duration to ensure:
 - .1 Safe, reliable, cost-effective, energy-efficient operation of systems in normal and emergency modes under all conditions.
 - .2 Effective on-going inspection, measurements of system performance.
 - .3 Proper preventive maintenance, diagnosis and trouble-shooting.
 - .4 Ability to update documentation.
 - .5 Ability to operate equipment and systems under emergency conditions until appropriate qualified assistance arrives.

1.5 TRAINING MATERIALS

- .1 Instructors to be responsible for content and quality.
- .2 Training materials to include:
 - .1 "As-Built" Contract Documents.
 - .2 Operating Manual.
 - .3 Maintenance Manual.
 - .4 Management Manual.
 - .5 TAB and PV Reports.
- .3 Project Manager, Commissioning Manager and [Facility] [Property] Manager will review training manuals.
- .4 Training materials to be in a format that permits future training procedures to same degree of detail.
- .5 Supplement training materials:
 - .1 Transparencies for overhead projectors.
 - .2 Multimedia presentations.
 - .3 Manufacturer's training videos.
 - .4 Equipment models.

1.6 SCHEDULING

- .1 Include in Commissioning Schedule time for training.
- .2 Deliver training during regular working hours, training sessions to be up to 3 hours in length.
- .3 Training to be completed prior to acceptance of facility.

1.7 RESPONSIBILITIES

- .1 Be responsible for:
 - .1 Implementation of training activities,
 - .2 Coordination among instructors,
 - .3 Quality of training, training materials,
- .2 NRC Representative will evaluate training and materials.
- .3 Upon completion of training, provide written report, signed by Instructors, witnessed by NRC Representative

1.8 TRAINING CONTENT

- .1 Training to include demonstrations by Instructors using the installed equipment and systems.
- .2 Content includes:
 - .1 Review of facility and occupancy profile.

- .2 Functional requirements.
 - .3 System philosophy, limitations of systems and emergency procedures.
 - .4 Review of system layout, equipment, components and controls.
 - .5 Equipment and system start-up, operation, monitoring, servicing, maintenance and shut-down procedures.
 - .6 System operating sequences, including step-by-step directions for starting up, shut-down, operation of valves, dampers, switches, adjustment of control settings and emergency procedures.
 - .7 Maintenance and servicing.
 - .8 Trouble-shooting diagnosis.
 - .9 Inter-Action among systems during integrated operation.
 - .10 Review of O&M documentation.
- .3 Provide specialized training as specified in relevant Technical Sections of the construction specifications.

1.9 VIDEO-BASED TRAINING

- .1 Manufacturer's videotapes to be used as training tool with NRC Representative's review and written approval 1 month prior to commencement of scheduled training.
- .2 On-Site training videos:
 - .1 Videotape training sessions for use during future training.
 - .2 To be performed after systems are fully commissioned.
 - .3 Organize into several short modules to permit incorporation of changes.
- .3 Production methods to be high quality.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 This Section includes requirements for careful removal and salvage, and reconditioning of building components identified for storage at a designated remote site, for storage on site, and subsequent reinstallation forming a part of Project ready for re use at a later date.

1.2 RELATED REQUIREMENTS

- .1 Section 01 10 00 – General Instructions
- .2 Section 01 74 19 – Waste Management and Disposal
- .3 Section 22 05 05 - Selective Demolition for Plumbing
- .4 Section 23 05 05 - Selective Demolition for HVAC

1.3 DEFINITIONS

- .1 Remove and Salvage: Detach items from existing construction and deliver them ready for reuse.
- .2 Remove and Reinstall: Detach items from existing construction, prepare them for reuse, and reinstall them where indicated.

1.4 ADMINISTRATIVE REQUIREMENTS

- .1 Coordination Existing Salvaged Work: Coordinate with Departmental Representative for confirmation of materials, components, and items of equipment identified for removal and salvage from their present existing locations and as follows:
 - .1 Items that are turned over to Departmental Representative.
 - .2 Off-site or on-site storage locations.
 - .3 Confirmation of items that are renovated or refurbished ready for reinstallation as a part of Work.
 - .4 Confirmation of items that Departmental Representative will not re use, but will retain as follows:
 - .1 Contractor is responsible for loading and handling identified salvaged items using their own forces and equipment.

Part 2 Products

2.1 SALVAGED ITEMS

.1 Items salvaged by Contractor include, but are not limited to:

Work	Deliver To
Diversion of miscellaneous office furniture from landfill through re-use/donation or recycling facilities (ie. metal filing cabinets and shelving, office desks and chairs, demountable panel partition systems, window blinds, wood cabinets, etc.)	Off-site applicable re-use or recycling facility
Lighting fixtures for salvage and re-installation	Departmental Representative approved storage location on-site for future re-installation
Diversion of miscellaneous metal mechanical equipment from landfill to appropriate recycling facility (ie. fan coil units, domestic cold water drinking fountains, mechanical piping (sprinkler, plumbing and chilled water), sheet metal ductwork and accessories, etc.)	Off-site applicable recycling facility
Carpet reclamation	Departmental Representative approved storage location on-site for future re-installation
Diversion of miscellaneous metal electrical conduits and wiring from landfill through recycling	Off-site applicable recycling facility
Diversion of architectural elements from landfill through re-use/donation to appropriate recycling facility (ie. ceiling grids, metal blinds, metal studs, doors and associated hardware, glazing, etc.)	Off-site applicable re-use or recycling facility
Diversion of miscellaneous packaging materials and cardboard from landfill through recycling facilities (ie. plastic wrap, cardboard, wood pallets, etc.)	Off-site applicable re-use or recycle facility

.2 Confirm with Departmental Representative additional items that appear salvageable prior to disposal.

Part 3 Execution

3.1 SALVAGE

- .1 Remove and handle salvageable items from site to minimize damage and to ensure that usability is maintained.
- .2 Clean, decontaminate, or remediate hazardous substances (lead based paint, asbestos dust, PCB residue, and similar substances) from salvaged materials so they are safe for reuse or resale.

- .3 Place materials on pallets or wrap in protective film to ensure that loose pieces and projections do not cause injury to personnel, and that salvaged items remain as complete units.
- .4 Clean items of construction or building debris, or materials that are not a part of salvaged work before delivering to Departmental Representative.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 This Section includes requirements for selective demolition and removal of plumbing, sprinkler systems and related mechanical components and incidentals required to complete work described in this Section ready for new construction.

1.2 RELATED REQUIREMENTS

- .1 Section 01 10 00 – General Instructions
- .2 Section 01 74 19 – Waste Management and Disposal
- .3 Section 23 05 05.01 – Selective Demolition for HVAC-R Equipment

1.3 REFERENCE STANDARDS

- .1 CSA Group (CSA)
 - .1 CSA S350 M1980 (R2003), Code of Practice for Safety in Demolition of Structures.

1.4 DEFINITIONS

- .1 Demolish: Detach items from existing construction and legally dispose of items off site, unless indicated as removed and salvaged, or removed and reinstalled.
- .2 Remove: Planned deconstruction and disassembly of electrical items from existing construction including removal of conduit, junction boxes, cabling and wiring from electrical component to panel taking care not to damage adjacent assemblies designated to remain; legally dispose of items off site, unless indicated as removed and salvaged, or removed and reinstalled.
- .3 Remove and Salvage: Detach items from existing construction and deliver them to Departmental Representative ready for reuse.
- .4 Remove and Reinstall: Detach items from existing construction, prepare them for reuse, and reinstall them where indicated.
- .5 Existing to Remain: Existing items of construction that are not removed and that are not otherwise indicated as being removed and salvaged, or removed and reinstalled.
- .6 Hazardous Substances: Dangerous substances, dangerous goods, hazardous commodities and hazardous products may include asbestos, mercury and lead, PCB's, poisons, corrosive agents, flammable substances, radioactive substances, or other material that can endanger human health or wellbeing or environment if handled improperly as defined by the Federal Hazardous Products Act (RSC 1985) including latest amendments.

1.5 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Action Submittals: Provide the following in accordance with Section 01 10 00 – General Instructions before starting work of this Section:

- .1 Construction Waste Management Plan (CWM Plan): Submit plan addressing opportunities for reduction, reuse, or recycling of materials prepared in accordance with Section 01 74 19 - Waste Management and Disposal.
- .2 Landfill Records: Indicate receipt and acceptance of selective demolition waste and hazardous wastes by a landfill facility licensed to accept hazardous wastes.

1.6 ADMINISTRATIVE REQUIREMENTS

- .1 Coordination: Coordinate work of this Section to avoid interference with work by other Sections.
- .2 Scheduling: Account for Departmental Representative's continued occupancy requirements during selective demolition with Section 02 41 19.16 - Selective Interior Demolition.

1.7 QUALITY ASSURANCE

- .1 Regulatory Requirements: Perform work of this Section in accordance with the following:
 - .1 Federal Workers' Compensation Service.
 - .2 Government of Canada, Labour Program: Workplace Safety.

1.8 SITE CONDITIONS

- .1 Existing Conditions: Condition of materials identified as being salvaged or demolished are based on their observed condition at time of site examination before tendering.
- .2 Discovery of Hazardous Substances: It is not expected that Hazardous Substances will be encountered in the Work; immediately notify Departmental Representative if materials suspected of containing hazardous substances are encountered and perform the following activities:
 - .1 Refer to Section 01 10 00 – General Instructions for directives associated with specific material types.
 - .2 Hazardous substances will be as defined in the Hazardous Products Act.
 - .3 Stop work in the area of the suspected hazardous substances.
 - .4 Take preventative measures to limit users' and workers' exposure, provide barriers and other safety devices and do not disturb.
 - .5 Hazardous substances will be removed by Departmental Representative under a separate contract or as a change to the Work.
 - .6 Proceed only after written instructions have been received from Departmental Representative.

1.9 SALVAGE AND DEBRIS MATERIALS

- .1 Demolished items become Contractor's property and will be removed from Project site; except for items indicated as being reused, salvaged, or otherwise indicated to remain Departmental Representative's property.
- .2 Carefully remove materials and items designated for salvage and store in a manner to prevent damage or devaluation of materials in accordance with Section 02 42 00 - Removal and Salvage of Construction Materials.

Part 2 Products

2.1 MATERIALS

- .1 General Patching and Repair Materials: Refer to Section 02 41 19.16 - Selective Interior Demolition for listing of patching and repair materials incidental to removal or demolition of components associated with work of this Section.
- .2 Plumbing Repair Materials: Use only new materials required for completion or repair matching materials damaged during performance of work of this Section; new materials are required to meet assembly or system characteristics as existing systems indicated to remain and carry CSA approval labels required by the Authority Having Jurisdiction.
- .3 Fire stopping Repair Materials: Use fire stopping materials compatible with existing fire stopping systems where removal or demolition work affects rated assemblies, restore to match existing fire rated performance.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Existing Conditions: Visit site, thoroughly examine and become familiar with conditions that may affect the work of this Section before tendering the Bid; Departmental Representative will not consider claims for extras for work or materials necessary for proper execution and completion of the contract that could have been determined by a site visit.

3.2 PREPARATION

- .1 Protection of Existing Systems to Remain: Protect systems and components indicated to remain in place during selective demolition operations and as follows:
 - .1 Prevent movement and install bracing to prevent settlement or damage of adjacent services and parts of existing buildings scheduled to remain.
 - .2 Notify Departmental Representative and cease operations where safety of buildings being demolished, adjacent structures or services appears to be endangered and await additional instructions before resuming demolition work specified in this Section.
 - .3 Prevent debris from blocking drainage inlets.
 - .4 Protect mechanical systems that must remain in operation.
- .2 Protection of Building Occupants: Sequence demolition work so that interference with the use of the building by the Departmental Representative] and users is minimized and as follows:
 - .1 Prevent debris from endangering the safe access to and egress from occupied buildings.
 - .2 Notify Departmental Representative and cease operations where safety of occupants appears to be endangered and await additional instructions before resuming demolition work specified in this Section.

3.3 EXECUTION

- .1 Demolition and Removal: Coordinate requirements of this Section with information contained in Section 02 41 19.16 - Selective Interior Demolition and as follows:

- .1 Disconnect and cap mechanical services in accordance with requirements of local Authority Having Jurisdiction.
- .2 Do not disrupt active or energized utilities without approval of the Departmental Representative.
- .3 Erect and maintain dust proof and weather tight partitions to prevent the spread of dust and fumes to occupied building areas; remove partitions when complete.
- .4 Demolish parts of existing building to accommodate new construction and remedial work as indicated.
- .5 At end of each day's work, leave worksite in safe condition.
- .6 Perform demolition work in a neat and workmanlike manner:
 - .1 Remove any tools or equipment after completion of work, and leave site clean and ready for subsequent renovation work.
 - .2 Repair and restore damages caused as a result of work of this Section to match existing materials and finishes.

3.4 CLOSEOUT ACTIVITIES

- .1 Demolition Waste Disposal: Arrange for legal disposal and remove demolished materials to accredited provincial landfill site or alternative disposal site (recycle centre) except where explicitly noted otherwise for materials being salvaged for re use in new construction in accordance with Section 02 42 00 - Removal and Salvage of Construction Materials.

END OF SECTION

PART 1 - GENERAL

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 93 – Testing, Adjusting and Balancing for HVAC.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 00 10 00 – General Sections.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Indicate on drawings:
 - .1 Mounting arrangements.
 - .2 Operating and maintenance clearances.
 - .2 Shop drawings and product data accompanied by:
 - .1 Detailed drawings of bases, supports, and anchor bolts.
 - .2 Acoustical sound power data, where applicable.
 - .3 Points of operation on performance curves.
 - .4 Manufacturer to certify current model production.
 - .5 Certification of compliance to applicable codes.
 - .3 In addition to transmittal letter referred to in Section 00 10 00 – General Instructions: use MCAC "Shop Drawing Submittal Title Sheet". Identify section and paragraph number.

1.3 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 00 10 00 – General Instructions.
- .2 Operation and Maintenance Data: submit operation and maintenance data for incorporation into manual.
 - .1 Operation and maintenance manual approved by, and final copies deposited with, Departmental Representative before final inspection.
 - .2 Operation data to include:
 - .1 Control schematics for systems including environmental controls.
 - .2 Description of systems and their controls.
 - .3 Description of operation of systems at various loads together with reset schedules and seasonal variances.
 - .4 Operation instruction for systems and component.
 - .5 Description of actions to be taken in event of equipment failure.
 - .6 Valves schedule and flow diagram.
 - .7 Colour coding chart.
 - .3 Maintenance data to include:

- .1 Servicing, maintenance, operation and trouble-shooting instructions for each item of equipment.
- .2 Data to include schedules of tasks, frequency, tools required and task time.
- .4 Performance data to include:
 - .1 Equipment manufacturer's performance datasheets with point of operation as left after commissioning is complete.
 - .2 Equipment performance verification test results.
 - .3 Special performance data as specified.
 - .4 Testing, adjusting and balancing reports as specified in Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.
- .5 Approvals:
 - .1 Submit 2 copies of draft Operation and Maintenance Manual to Departmental Representative for approval. Submission of individual data will not be accepted unless directed by Departmental Representative.
 - .2 Make changes as required and re-submit as directed by Departmental Representative.
- .6 Additional data:
 - .1 Prepare and insert into operation and maintenance manual additional data when need for it becomes apparent during specified demonstrations and instructions.
- .7 Site records:
 - .1 Departmental Representative will provide 1 set of reproducible mechanical drawings. Provide sets of [white] prints as required for each phase of work. Mark changes as work progresses and as changes occur. Include changes to existing mechanical systems, control systems and low voltage control wiring.
 - .2 Transfer information to reproducibles, revising reproducibles to show work as actually installed.
 - .3 Use different colour waterproof ink for each service.
 - .4 Make available for reference purposes and inspection.
- .8 As-built drawings:
 - .1 Prior to start of Testing, Adjusting and Balancing for HVAC, finalize production of as-built drawings.
 - .2 Identify each drawing in lower right hand corner in letters at least 12 mm high as follows: - "AS BUILT DRAWINGS: THIS DRAWING HAS BEEN REVISED TO SHOW MECHANICAL SYSTEMS AS INSTALLED" (Signature of Contractor) (Date).
 - .3 Submit to Departmental Representative for approval and make corrections as directed.
 - .4 Perform testing, adjusting and balancing for HVAC using as-built drawings.
 - .5 Submit completed reproducible as-built drawings with Operating and Maintenance Manuals.
- .9 Submit copies of as-built drawings for inclusion in final TAB report.

1.4 MAINTENANCE MATERIAL SUBMITTALS

- .1 Submit in accordance with Section 00 10 00 – General Instructions.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 00 10 00 – General Instructions and [with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect equipment from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Packaging Waste Management: in accordance with Section 00 10 00 – General Instructions.

PART 2 - PRODUCTS

2.1 NOT USED

- .1 Not used.

PART 3 - EXECUTION

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 PAINTING REPAIRS AND RESTORATION

- .1 Do painting in accordance with generally accepted industry best practices.
- .2 Prime and touch up marred finished paintwork to match original.

- .3 Restore to new condition, finishes which have been damaged.

3.3 SYSTEM CLEANING

- .1 Clean interior and exterior of all systems including strainers.

3.4 FIELD QUALITY CONTROL

- .1 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.

3.5 DEMONSTRATION

- .1 Departmental Representative will use equipment and systems for test purposes prior to acceptance. Supply labour, material, and instruments required for testing.
- .2 Supply tools, equipment and personnel to demonstrate and instruct operating and maintenance personnel in operating, controlling, adjusting, trouble-shooting and servicing of all systems and equipment during regular work hours, prior to acceptance.
- .3 Use operation and maintenance manual, as-built drawings, and audio visual aids as part of instruction materials.
- .4 Instruction duration time requirements as specified in appropriate sections.
- .5 Departmental Representative will record these demonstrations on video tape for future reference.

3.6 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 00 10 00 – General Instructions.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 00 10 00
- .3 Waste Management: in accordance with Section 00 10 00 – General Instructions.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

3.7 PROTECTION

- .1 Protect equipment and systems openings from dirt, dust, and other foreign materials with materials appropriate to system.

END OF SECTION

PART 1 - GENERAL

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 00 – Common Work Results for HVAC.

1.2 REFERENCES

- .1 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-1.181-99, Ready-Mixed Organic Zinc-Rich Coating.
- .2 Green Seal Environmental Standards (GSES)
 - .1 Standard GS-11-2008, 2nd Edition, Environmental Standard for Paints and Coatings.
- .3 National Fire Code of Canada (NFCC 2005)

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 00 10 00 – General Instructions.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature, specifications and datasheets for piping and equipment and include product characteristics, performance criteria, physical size, finish and limitations.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 00 10 00 – General Instructions and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
 - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: in accordance with Section 00 10 00 – General Instructions.

PART 2 - PRODUCTS

2.1 MATERIAL

- .1 Sealants: maximum VOC limit to GSES GS-36.

- .2 Adhesives: maximum VOC limit to GSES GS-36.
- .3 Fire Stopping: refer to drawings

PART 3 - EXECUTION

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 CONNECTIONS TO EQUIPMENT

- .1 In accordance with manufacturer's instructions unless otherwise indicated.
- .2 Use valves and either unions or flanges for isolation and ease of maintenance and assembly.
- .3 Use double swing joints when equipment mounted on vibration isolation and when piping subject to movement.

3.3 CLEARANCES

- .1 Provide clearance around systems, equipment and components for observation of operation, inspection, servicing, maintenance and as recommended by manufacturer and National Fire Code of Canada.
- .2 Provide space for disassembly, removal of equipment and components as recommended by manufacturer and as indicated without interrupting operation of other system, equipment, and components.

3.4 DRAINS

- .1 Install piping with grade in direction of flow except as indicated.
- .2 Install drain valve at low points in piping systems, at equipment and at section isolating valves.
- .3 Pipe each drain valve discharge separately to above floor drain.
 - .1 Discharge to be visible.
- .4 Drain valves: NPS 3/4 gate or globe valves unless indicated otherwise, with hose end male thread, cap and chain.

3.5 AIR VENTS

- .1 Install manual air vents at high points in piping systems.
- .2 Install isolating valve at each automatic air valve.
- .3 Install drain piping to approved location and terminate where discharge is visible.

3.6 DIELECTRIC COUPLINGS

- .1 General: compatible with system, to suit pressure rating of system.
- .2 Locations: where dissimilar metals are joined.
- .3 NPS 2 and under: isolating unions or bronze valves.
- .4 Over NPS 2: isolating flanges.

3.7 PIPEWORK INSTALLATION

- .1 Screwed fittings jointed with Teflon tape.
- .2 Protect openings against entry of foreign material.
- .3 Install to isolate equipment and allow removal without interrupting operation of other equipment or systems.
- .4 Assemble piping using fittings manufactured to ANSI standards.
- .5 Saddle type branch fittings may be used on mains if branch line is no larger than half size of main.
 - .1 Hole saw (or drill) and ream main to maintain full inside diameter of branch line prior to welding saddle.
- .6 Install exposed piping, equipment, rectangular cleanouts and similar items parallel or perpendicular to building lines.
- .7 Install concealed pipework to minimize furring space, maximize headroom, conserve space.
- .8 Slope piping, except where indicated, in direction of flow for positive drainage and venting.
- .9 Install, except where indicated, to permit separate thermal insulation of each pipe.
- .10 Group piping wherever possible.
- .11 Ream pipes, remove scale and other foreign material before assembly.
- .12 Use eccentric reducers at pipe size changes to ensure positive drainage and venting.

- .13 Provide for thermal expansion as indicated.
- .14 Valves:
 - .1 Install in accessible locations.
 - .2 Remove interior parts before soldering.
 - .3 Install with stems above horizontal position unless indicated.
 - .4 Valves accessible for maintenance without removing adjacent piping.
 - .5 Use gate, ball or butterfly valves at branch take-offs for isolating purposes except where specified.
 - .6 Install butterfly valves between weld neck flanges to ensure full compression of liner.
 - .7 Use chain operators on valves NPS 2 1/2 and larger where installed more than 2400 mm above floor in Mechanical Rooms.
- .15 Check Valves:
 - .1 Install silent check valves in vertical pipes with downward flow and as indicated.
 - .2 Install swing check valves in horizontal lines as indicated.

3.8 SLEEVES

- .1 General: install where pipes pass through masonry, concrete structures, fire rated assemblies, and as indicated.
- .2 Material: schedule 40 black steel pipe.
- .3 Construction: use annular fins continuously welded at mid-point at foundation walls and where sleeves extend above finished floors.
- .4 Sizes: 6 mm minimum clearance between sleeve and uninsulated pipe or between sleeve and insulation.
- .5 Installation:
 - .1 Concrete, masonry walls, concrete floors on grade: terminate flush with finished surface.
 - .2 Other floors: terminate 25 mm above finished floor.
 - .3 Before installation, paint exposed exterior surfaces with heavy application of zinc-rich paint to CAN/CGSB-1.181.
- .6 Sealing:
 - .1 Foundation walls and below grade floors: fire retardant, waterproof non-hardening mastic.
 - .2 Elsewhere:
 - .1 Provide space for firestopping.
 - .2 Maintain fire rating integrity.
 - .3 Sleeves installed for future use: fill with lime plaster or other easily removable filler.
 - .4 Ensure no contact between copper pipe or tube and sleeve.

3.9 ESCUTCHEONS

- .1 Install on pipes passing through walls, partitions, floors, and ceilings in finished areas.
- .2 Construction: one piece type with set screws.
 - .1 Chrome or nickel plated brass or type 302 stainless steel.
- .3 Sizes: outside diameter to cover opening or sleeve.
 - .1 Inside diameter to fit around pipe or outside of insulation if so provided.

3.10 PREPARATION FOR FIRE STOPPING

- .1 Install firestopping within annular space between pipes, ducts, insulation and adjacent fire separation in accordance with details on drawings.
- .2 Uninsulated unheated pipes not subject to movement: no special preparation.
- .3 Uninsulated heated pipes subject to movement: wrap with non-combustible smooth material to permit pipe movement without damaging fire stopping material or installation.
- .4 Insulated pipes: ensure integrity of insulation and vapour barriers.

3.11 FLUSHING OUT OF PIPING SYSTEMS

- .1 Before start-up, clean interior of piping systems in accordance with requirements of Section 00 10 00 – General Instructions supplemented as specified in relevant mechanical sections.
- .2 Preparatory to acceptance, clean and refurbish equipment and leave in operating condition, including replacement of filters in piping systems.

3.12 PRESSURE TESTING OF EQUIPMENT AND PIPEWORK

- .1 Advise Departmental Representative 48hours minimum prior to performance of pressure tests.
- .2 Pipework: test as specified in relevant sections of heating, ventilating and air conditioning work.
- .3 Maintain specified test pressure without loss for 4 hours minimum unless specified for longer period of time in relevant mechanical sections.
- .4 Prior to tests, isolate equipment and other parts which are not designed to withstand test pressure or media.
- .5 Conduct tests in presence of Departmental Representative.
- .6 Pay costs for repairs or replacement, retesting, and making good. Departmental Representative to determine whether repair or replacement is appropriate.

- .7 Insulate or conceal work only after approval and certification of tests by Departmental Representative.

3.13 EXISTING SYSTEMS

- .1 Connect into existing piping systems at times approved by Departmental Representative.
- .2 Request written approval by Departmental Representative 10days minimum, prior to commencement of work.
- .3 Be responsible for damage to existing plant by this work.

3.14 CLEANING

- .1 Clean in accordance with Section 00 10 00 – General Instructions.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: in accordance with Section 00 10 00 – General Instructions.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 This Section includes requirements for selective demolition and removal of heating, ventilation, air conditioning systems, refrigerant systems, controls and automated automation components, and related mechanical components and incidentals required to complete work described in this Section to prepare for new construction.

1.2 RELATED SECTIONS

- .1 Section 01 10 00 – General Instructions
- .2 Section 01 74 19 - Waste Management and Disposal
- .3 Section 02 41 19.16 - Selective Interior Demolition
- .4 Section 02 42 00 - Removal and Salvage of Construction Materials
- .5 Section 22 05 05 – Selective Demolition for Plumbing
- .6 Section 26 05 05 – Selective Demolition for Electrical

1.3 REFERENCE STANDARDS

- .1 CSA Group (CSA)
 - .1 CSA S350 M1980 (R2003), Code of Practice for Safety in Demolition of Structures.
- .2 Federal Halocarbon Regulations, 2003 (SOR/2003-289)

1.4 DEFINITIONS

- .1 For purposes of mechanical sections, the following definitions shall apply:
 - .1 Concealed: mechanical services and equipment is suspended ceilings and in chases and furred spaces.
 - .2 Exposed: will mean not concealed as defined above.
 - .3 Demolish: detach items from existing construction and legally dispose of items off site, unless indicated as removed and salvaged, or removed and reinstalled.
 - .4 Remove: planned deconstruction and disassembly of electrical items from existing construction including removal of conduit, junction boxes, cabling and wiring from electrical component to panel taking care not to damage adjacent assemblies designated to remain; legally dispose of items off site, unless indicated as removed and salvaged, or removed and reinstalled.
 - .5 Remove and Salvage: detach items from existing construction and deliver them to Departmental Representative ready for reuse.
 - .6 Remove and Reinstall: detach items from existing construction, prepare them for reuse, and reinstall them where indicated.

- .7 Existing to Remain: existing items of construction that are not removed and that are not otherwise indicated as being removed and salvaged, or removed and reinstalled.
- .8 Hazardous Substances: dangerous substances, dangerous goods, hazardous commodities and hazardous products may include asbestos, mercury and lead, PCB's, poisons, corrosive agents, flammable substances, radioactive substances, or other material that can endanger human health or wellbeing or environment if handled improperly as defined by the Federal Hazardous Products Act (RSC 1985) including latest amendments.

1.5 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: Provide in accordance with Section 01 10 00 – General Instructions, and as outlined in the following:
 - .1 Construction Waste Management Plan (CWM Plan): submit plan addressing opportunities for reduction, reuse, or recycling of materials prepared in accordance with Section 01 74 19 - Waste Management and Disposal.
 - .2 Landfill Records: indicate receipt and acceptance of selective demolition waste and hazardous wastes by a landfill facility licensed to accept hazardous wastes.
 - .3 Halocarbon Service Logs: Contractor shall complete halocarbon service logs and provide copies to Departmental Representative containing all information in accordance with requirements outlined in the Federal Halocarbon Regulation.

1.6 EXAMINATION OF THE SITE

- .1 Carefully examine conditions at the site which will or may affect your work, and become familiar with both the new and existing construction, finishes, and other work associated with your work in order that your tender price includes for everything necessary for completion of your work within the proposed project schedule.

1.7 SALVAGE AND DEBRIS MATERIALS

- .1 Demolished items become property of the Contractor and will be removed from the work site, except items indicated as being reused, salvaged or otherwise indicated to remain in accordance with Section 01 74 19 - Waste Management and Disposal.
- .2 Carefully remove materials and items designated for salvage and store in a manner to prevent damage or devaluation of materials in accordance with Section 02 42 00 – Removal and Salvage of Construction Materials.

Part 2 Products

2.1 MATERIAL

- .1 HVAC Repair Materials: use only new materials required for completion or repair matching materials damaged during performance of work of this Section; new materials are required to meet assembly or system characteristics as existing systems indicated to remain and carry CSA approval labels required by the Authority Having Jurisdiction.

- .2 Fire stopping Repair Materials: use fire stopping materials compatible with existing fire stopping systems where removal or demolition work affects rated assemblies, restore to match existing fire rated performance.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Existing Conditions: visit site, thoroughly examine and become familiar with conditions that may affect the work of this Section before tendering the Bid; Departmental Representative will not consider claims for extras for work or materials necessary for proper execution and completion of the contract that could have been determined by a site visit.

3.2 PREPARATION

- .1 Protection of Existing Systems to Remain: protect systems and components indicated to remain in place during selective demolition operations and as follows:
 - .1 Prevent movement and install bracing to prevent settlement or damage of adjacent services and parts of existing buildings scheduled to remain.
 - .2 Notify Departmental Representative and cease operations where safety of buildings being demolished, adjacent structures or services appears to be endangered and await additional instructions before resuming demolition work specified in this Section.
 - .3 Prevent debris from blocking drainage inlets.
 - .4 Protect mechanical systems that must remain in operation.
- .2 Protection of Building Occupants: sequence demolition work so that interference with the use of the building by the Departmental Representative and users is minimized and as follows:
 - .1 Prevent debris from endangering the safe access to and egress from occupied buildings.
 - .2 Notify Departmental Representative and cease operations where safety of occupants appears to be endangered and await additional instructions before resuming demolition work specified in this Section.

3.3 EXECUTION

- .1 Demolition and Removal: coordinate requirements of this Section as follows:
 - .1 Disconnect and cap gas supply and electrical services in accordance with requirements of local Authority Having Jurisdiction.
 - .2 Do not disrupt active or energized utilities without approval of the Departmental Representative.
 - .3 Erect and maintain dust proof and weather tight partitions to prevent the spread of dust and fumes to occupied building areas; remove partitions when complete.
 - .4 Demolish parts of existing building to accommodate new construction and remedial work as indicated.
 - .5 At end of each day's work, leave worksite in safe condition.

- .6 Perform demolition work in a neat and workmanlike manner:
 - .1 Remove any tools or equipment after completion of work, and leave site clean and ready for subsequent renovation work.
 - .2 Repair and restore damages caused as a result of work of this Section to match existing materials and finishes.
- .2 Halocarbon Requirements: Contractor shall coordinate requirements of this Section as outlined below and in accordance with requirements specified in the Federal Halocarbon Regulation:
 - .1 Contractor shall generate halocarbon service log records for work on equipment (cooling equipment with CFC's, HCFC's and HRC refrigerants; fire suppression systems; solvent cleaning systems) that may result in the release of a halocarbon.
 - .2 Contractor shall generate Decommissioning, Dismantling or Destroying (DDD) Notice containing all information in accordance with requirements outlined in the Federal Halocarbon Regulation for all systems to be decommissioned, dismantled or destroyed as part of work activities.
 - .1 Prior to commencement of DDD activities Contractor shall collect halocarbons in approved, designated container per Federal Halocarbon Regulation.
 - .2 Contractor shall generate DDD Notice and affix notice to system and provide copies to be maintained on site by Departmental Representative.
 - .3 Contractor shall provide additional copy of all halocarbon service log records, including DDD Notices in the O&M Manual.
 - .3 Contractor may generate halocarbon service log records using their internally generated reporting documentation, if service records meet all specified requirements outlined in the Federal Halocarbon Regulation. Otherwise, the Contractor shall request NRC service logs from Departmental Representative for documentation purposes.

D / M / Y J / M / A	SERIAL NUMBER N° DE SÉRIE	MAKE / MODEL MARQUE / MODÈLE	YES OUI	NO NON	YES OUI	NO NON	TYPE	CODE(S)	QTY. +/-	LB OZ.	KG	CERTIFICATE NO. N° DU CERTIFICAT	EXPIRY DATE D'ÉCHEANCE	CONTROL NO. N° DE CONTRÔLE		
EQUIPMENT / ÉQUIPEMENT												LEAK - FUITE	REFRIGERANT / FRIGORIGÈNE	TECHNICIAN / TECHNICIEN(NE)	CONTROL NO. N° DE CONTRÔLE	
HALOCARBON SERVICE LOG, DECOMMISSIONING AND LEAK TEST NOTICE REGISTRE D'ENTRETIEN D'HALOCARBURE, AVIS DE MISE HORS SERVICE ET D'ESSAIS DE DÉTECTION DES FUITES															CONTROL NO. N° DE CONTRÔLE	5501
OWNER/ PROPRIÉTAIRE		NATIONAL RESEARCH COUNCIL CANADA CONSEIL NATIONAL DE RECHERCHES CANADA		PMO #												
ADDRESS / ADRESSE				SAP I.D. NUMBER / N° D'IDENTIFICATION												
NAME OF OPERATOR / NOM DE L'OPÉRATEUR				TOTAL SYSTEM CHARGE / CAPACITÉ TOTALE DE CHARGE DU SYSTÈME												
LOCATION OF SYSTEM / EMPLACEMENT PRÉCIS DU SYSTÈME BUILDING - ROOM / ÉDIFICE - SALLE				IF LEAK TESTING / EN CAS D'ESSAIS DE DÉTECTION DES FUITES		RECORD DATES OF TWO PREVIOUS LEAK TESTS / ENREGISTRER LES DATES DES DEUX DERNIERS ESSAIS										
DO NOT REMOVE THIS RECORD FROM UNIT NE PAS ENLEVER CETTE FICHE DE L'APPAREIL				IF DECOMMISSIONING / EN CAS DE MISE HORS SERVICE		RECORD FINAL DESTINATION OF SYSTEM / ENREGISTRER DESTINATION FINALE DU SYSTÈME										
CODES:				STORAGE/ ENTREPOSAGE		CONTRACTOR/ ENTREPRENEUR		RECYCLING/ RECYCLAGE		LANDFILL/ DÉCHARGE						
+/- Refrigerant / frigorigène: (+) added / ajouté; (-) recovered / récupéré				TECHNICIAN'S NAME - PRINT NOM DU TECHNICIEN(NE) - LETTRES MOULÉES		TECHNICIAN'S EMPLOYER EMPLOYEUR DU TECHNICIEN(NE)										
0 - The same recovered refrigerant removed and returned to system / Frigorigène remis au système suite aux travaux.				WHITE COPY: UNIT / COPIE BLANC: UNITÉ		PINK COPY: OFFICE / COPIE ROSE: BUREAU										
1 - New refrigerant added to system / Frigorigène nouveau ajouté au système.																
2 - Recovered refrigerant added to system / Frigorigène récupéré ajouté au système.																
3 - Refrigerant returned to wholesaler / Frigorigène retourné au grossiste.																
4 - Refrigerant recovered from system / Frigorigène récupéré du système.																
5 - Refrigerant purchased from wholesalers / Frigorigène acheté du grossiste.																
6 - Refrigerant transferred within company / Frigorigène transféré à l'intérieur de la compagnie.																
7 - System no longer contains refrigerant / Le système ne contient plus de frigorigène.																
8 - Leak test / Essai de détection des fuites.																

3.4

CLOSEOUT ACTIVITIES

- .1 Demolition Waste Disposal: arrange for legal disposal and remove demolished materials to accredited provincial landfill site or alternative disposal site (recycle centre) except where explicitly noted otherwise for materials being salvaged for reuse in new construction in accordance with requirements outlined in Section 01 74 19 - Waste Management and Disposal.
- .2 Halocarbon Service Logs: arrange for supplemental copies of all halocarbon service logs as specified in the Federal Halocarbon Regulations, including DDD Notices, to be incorporated into O&M Manuals upon project completion.

END OF SECTION

PART 1 - GENERAL

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 00- Common Work Results for HVAC.

1.2 REFERENCES

- .1 American National Standards Institute/American Society of Mechanical Engineers (ANSI/ASME)
 - .1 ANSI/ASME B31.1-2007, Power Piping.
 - .2 ANSI/ASME Boiler and Pressure Vessel Code-2007:
 - .1 BPVC 2007 Section I: Power Boilers.
 - .2 BPVC 2007 Section V: Nondestructive Examination.
 - .3 BPVC 2007 Section IX: Welding and Brazing Qualifications.
- .2 American National Standards Institute/American Water Works Association (ANSI/AWWA)
 - .1 ANSI/AWWA C206-03, Field Welding of Steel Water Pipe.
- .3 American Welding Society (AWS)
 - .1 AWS C1.1M/C1.1-2000(R2006), Recommended Practices for Resistance Welding.
 - .2 AWS Z49.1-2005, Safety in Welding, Cutting and Allied Process.
 - .3 AWS W1-2000, Welding Inspection Handbook..
- .4 Canadian Standards Association (CSA International)
 - .1 CSA W47.2-M1987(R2008), Certification of Companies for Fusion Welding of Aluminum.
 - .2 CSA W48-06, Filler Metals and Allied Materials for Metal Arc Welding.
 - .3 CSA B51-03(R2007), Boiler, Pressure Vessel and Pressure Piping Code.
 - .4 CSA-W117.2-2006, Safety in Welding, Cutting and Allied Processes.
 - .5 CSA W178.1-2008, Certification of Welding Inspection Organizations.
 - .6 CSA W178.2-2008, Certification of Welding Inspectors.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 00 10 00 – General Instructions.

1.4 QUALITY ASSURANCE

- .1 Qualifications:
 - .1 Welders:
 - .1 Welding qualifications in accordance with CSA B51.
 - .2 Use qualified and licensed welders possessing certificate for each procedure performed from authority having jurisdiction.
 - .3 Submit welder's qualifications to Departmental Representative.
 - .4 Each welder to possess identification symbol issued by authority having jurisdiction.
 - .5 Certification of companies for fusion welding of aluminum in accordance with CSA W47.2.

- .2 Inspectors:
 - .1 Inspectors qualified to CSA W178.2.
- .3 Certifications:
 - .1 Registration of welding procedures in accordance with CSA B51.
 - .2 Copy of welding procedures available for inspection.
 - .3 Safety in welding, cutting and allied processes in accordance with CSA-W117.2.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle in accordance with Section 00 10 00 – General Instructions.
- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: in accordance with Section 00 10 00 – General Instructions.

PART 2 - PRODUCTS

2.1 ELECTRODES

- .1 Electrodes: in accordance with CSA W48 Series.

PART 3 - EXECUTION

3.1 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 QUALITY OF WORK

- .1 Welding: in accordance with ANSI/ASME B31.1, ANSI/ASME Boiler and Pressure Vessel Code, Sections I and IX and ANSI/AWWA C206, using procedures conforming to AWS B3.0, AWS C1.1, and applicable requirements of provincial authority having jurisdiction.
- .2 All welds shall have clearly identified markings to indicate welder who completed weld. In the event that a weld is not clearly marked by a welder, the Departmental Representative has the right to reject the weld or require full gamma ray radiographic at Contractor's expense.

3.3 INSTALLATION REQUIREMENTS

- .1 Identify each weld with welder's identification symbol.
- .2 Backing rings:
 - .1 Where used, fit to minimize gaps between ring and pipe bore.

- .2 Do not install at orifice flanges.
- .3 Fittings:
 - .1 NPS 2 and smaller: install welding type sockets.
 - .2 Branch connections: install welding tees or forged branch outlet fittings.

3.4 INSPECTION AND TESTS - GENERAL REQUIREMENTS

- .1 Review weld quality requirements and defect limits of applicable codes and standards with Departmental Representative before work is started.
- .2 Formulate "Inspection and Test Plan" in co-operation with Departmental Representative.
- .3 Do not conceal welds until they have been inspected, tested and approved by inspector.
- .4 Provide for inspector to visually inspect welds during early stages of welding procedures in accordance with Welding Inspection Handbook. Repair or replace defects as required by codes and as specified.

3.5 SPECIALIST EXAMINATIONS AND TESTS

- .1 General:
 - .1 Perform examinations and tests by specialist qualified to CSA W178.1 and CSA W178.2 and approved by Departmental Representative.
 - .2 To ANSI/ASME Boiler and Pressure Vessels Code, Section V, CSA B51 and requirements of authority having jurisdiction.
- .2 Hydrostatically test welds to ANSI/ASME B31.1.
- .3 Visual examinations: include entire circumference of weld externally and wherever possible internally.
- .4 Failure of visual examinations:
 - .1 Upon failure of welds by visual examination, perform additional testing as directed by Departmental Representative, selected at random by Departmental Representative by radiographic tests.

3.6 DEFECTS CAUSING REJECTION

- .1 As described in ANSI/ASME B31.1 and ANSI/ASME Boiler and Pressure Vessels Code.

3.7 REPAIR OF WELDS WHICH FAILED TESTS

- .1 Re-inspect and re-test repaired or re-worked welds at Contractor's expense.

3.8 CLEANING

- .1 Clean in accordance with Section 00 10 00 – General Instructions.
- .2 Waste Management: in accordance with Section 00 10 00 – General Instructions.

END OF SECTION

PART 1 - GENERAL

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 00 – Common Work Results for HVAC.

1.2 REFERENCES

- .1 American National Standards Institute (ANSI)/American Society of Mechanical Engineers (ASME)
 - .1 ANSI/ASME B1.20.1-1983(R2006), Pipe Threads, General Purpose (Inch).
- .2 ASTM International
 - .1 ASTM B62-02, Standard Specification for Composition Bronze or Ounce Metal Castings.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 00 10 00 – General Instructions.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and data sheets for equipment and systems and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit data for valves specified in this Section.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 00 10 00 – General Instructions and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
 - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: in accordance with Section 00 10 00 – General Instructions.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Valves:
 - .1 Except for specialty valves, to be single manufacturer.
 - .2 Products to have CRN registration numbers.
- .2 End Connections:
 - .1 Connection into adjacent piping/tubing:
 - .1 Steel pipe systems: screwed ends to ANSI/ASME B1.20.1.
- .3 Lockshield Keys:
 - .1 Where lockshield valves are specified, provide 10 keys of each size: malleable iron cadmium plated.
- .4 Globe Valves – For balancing service in hot water piping:
 - .1 Connections: screwed with hexagonal shoulders.
 - .2 Y-pattern, bronze body c/w two brass metering ports, memory feature and capable of precise flow measurement, flow balancing and drip tight shut-off.
 - .3 Acceptable product: Tour & Andersson.
- .5 Ball Valves – For installation in hot water piping:
 - .1 NPS 2 and under:
 - .1 Body and cap: cast high tensile bronze to ASTM B62.
 - .2 Pressure rating: 4140-kPa CWP.
 - .3 Connections: screwed ends to ANSI B1.20.1 and with hexagonal shoulders.
 - .4 Stem: tamperproof ball drive.
 - .5 Stem packing nut: external to body.
 - .6 Ball and seat: replaceable stainless steel solid ball and Teflon seats.
 - .7 Stem seal: TFE with external packing nut.
 - .8 Operator: removable lever handle.
- .6 Drain valves:
 - .1 Minimum NPS $\frac{3}{4}$ unless otherwise specified: straight pattern bronze ball valve with hose end male thread adapter and complete with cap and chain.

PART 3 - EXECUTION

3.1 INSTALLATION

- .1 Install rising stem valves in upright position with stem above horizontal.
- .2 Remove internal parts before soldering.
- .3 Install valves with unions at each piece of equipment arranged to allow servicing, maintenance, and equipment removal.

3.2 CLEANING

- .1 Clean in accordance with Section 00 10 00 – General Instructions.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: in accordance with Section 00 10 00 – General Instructions.

END OF SECTION

PART 1 - GENERAL

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 00 – Common Work Results for HVAC.
- .2 Section 23 05 48 – Vibration and Seismic Controls for HVAC Piping and Equipment.

1.2 REFERENCES

- .1 American Society of Mechanical Engineers (ASME)
 - .1 ASME B31.1-07, Power Piping.
- .2 ASTM International
 - .1 ASTM A125-1996(2007), Standard Specification for Steel Springs, Helical, Heat-Treated.
 - .2 ASTM A307-07b, Standard Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
 - .3 ASTM A563-07a, Standard Specification for Carbon and Alloy Steel Nuts.
- .3 Manufacturer's Standardization Society of the Valves and Fittings Industry (MSS)
 - .1 MSS SP 58-2002, Pipe Hangers and Supports - Materials, Design and Manufacture.
 - .2 MSS SP 69-2003, Pipe Hangers and Supports - Selection and Application.
 - .3 MSS SP 89-2003, Pipe Hangers and Supports - Fabrication and Installation Practices.
- .4 Underwriter's Laboratories of Canada (ULC)

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 00 10 00 – General Instructions.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and data sheets for hangers and supports and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit shop drawings for:
 - .1 Bases, hangers and supports.
 - .2 Connections to equipment and structure.
 - .3 Structural assemblies.
- .4 Certificates:
 - .1 Submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .5 Manufacturers' Instructions:
 - .1 Provide manufacturer's installation instructions.
 - .1 Departmental Representative will make available 1 copy of systems supplier's

installation instructions.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 00 10 00 – General Instructions and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
 - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: in accordance with Section 00 10 00 – General Instructions.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

- .1 Design Requirements:
 - .1 Construct pipe hanger and support to manufacturer's recommendations utilizing manufacturer's regular production components, parts and assemblies.
 - .2 Base maximum load ratings on allowable stresses prescribed by ASME B31.1 or MSS SP 58.
 - .3 Ensure that supports, guides, anchors do not transmit excessive quantities of heat to building structure.
 - .4 Design hangers and supports to support systems under conditions of operation, allow free expansion and contraction, prevent excessive stresses from being introduced into pipework or connected equipment.
 - .5 Provide for vertical adjustments after erection and during commissioning. Amount of adjustment in accordance with MSS SP 58.
- .2 Performance Requirements:
 - .1 Design supports, platforms, catwalks, hangers to withstand seismic events as specified Section 23 05 48 – Vibration and Seismic Controls for HVAC Piping and Equipment.

2.2 GENERAL

- .1 Fabricate hangers, supports and sway braces in accordance with MSS SP 58. ANSI B31.1 and
- .2 Use components for intended design purpose only. Do not use for rigging or erection purposes.

2.3 PIPE HANGERS

- .1 Finishes:
 - .1 Pipe hangers and supports: galvanized-exterior and painted with zinc-rich paint –interior after manufacture.
 - .2 Use hot dipped galvanizing process.

- .3 Ensure steel hangers in contact with copper piping are copper plated or epoxy coated.
- .2 Upper attachment structural: suspension from lower flange of I-Beam:
 - .1 Cold piping NPS 2 maximum: malleable iron C-clamp with hardened steel cup point setscrew, locknut and carbon steel retaining clip.
 - .1 Rod: 9 mm UL listed
 - .2 Cold piping NPS 2 1/2 or greater, hot piping: malleable iron beam clamp, eye rod, jaws and extension with carbon steel retaining clip, tie rod, nuts and washers, UL listed to MSS-SP58 and MSS-SP69.
- .3 Upper attachment structural: suspension from upper flange of I-Beam:
 - .1 Cold piping NPS 2 maximum: ductile iron top-of-beam C-clamp with hardened steel cup point setscrew, locknut and carbon steel retaining clip, UL listed to MSS SP69.
 - .2 Cold piping NPS 2 1/2 or greater, hot piping: malleable iron top-of-beam jaw-clamp with hooked rod, spring washer, plain washer and nut UL listed.
- .4 Upper attachment to concrete:
 - .1 Ceiling: carbon steel welded eye rod, clevis plate, clevis pin and cotters with weldless forged steel eye nut. Ensure eye 6 mm minimum greater than rod diameter.
 - .2 Concrete inserts: wedge shaped body with knockout protector plate UL listed to MSS SP69.
- .5 Hanger rods: threaded rod material to MSS SP58:
 - .1 Ensure that hanger rods are subject to tensile loading only.
 - .2 Provide linkages where lateral or axial movement of pipework is anticipated.
- .7 Pipe attachments: material to MSS SP58:
 - .1 Attachments for steel piping: carbon steel Galvanized.
 - .2 Attachments for copper piping: copper plated black steel.
 - .3 Oversize pipe hangers and supports.
- .8 Adjustable clevis: material to MSS SP69 UL listed, clevis bolt with nipple spacer and vertical adjustment nuts above and below clevis.
- .9 Shop and field-fabricated assemblies.
 - .1 Trapeze hanger assemblies: MSS SP-89.
 - .2 Steel brackets : MSS SP-89.
 - .3 Sway braces for seismic restraint systems: to MSS SP-89.

2.4 RISER CLAMPS

- .1 Steel or cast iron pipe: galvanized carbon steel to MSS SP 58, type 42, UL listed.
- .2 Copper pipe: carbon steel copper plated to MSS SP 58, type 42.
- .3 Bolts: to ASTM A307.
- .4 Nuts: to ASTM A563.

2.5 INSULATION PROTECTION SHIELDS

- .1 Insulated cold piping:
 - .1 64 kg/m³ density insulation plus insulation protection shield to: MSS SP 69, galvanized sheet carbon steel. Length designed for maximum 3 m span.
- .2 Insulated hot piping:
 - .1 Curved plate 300 mm long, with edges turned up, welded-in centre plate for pipe sizes NPS 12 and over, carbon steel to comply with MSS SP 69.

2.6 CONSTANT SUPPORT SPRING HANGERS

- .1 Springs: alloy steel to ASTM A125, shot peened, magnetic particle inspected, with +/-5% spring rate tolerance, tested for free height, spring rate, loaded height and provided with Certified Mill Test Report (CMTR).
- .2 Load adjustability: 10 % minimum adjustability each side of calibrated load. Adjustment without special tools. Adjustments not to affect travel capabilities.
- .3 Provide upper and lower factory set travel stops.
- .4 Provide load adjustment scale for field adjustments.
- .5 Total travel to be actual travel + 20%. Difference between total travel and actual travel 25 mm minimum.
- .6 Individually calibrated scales on each side of support calibrated prior to shipment, complete with calibration record.

2.7 VARIABLE SUPPORT SPRING HANGERS

- .1 Vertical movement: 13 mm minimum, 50 mm maximum, use single spring pre-compressed variable spring hangers.
- .2 Vertical movement greater than 50 mm: use double spring pre-compressed variable spring hanger with 2 springs in series in single casing.
- .3 Variable spring hanger complete with factory calibrated travel stops. Provide certificate of calibration for each hanger.
- .4 Steel alloy springs: to ASTM A125, shot peened, magnetic particle inspected, with +/-5 % spring rate tolerance, tested for free height, spring rate, loaded height and provided with CMTR.

2.8 EQUIPMENT SUPPORTS

- .1 Fabricate equipment supports not provided by equipment manufacturer from structural grade steel approved by a structural engineer.

2.9 EQUIPMENT ANCHOR BOLTS AND TEMPLATES

- .1 Provide templates to ensure accurate location of anchor bolts.

2.10 OTHER EQUIPMENT SUPPORTS

- .1 Fabricate equipment supports from structural grade steel approved by a structural engineer.
- .2 Submit structural calculations with shop drawings.

PART 3 - EXECUTION

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Install in accordance with:
 - .1 Manufacturer's instructions and recommendations.
- .2 Clamps on riser piping:
 - .1 Support independent of connected horizontal pipework using riser clamps and riser clamp lugs welded to riser.
 - .2 Bolt-tightening torques to industry standards.
 - .3 Steel pipes: install below coupling or shear lugs welded to pipe.
 - .4 Cast iron pipes: install below joint.
- .3 Clevis plates:
 - .1 Attach to concrete with 4 minimum concrete inserts, one at each corner.
- .4 Provide supplementary structural steelwork where structural bearings do not exist or where concrete inserts are not in correct locations.
- .5 Use approved constant support type hangers where:
 - .1 Vertical movement of pipework is 13 mm or more,
 - .2 Transfer of load to adjacent hangers or connected equipment is not permitted.
- .6 Use variable support spring hangers where:
 - .1 Transfer of load to adjacent piping or to connected equipment is not critical.
 - .2 Variation in supporting effect does not exceed 25 % of total load.

3.3 HANGER SPACING

- .1 Plumbing piping: to Canadian Plumbing Code.

- .2 Copper piping: up to NPS 1/2: every 1.5 m.
- .3 Flexible joint roll groove pipe: in accordance with table below for steel, but not less than one hanger at joints. Table listings for straight runs without concentrated loads and where full linear movement is not required.
- .4 Within 300 mm of each elbow.
- .5 In accordance with table below, but not less than one hanger at joints:
MAXIMUM HANGER SPACING AND MINIMUM ROD SIZE

O.D		STEEL PIPE				COPPER TUBE		ROD SIZE	
INCHES	mm	WATER		STEAM / AIR		FT	METER	INCH	mm
		FT	METER	FT	METER				
<= 1/2	12.7	7	2.13	8	2.44	5	1.52	1/4'	6.4
3/4'	19.1	7	2.13	9	2.74	5	1.52	1/4'	6.4
1	25.4	7	2.13	9	2.74	6	1.83	1/4'	6.4
1-1/4'	31.7	8	2.44	10	3.05	7	2.13	1/4'	6.4
1-1/2'	38.1	9	2.74	12	3.66	8	2.44	3/8'	9.5
2	50.8	10	3.05	13	3.96	8	2.44	3/8'	9.5
2-1/2'	63.5	11	3.35	14	4.27	9	2.74	3/8'	9.5
3	76.2	12	3.66	15	4.57	10	3.05	3/8'	9.5
4	101.6	14	4.27	17	5.18	12	3.66	1/2'	12.7
6	152.4	17	5.18	21	6.40	14	4.27	1/2'	12.7
8	203.2	19	5.79	24	7.31	16	4.88	5/8'	15.8
10	254.0	20	6.10	26	7.92	18	5.49	3/4'	19.0
12	304.8	23	7.01	30	9.14	19	5.79	7/8'	22.2
14	355.6	25	7.62	32	9.75			1	25.4
16	406.4	27	8.23	35	10.67			1	25.4
18	457.2	28	8.53	37	11.28			1-1/4'	31.7
20	508.0	30	9.14	39	11.89			1-1/4'	31.7

3.4 HANGER INSTALLATION

- .1 Install hanger so that rod is vertical under operating conditions.
- .2 Adjust hangers to equalize load.
- .3 Support from structural members. Where structural bearing does not exist or inserts are not in suitable locations, provide supplementary structural steel members.

3.5 HORIZONTAL MOVEMENT

- .1 Angularity of rod hanger resulting from horizontal movement of pipework from cold to hot position not to exceed 4 degrees from vertical.
- .2 Where horizontal pipe movement is less than 13 mm, offset pipe hanger and support so that rod hanger is vertical in the hot position.

3.6 FINAL ADJUSTMENT

- .1 Adjust hangers and supports:

- .1 Ensure that rod is vertical under operating conditions.
- .2 Equalize loads.

- .2 Adjustable clevis:
 - .1 Tighten hanger load nut securely to ensure proper hanger performance.
 - .2 Tighten upper nut after adjustment.

- .3 C-clamps:
 - .1 Follow manufacturer's recommended written instructions and torque values when tightening C-clamps to bottom flange of beam.

- .4 Beam clamps:
 - .1 Hammer jaw firmly against underside of beam.

3.7 CLEANING

- .1 Clean in accordance with Section 00 10 00 – General Instructions.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.

- .2 Waste Management: in accordance with Section 00 10 00 – General Instructions.

END OF SECTION

PART 1 - GENERAL

1.1 SUMMARY

- .1 Section 23 05 00 – Common Work Results for HVAC.

1.2 REFERENCES

- .1 National Building Code of Canada (NBC) – 2015.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 00 10 00 – General Instructions.
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 00 10 00 – General Instructions. Include product characteristics, performance criteria, and limitations.
- .2 Submit shop drawings in accordance with Section 00 10 00 – General Instructions.
 - .1 Shop drawings: submit drawings stamped and signed by professional engineer registered or licensed in Province of Ontario, Canada.
 - .2 Provide system shop drawings complete with performance and product data.
 - .3 Provide detailed drawings of seismic control measures for equipment and piping.

1.4 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with Section 00 10 00 – General Instructions.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: in accordance with Section 00 10 00 – General Instructions.

PART 2 - PRODUCTS

2.1 GENERAL

- .1 Size and shape of bases type and performance of vibration isolation as indicated.

2.2 ELASTOMERIC PADS

- .1 Type EP1 - neoprene waffle or ribbed; 9mm minimum thick; 50durometer; maximum loading 350kPa.

- .2 Type EP2 - rubber waffle or ribbed; 9 mm minimum thick; 30 durometer natural rubber; maximum loading 415 kPa.
- .3 Type EP3 - neoprene-steel-neoprene; 9 mm minimum thick neoprene bonded to 1.71 mm steel plate; 50 durometer neoprene, waffle or ribbed; holes sleeved with isolation washers; maximum loading 350 kPa.
- .4 Type EP4 - rubber-steel-rubber; 9 mm minimum thick rubber bonded to 1.71 mm steel plate; 30 durometer natural rubber, waffle or ribbed; holes sleeved with isolation washers; maximum loading 415 kPa.

2.3 ELASTOMERIC MOUNTS

- .1 Type M1 - colour coded; neoprene in shear; maximum durometer of 60; threaded insert and two bolt-down holes; ribbed top and bottom surfaces.

2.4 SPRINGS

- .1 Design stable springs: ratio of lateral to axial stiffness is equal to or greater than 1.2 times ratio of static deflection to working height. Select for 50% travel beyond rated load. Units complete with levelling devices.
- .2 Ratio of height when loaded to diameter of spring between 0.8 to 1.0.
- .3 Colour code springs.

2.5 SPRING MOUNT

- .1 Zinc or cadmium plated hardware; housings coated with rust resistant paint.
- .2 Type M2 - stable open spring: support on bonded 6 mm minimum thick ribbed neoprene or rubber friction and acoustic pad.
- .3 Type M3 - stable open spring: 6 mm minimum thick ribbed neoprene or rubber friction and acoustic pad, bonded under isolator and on isolator top plate; levelling bolt for rigidly mounting to equipment.
- .4 Type M4 - restrained stable open spring: supported on bonded 6 mm minimum thick ribbed neoprene or rubber friction and acoustic pad; built-in resilient limit stops, removable spacer plates.
- .5 Type M5 - enclosed spring mounts with snubbers for isolation up to 950 kg maximum.

2.6 HANGERS

- .1 Colour coded springs, rust resistant, painted box type hangers. Arrange to permit hanger box or rod to move through a 30 degrees arc without metal to metal contact.
- .2 Type H1 - neoprene - in-shear, moulded with rod isolation bushing which passes through hanger box.

- .3 Type H2 - stable spring, elastomeric washer, cup with moulded isolation bushing which passes through hanger box.
- .4 Type H3 - stable spring, elastomeric element, cup with moulded isolation bushing which passes through hanger box.
- .5 Type H4 - stable spring, elastomeric element with precompression washer and nut with deflection indicator.

2.7 SEISMIC CONTROL MEASURES

- .1 General:
 - .1 Following systems and/or equipment to remain operational during and after earthquakes:
 - .1 Heating system (equipment and piping).
 - .2 Seismic control systems to work in every direction.
 - .3 Fasteners and attachment points to resist same maximum load as seismic restraint.
 - .4 Drilled or power driven anchors and fasteners not permitted.
 - .5 No equipment, equipment supports or mounts to fail before failure of structure.
 - .6 Supports of cast iron or threaded pipe not permitted.
 - .7 Seismic control measures not to interfere with integrity of firestopping.
 - .2 Static equipment:
 - .1 Anchor equipment to equipment supports. Anchor equipment supports to structure.
 - .2 Suspended equipment:
 - .1 Use one or more of following methods depending upon site conditions:
 - .1 Install tight to structure.
 - .2 Cross brace in every direction.
 - .3 Brace back to structure.
 - .4 Cable restraint system.
 - .3 Seismic restraints:
 - .1 Cushioning action gentle and steady.
 - .2 Never reach metal-like stiffness.
 - .3 Vibration isolated equipment:
 - .1 Seismic control measures not to jeopardize noise and vibration isolation systems. Provide 6 to 9 mm clearance during normal operation of equipment and systems between seismic restraint and equipment.
 - .2 Incorporate seismic restraints into vibration isolation system to resist complete isolator unloading.
 - .3 As indicated.
 - .4 Piping systems:
 - .1 Piping systems: hangers longer than 300 mm; brace at each hanger.
 - .2 Compatible with requirements for anchoring and guiding of piping systems.
 - .5 Bracing methods:
 - .1 Approved by Departmental Representative.
 - .2 Structural angles or channels.
 - .3 Cable restraint system incorporating grommets, shackles and other hardware to ensure alignment of restraints and to avoid bending of cables at connection points. Incorporate neoprene into cable connections to reduce shock loads.

PART 3 - EXECUTION

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Seismic control measures to meet requirements of NBC.
- .2 Install vibration isolation equipment in accordance with manufacturer's instructions and adjust mountings to level equipment.
- .3 Ensure piping, ducting and electrical connections to isolated equipment do not reduce system flexibility and that piping, conduit and ducting passage through walls and floors do not transmit vibrations.
- .4 Unless indicated otherwise, support piping connected to isolated equipment with spring mounts or spring hangers with 25 mm minimum static deflection as follows:
 - .1 Up to NPS4: first 3 points of support. NPS5 to NPS8: first 4 points of support. NPS10 and Over: first 6 points of support.
 - .2 First point of support: static deflection of twice deflection of isolated equipment, but not more than 50 mm.
- .5 Where isolation is bolted to floor use vibration isolation rubber washers.
- .6 Block and shim level bases so that ductwork and piping connections can be made to rigid system at operating level, before isolator adjustment is made. Ensure that there is no physical contact between isolated equipment and building structure.

3.3 FIELD QUALITY CONTROL

- .1 Manufacturer's Field Services:
 - .1 Arrange with manufacturer's representative to review work of this Section and submit written reports to verify compliance with Contract Documents.
 - .2 Manufacturer's Field Services: consisting of product use recommendations and periodic site visits to review installation, scheduled as follows:
 - .1 After delivery and storage of Products.
 - .2 After preparatory work is complete but before installation commences.
 - .3 Twice during the installation, at 25% and 60% completion stages.
 - .4 Upon completion of installation.
 - .3 Submit manufacturer's reports to Departmental Representative within 3 days of manufacturer representative's review.
 - .4 Make adjustments and corrections in accordance with written report.

3.4 CLEANING

- .1 Proceed in accordance with Section 00 10 00 – General Instructions.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

PART 1 - GENERAL

1.1 SUMMARY

- .1 Section 23 05 00 – Common Work Results for HVAC.

1.2 REFERENCES

- .1 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-24.3-92, Identification of Piping Systems.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Product Data:
 - .1 Submittals: in accordance with Section 00 10 00 – General Instructions.
 - .2 Product data to include paint colour chips, other products specified in this section.

1.4 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with Section 00 10 00 – General Instructions and with manufacturer's written instructions.
- .2 Waste Management and Disposal: in accordance with Section 00 10 00 – General Instructions.

PART 2 - PRODUCTS

2.1 MANUFACTURER'S EQUIPMENT NAMEPLATES

- .1 Metal or plastic laminate nameplate mechanically fastened to each piece of equipment by manufacturer.
- .2 Lettering and numbers raised or recessed.
- .3 Information to include, as appropriate:
 - .1 Equipment: manufacturer's name, model, size, serial number, capacity.
 - .2 Motor: voltage, Hz, phase, power factor, duty, frame size.

2.2 SYSTEM NAMEPLATES

- .1 Colours:

- .1 Hazardous: red letters, white background.
- .2 Elsewhere: black letters, white background (except where required otherwise by applicable codes).
- .2 Construction:
 - .1 3 mm thick laminated plastic, matte finish, with square corners, letters accurately aligned and machine engraved into core.
- .3 Sizes:
 - .1 Conform to following table:

Size # mm	Sizes (mm)	No. of Lines	Height of Letters (mm)
1	10 x 50	1	3
2	13 x 75	1	5
3	13 x 75	2	3
4	20 x 100	1	8
5	20 x 100	2	5
6	20 x 200	1	8
7	25 x 125	1	12
8	25 x 125	2	8
9	35 x 200	1	20
 - .2 Use maximum of 25 letters/numbers per line.
- .4 Locations:
 - .1 Terminal cabinets, control panels: use size # 5.
 - .2 Equipment in Mechanical Rooms: use size # 9.

2.3 EXISTING IDENTIFICATION SYSTEMS

- .1 Apply existing identification system to new work.
- .2 Where existing identification system does not cover for new work, use identification system specified this section.
- .3 Before starting work, obtain written approval of identification system from Departmental Representative.

2.4 IDENTIFICATION OF PIPING SYSTEMS

- .1 Identify contents by background colour marking, pictogram (as necessary), legend; direction of flow by arrows. To CAN/CGSB 24.3 except where specified otherwise.
- .2 Pictograms:
 - .1 Where required: Workplace Hazardous Materials Information System (WHMIS) regulations.
- .3 Legend:
 - .1 Block capitals to sizes and colours listed in CAN/CGSB 24.3.

- .4 Arrows showing direction of flow:
 - .1 Outside diameter of pipe or insulation less than 75 mm: 100 mm long x 50 mm high.
 - .2 Outside diameter of pipe or insulation 75 mm and greater: 150 mm long x 50 mm high.
 - .3 Use double-headed arrows where flow is reversible.
- .5 Extent of background colour marking:
 - .1 To full circumference of pipe or insulation.
 - .2 Length to accommodate pictogram, full length of legend and arrows.
- .6 Materials for background colour marking, legend, arrows:
 - .1 Pipes and tubing 20 mm and smaller: waterproof and heat-resistant pressure sensitive plastic marker tags.
 - .2 Other pipes: pressure sensitive plastic-coated cloth with protective overcoating, waterproof contact adhesive undercoating, suitable for ambient of 100% RH and continuous operating temperature of 150 degrees C and intermittent temperature of 200 degrees C.
- .7 Colours and Legends:
 - .1 Where not listed, obtain direction from Departmental Representative.
 - .2 Colours for legends, arrows: to following table:

Background colour:	Legend, arrows:
Yellow	BLACK
Green	WHITE
Red	WHITE

- .3 Background colour marking and legends for piping systems:

Contents	Background colour marking	Legend
Hot Water Heating Supply	Yellow	HEATING SUPPLY
Hot Water Heating Return	Yellow	HEATING RETURN

2.5 VALVES, CONTROLLERS

- .1 Brass tags with 12 mm stamped identification data filled with black paint.
- .2 Include flow diagrams for each system, of approved size, showing charts and schedules with identification of each tagged item, valve type, service, function, normal position, location of tagged item.

2.6 CONTROLS COMPONENTS IDENTIFICATION

- .1 Identify all systems, equipment, components, controls, sensors with system nameplates specified in this section.
- .2 Inscriptions to include function and (where appropriate) fail-safe position.

2.7 LANGUAGE

- .1 Identification in English and French.
- .2 Use one nameplate and label for both languages.

PART 3 - EXECUTION

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Perform work in accordance with CAN/CGSB-24.3 except as specified otherwise.
- .2 Provide ULC and CSA registration plates as required by respective agency.

3.3 NAMEPLATES

- .1 Locations:
 - .1 In conspicuous location to facilitate easy reading and identification from operating floor.
- .2 Standoffs:
 - .1 Provide for nameplates on hot and/or insulated surfaces.
- .3 Protection:
 - .1 Do not paint, insulate or cover.

3.4 LOCATION OF IDENTIFICATION ON PIPING SYSTEMS

- .1 On long straight runs in open areas in boiler rooms, equipment rooms, galleries, tunnels: at not more than 17 m intervals and more frequently if required to ensure that at least one is visible from any one viewpoint in operating areas and walking aisles.
- .2 Adjacent to each change in direction.
- .3 At least once in each small room through which piping or ductwork passes.
- .4 On both sides of visual obstruction or where run is difficult to follow.
- .5 On both sides of separations such as walls, floors, partitions.

- .6 Where system is installed in pipe chases, ceiling spaces, galleries, confined spaces, at entry and exit points, and at access openings.
- .7 At beginning and end points of each run and at each piece of equipment in run.
- .8 At point immediately upstream of major manually operated or automatically controlled valves, and dampers. Where this is not possible, place identification as close as possible, preferably on upstream side.
- .9 Identification easily and accurately readable from usual operating areas and from access points.
 - .1 Position of identification approximately at right angles to most convenient line of sight, considering operating positions, lighting conditions, risk of physical damage or injury and reduced visibility over time due to dust and dirt.

3.5 VALVES, CONTROLLERS

- .1 Valves and operating controllers, except at plumbing fixtures, radiation, or where in plain sight of equipment they serve: Secure tags with non-ferrous chains or closed "S" hooks.
- .2 Install one copy of flow diagrams, valve schedules mounted in frame behind non-glare glass where directed by Departmental Representative. Provide one copy (reduced in size if required) in each operating and maintenance manual.
- .3 Number valves in each system consecutively.

3.6 CLEANING

- .1 Proceed in accordance with Section 00 10 00 – General Instructions.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

PART 1 - GENERAL

1.1 SUMMARY

- .1 TAB is used throughout this Section to describe the process, methods and requirements of testing, adjusting and balancing for HVAC.
- .2 TAB means to test, adjust and balance to perform in accordance with requirements of Contract Documents and to do other work as specified in this section.

1.2 QUALIFICATIONS OF TAB PERSONNEL

- .1 Submit names of personnel to perform TAB to Departmental Representative within 90 days of award of contract.
- .2 Provide documentation confirming qualifications, successful experience.
- .3 TAB: performed in accordance with the requirements of standard under which TAB Firm's qualifications are approved:
 - .1 Associated Air Balance Council, (AABC) National Standards for Total System Balance, MN-1-2002.
 - .2 National Environmental Balancing Bureau (NEBB) TABES, Procedural Standards for Testing, Adjusting, Balancing of Environmental Systems-1998.
 - .3 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA), HVAC TAB HVAC Systems - Testing, Adjusting and Balancing-2002.
- .4 Recommendations and suggested practices contained in the TAB Standard: mandatory.
- .5 Use TAB Standard provisions, including checklists, and report forms to satisfy Contract requirements.
- .6 Use TAB Standard for TAB, including qualifications for TAB Firm and Specialist and calibration of TAB instruments.
- .7 Where instrument manufacturer calibration recommendations are more stringent than those listed in TAB Standard, use manufacturer's recommendations.
- .8 TAB Standard quality assurance provisions such as performance guarantees form part of this contract.
 - .1 For systems or system components not covered in TAB Standard, use TAB procedures developed by TAB Specialist.
 - .2 Where new procedures, and requirements, are applicable to Contract requirements have been published or adopted by body responsible for TAB Standard used (AABC, NEBB, or TABB), requirements and recommendations contained in these procedures and requirements are mandatory.

1.3 PURPOSE OF TAB

- .1 Test to verify proper and safe operation, determine actual point of performance, evaluate qualitative

and quantitative performance of equipment, systems and controls at design, average and low loads using actual or simulated loads

- .2 Adjust and regulate equipment and systems to meet specified performance requirements and to achieve specified interaction with other related systems under normal and emergency loads and operating conditions.
- .3 Balance systems and equipment to regulate flow rates to match load requirements over full operating ranges.

1.4 EXCEPTIONS

- .1 TAB of systems and equipment regulated by codes, standards to satisfaction of authority having jurisdiction.

1.5 CO-ORDINATION

- .1 Schedule time required for TAB (including repairs, re-testing) into project construction and completion schedule to ensure completion before acceptance of project.
- .2 Do TAB of each system independently and subsequently, where interlocked with other systems, in unison with those systems.

1.6 PRE-TAB REVIEW

- .1 Review contract documents before project construction is started and confirm in writing to Departmental Representative adequacy of provisions for TAB and other aspects of design and installation pertinent to success of TAB.
- .2 Review specified standards and report to Departmental Representative in writing proposed procedures which vary from standard.
- .3 During construction, co-ordinate location and installation of TAB devices, equipment, accessories, measurement ports and fittings.

1.7 START-UP

- .1 Follow start-up procedures as recommended by equipment manufacturer unless specified otherwise.
- .2 Follow special start-up procedures specified elsewhere in Division 23.

1.8 OPERATION OF SYSTEMS DURING TAB

- .1 Operate systems for length of time required for TAB and as required by Departmental Representative for verification of TAB reports.

1.9 START OF TAB

- .1 Notify Departmental Representative 7 days prior to start of TAB.
- .2 Start TAB when building is essentially completed, including:
 - .1 Installation of ceilings, doors, windows, other construction affecting TAB.
 - .2 Provisions for TAB installed and operational.
 - .3 Start-up, verification for proper, normal and safe operation of mechanical and associated electrical and control systems affecting TAB including but not limited to:
 - .1 Proper thermal overload protection in place for electrical equipment.
 - .2 Liquid systems:
 - .1 Flushed, filled, vented.
 - .2 Correct pump rotation.
 - .3 Strainers in place, baskets clean.
 - .4 Isolating and balancing valves installed, open.
 - .5 Calibrated balancing valves installed, at factory settings.
 - .6 Chemical treatment systems complete, operational.

1.10 APPLICATION TOLERANCES

- .1 Do TAB to following tolerances of design values:
 - .1 Hydronic systems: plus or minus 10%.

1.11 ACCURACY TOLERANCES

- .1 Measured values accurate to within plus or minus 2% of actual values.

1.12 INSTRUMENTS

- .1 Prior to TAB, submit to Departmental Representative list of instruments used together with serial numbers.
- .2 Calibrate in accordance with requirements of most stringent of referenced standard for either applicable system or HVAC system.
- .3 Calibrate within 3 months of TAB. Provide certificate of calibration to Departmental Representative.

1.13 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit, prior to commencement of TAB:
- .2 Proposed methodology and procedures for performing TAB if different from referenced standard.

1.14 PRELIMINARY TAB REPORT

- .1 Submit for checking and approval of Departmental Representative, prior to submission of formal TAB report, sample of rough TAB sheets. Include:

- .1 Details of instruments used.
- .2 Details of TAB procedures employed.
- .3 Calculations procedures.
- .4 Summaries.

1.15 TAB REPORT

- .1 Format in accordance with referenced standard.
- .2 TAB report to show results in SI units and to include:
 - .1 Project record drawings.
 - .2 System schematics.
- .3 Submit electronic copy of TAB Report to Departmental Representative for verification and approval, in English.

1.16 VERIFICATION

- .1 Reported results subject to verification by Departmental Representative.
- .2 Provide personnel and instrumentation to verify up to 100% of reported results.
- .3 Number and location of verified results as directed by Departmental Representative.
- .4 Pay costs to repeat TAB as required to satisfaction of Departmental Representative.

1.17 SETTINGS

- .1 After TAB is completed to satisfaction of Departmental Representative, ensure sensors are at required settings.
- .2 Permanently mark settings to allow restoration at any time during life of facility. Do not eradicate or cover markings.

1.18 COMPLETION OF TAB

- .1 TAB considered complete when final TAB Report received and approved by Departmental Representative.

1.19 HYDRONIC SYSTEMS

- .1 Standard: TAB to most stringent of this section.
- .2 Do TAB of following systems, equipment, components, controls:
 - .1 New heating equipment shown on the drawings.
- .3 Qualifications: personnel performing TAB qualified to standards of AABC, NEBB.

- .4 Quality assurance: perform TAB under direction of supervisor qualified to standards of AABC, NEBB.
- .5 Locations of equipment measurements: to include as appropriate:
 - .1 Any equipment which can modify flow or fluid conditions.
- .6 Coordinate with Division 25 to override all existing heating water control valves in the building to 100%, prior to balancing new balancing valves.

PART 2 - PRODUCTS

2.1 NOT USED

- .1 Not used.

PART 3 - EXECUTION

3.1 NOT USED

- .1 Not used.

END OF SECTION

PART 1 - GENERAL

1.1 SUMMARY

- .1 Section 23 05 00 – Common Work Results for HVAC.

1.2 REFERENCES

- .1 American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)
 - .1 ASHRAE Standard 90.1-01, Energy Standard for Buildings Except Low-Rise Residential Buildings (IESNA co-sponsored; ANSI approved; Continuous Maintenance Standard).
- .2 American Society for Testing and Materials International (ASTM)
 - .1 ASTM C 335-04, Standard Test Method for Steady State Heat Transfer Properties of Horizontal Pipe Insulation.
 - .2 ASTM C 449/C 449M-00, Standard Specification for Mineral Fiber-Hydraulic-Setting Thermal Insulating and Finishing Cement.
 - .3 ASTM C 547-2003, Mineral Fiber Pipe Insulation.
 - .4 ASTM C 921-03a, Standard Practice for Determining the Properties of Jacketing Materials for Thermal Insulation.
- .3 Canadian General Standards Board (CGSB)
 - .1 CGSB 51-GP-52Ma-89, Vapour Barrier, Jacket and Facing Material for Pipe, Duct and Equipment Thermal Insulation.
- .4 Manufacturer's Trade Associations
 - .1 Thermal Insulation Association of Canada (TIAC): National Insulation Standards (Revised 2004).
- .5 Underwriters' Laboratories of Canada (ULC)
 - .1 CAN/ULC-S702-1997, Thermal Insulation, Mineral Fibre, for Buildings

1.3 DEFINITIONS

- .1 For purposes of this section:
 - .1 "CONCEALED" - insulated mechanical services in suspended ceilings and non-accessible chases and furred-in spaces.
 - .2 "EXPOSED" - will mean "not concealed" as specified.
- .2 TIAC ss:
 - .1 CRF: Code Rectangular Finish.
 - .2 CPF: Code Piping Finish.

1.4 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 00 10 00 – General Instructions.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 00 10 00 – General Instructions. Include product characteristics, performance criteria, and limitations.
- .3 Shop Drawings:
 - .1 Submit shop drawings in accordance with Section 00 10 00 – General Instructions.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with manufacturer's written instructions and Section 00 10 00 – General Instructions.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
 - .3 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .2 Storage and Protection:
 - .1 Protect from weather, construction traffic.
 - .2 Protect against damage.
 - .3 Store at temperatures and conditions required by manufacturer.
- .3 Waste Management and Disposal: in accordance with Section 00 10 00 – General Instructions.

PART 2 - PRODUCTS

2.1 FIRE AND SMOKE RATING

- .1 In accordance with CAN/ULC-S102.
 - .1 Maximum flame spread rating: 25.
 - .2 Maximum smoke developed rating: 50.

2.2 INSULATION

- .1 Mineral fibre specified includes glass fibre, rock wool, slag wool.
- .2 Thermal conductivity ("k" factor) not to exceed specified values at 24 degrees C mean temperature when tested in accordance with ASTM C335.

- .3 TIAC Code A-1: rigid moulded mineral fibre without factory applied vapour retarder jacket.
 - .1 Jacket shall be suitable to be painted with future latex paint.
 - .2 Mineral fibre: to CAN/ULC-S102-M88.
 - .3 Jacket: to CGSB 51-GP-9M, self-sealing lap.
 - .4 Temperature Range: 0 to 538°C.
 - .5 Maximum "k" factor: 0.033 W/m°C at 24°C to ASTM C335.

2.3 INSULATION SECUREMENT

- .1 Tape: self-adhesive, aluminum, plain, 50mm wide minimum.
- .2 Contact adhesive: quick setting.
- .3 Canvas adhesive: washable.
- .4 Single/double bands: stainless steel, 19mm wide, 0.5mm thick.
- .5 Wire mesh: 25mm hexagonal type 304 stainless steel wire mesh, tightly laced together at horizontal and circumferential mesh joints.

2.4 JACKETS

- .1 Polyvinyl Chloride (PVC):
 - .1 One-piece moulded type to CAN/CGSB-51.53 with pre-formed shapes as required.
 - .2 Colours: as indicated
 - .3 Minimum service temperature: -20°C
 - .4 Maximum service temperature: 65°C
 - .5 Moisture vapour transmission: 0.02 perm.
 - .6 Thickness: 0.3mm
 - .7 Fastenings:
 - .1 Use solvent weld adhesive compatible with insulation to seal laps and joints.
 - .2 Pressure sensitive vinyl tape of matching colour.
 - .8 Special requirements:
 - .1 Indoor: as indicated.

PART 3 - EXECUTION

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 PRE-INSTALLATION REQUIREMENT

- .1 Pressure testing of piping systems and adjacent equipment to be complete, witnessed and certified.
- .2 Piping to be inspected and approved by NRC.
- .3 Surfaces clean, dry, free from foreign material.

3.3 INSTALLATION

- .1 Install in accordance with TIAC National Standards.
- .2 Apply materials in accordance with manufacturers instructions and this specification.
- .3 Use two layers with staggered joints (minimal 400mm) when required nominal wall thickness exceeds 50mm.
- .4 Supports, Hangers:
 - .1 Apply high compressive strength insulation, suitable for service, at oversized saddles and shoes where insulation saddles have not been provided.

3.4 PIPING INSULATION SCHEDULES

- .1 Includes valves, valve bonnets, strainers, flanges and fittings unless otherwise specified.
- .2 TIAC Code: A-1.
 - .1 Securements: Bands, Tape at 300mm on centre.
 - .2 Seals: lap seal adhesive, lagging adhesive.
 - .3 Installation: TIAC Code 1501-H.
- .3 Thickness of insulation as listed in following table.
 - .1 Run-outs to individual units and equipment not exceeding 4000 mm long.
 - .2 Do not insulate exposed runouts to plumbing fixtures, chrome plated piping, valves, fittings.

Application	TIAC code	Pipe sizes (NPS) and insulation thickness (mm)			
		to 1	1 1/4 to 2	2 1/2 to 4	5 to 6
Hot Water Heating	A-1	25	38	38	38

- .4 Finishes:
 - .1 Exposed indoors: PVC jacket.
 - .2 Installation: to appropriate TIAC code CRF/1 through CPF/5.

3.5 CLEANING

- .1 Proceed in accordance with Section 00 10 00 – General Instructions.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

PART 1 - GENERAL

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 00 – Common Work Results for HVAC.
- .2 Section 23 05 05 – Installation of Pipework.
- .3 Section 23 05 93 – Testing, Adjusting and Balancing.
- .4 Section 23 05 23.01 – Valves – Bronze
- .5 Section 23 05 29 - Hangers and Supports for HVAC Piping and Equipment

1.2 REFERENCES

- .1 American Society of Mechanical Engineers (ASME)
 - .1 ASME B16.1-10, Gray Iron Pipe Flanges and Flanged Fittings: Classes 25, 125, and 250.
 - .2 ASME B16.3-06, Malleable Iron Threaded Fittings: Classes 150 and 300.
 - .3 ASME B16.5-09, Pipe Flanges and Flanged Fittings: NPS ½ through NPS 24 Metric/Inch Standard.
 - .4 ASME B18.2.1-10, Square Hex, Heavy Hex and Askew Head Bolts and Hex, Heavy Hex, Hex Flange. Loded Head and Lag Screws (Inch Series).
 - .5 ASME B18.2.2-10, Nuts for General Applications: Machine Screw Nuts, Hex, Square, Hex Flange, and Coupling Nuts (Inch Series).
- .2 ASTM International
 - .1 ASTM A47/A47M-99(2009), Standard Specification for Ferritic Malleable Iron Castings.
 - .2 ASTM A53/A53M-10, Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc Coated Welded and Seamless.
 - .3 ASTM A536-84(2009), Standard Specification for Ductile Iron Castings.
- .3 American National Standards Institute/American Water Works Association (ANSI/AWWA)
 - .1 ANSI/AWWA C111/A21.11-06, Standard for Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings.
- .4 CSA International
 - .1 CSA B242-05(R2011), Groove and Shoulder Type Mechanical Pipe Couplings.
 - .2 CSA W48-06, Filler Metals and Allied Materials for Metal Arc Welding.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 00 10 00 – General Instructions.
- .2 Product Data:
 - .1 Submit manufacturer’s instructions, printed product literature and data sheets for hydronic systems and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Indicate on drawings:
 - .1 Components and accessories.

1.4 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 00 10 00 – General Instructions.
- .2 Operation and Maintenance Data: submit operation and maintenance data for hydronic systems for incorporation into manual.
 - .1 Include special servicing requirements.

1.5 EXTRA STOCK MATERIALS

- .1 Supply spare parts as follows:
 - .1 Valve seas: 1 minimum for every ten valves, each size.
 - .2 Discs: 1 minimum for every ten valves, each size.
 - .3 Stem packing: 1 minimum for every ten valves, each size.
 - .4 Valve handles: 2 minimum of each size.
 - .5 Gaskets for flanges: 1 minimum for every ten flanges.

1.6 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 00 10 00 – General Instructions and with manufacturer’s written instructions.
- .2 Delivery and acceptance requirements: deliver materials to site in original factory packaging, labelled with manufacturer’s name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors and in accordance with manufacturer’s recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect hydronic systems from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.

- .4 Packaging Waste Management: in accordance with Section 00 10 00 – General Instructions.

PART 2 - PRODUCTS

2.1 PIPE

- .1 Steel pipe: to ASTM A53/A53M, Grade B, as follows:
 - .1 To NPS 6: Schedule 40.

2.2 PIPE JOINTS

- .1 NPS 2 and under: screwed fittings with PTFE tape.
- .2 NPS 2-1/2 and over: welding fittings and flanges to CSA W48.
- .3 Roll grooved: standard coupling to CSA B242.
- .4 Flanges: plain or raised face, slip-on to ANSI/AWWA C111/A21.11.
- .5 Orifice flanges: slip-on raised face, 2100 kPa.
- .6 Flange gaskets: to ANSI/AWWA C111/A21.11.
- .7 Pipe thread: taper.
- .8 Bolts and nuts: to ASME B18.2.1 and ASME B18.2.2.
- .9 Roll grooved coupling gaskets: type EPDM.

2.3 FITTINGS

- .1 Screwed fittings: malleable iron, to ASME B16.3, Class 150.
- .2 Pipe flanges and flanged fittings:
 - .1 Cast iron: to ASME B16.1, Class 125.
 - .2 Steel: to ASME B16.5
- .3 Butt-welding fittings: steel, to ASME B16.9
- .4 Unions: malleable iron, to ASTM A47/A47M and ASME B16.3.
- .5 Fittings for roll grooved piping: malleable iron to ASTM A47/A47M, ductile iron to ASTM A536.

2.4 VALVES

- .1 Connections:
 - .1 NPS 2 and smaller: screwed ends.
 - .2 NPS 2-1/2 and larger: flanged, grooved ends.
- .2 Balancing, for TAB:
 - .1 Sizes: calibrated balancing valves, as specified this section.
 - .2 NPS 2 and under: globe, as specified Section 23 05 23.01 - Valves - Bronze.
 - .3 Only Tour & Andersson (Victaulic) valves are accepted.
- .3 Drain valves: Ball, as specified in Section 23 05 23.01 – Valves – Bronze.
- .4 Ball valves:
 - .1 NPS 2 and under: as specified Section 23 05 23.01 - Valves - Bronze.

PART 3 - EXECUTION

3.1 PREPARATION

- .1 Lay out work in accordance with lines and grades as indicated.
- .2 Verify lines, levels, dimensions as indicated against established benchmarks. Report discrepancies to Departmental Representative and obtain written instruction.
- .3 When required by Departmental Representative, provide drawings showing relative locations of various services.

3.2 PIPING INSTALLATION

- .1 Install pipework in accordance with Section 23 05 05 - Installation of Pipe Work.

3.3 CIRCUIT BALANCING VALVES

- .1 Install flow balancing valves as indicated.
- .2 Remove handwheel after installation and when TAB is complete.
- .3 Tape joints in prefabricated insulation on valves installed in chilled water mains.

3.4 BALANCING

- .1 In accordance with Section 23 05 93 - Testing, Adjusting and Balancing for HVAC for applicable procedures.

3.5 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 00 10 00- General Instructions.
 - .1 Leave Work area clean at end of each day.

- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 00 10 00 – General Instructions.
- .3 Waste Management: in accordance with Section 00 10 00 – General Instructions.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

3.6 PROTECTION

- .1 Protect installed products and components from damage during construction.
- .2 Repair damage to adjacent materials caused by hydronic systems installation.

END OF SECTION

PART 1 - GENERAL

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 00 – Common Work Results for HVAC.

1.2 REFERENCES

- .1 ASTM International
 - .1 ASTM B62-09, Standard Specification for Composition Bronze or Ounce Metal Castings.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 00 10 00 – General Instructions.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for expansion tanks, air vents, separators, valves, and strainers and include product characteristics, performance criteria, physical size, finish and limitations.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 00 10 00 – General Instructions and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect hydronic specialties from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Packaging Waste Management: in accordance with Section 00 10 00 – General Instructions.

PART 2 - PRODUCTS

2.1 PIPE LINE STRAINER

- .1 NPS 1/2 to 2: bronze body to ASTM B62, screwed connections, Y pattern.
- .2 Blowdown connection: NPS 1.
- .3 Screen: stainless steel with 1.19 mm perforations.
- .4 Working pressure: 860 kPa.

PART 3 - EXECUTION

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contractors are acceptable for installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and data sheets.

3.3 GENERAL

- .1 Run drain lines to terminate above nearest drain.
- .2 Maintain adequate clearance to permit service and maintenance.
- .3 Should deviations beyond allowable clearances arise, request and follow Departmental Representative's directive.
- .4 Check shop drawings for conformance of tappings for ancillaries and for equipment operating weights.

3.4 STRAINERS

- .1 Install in horizontal or down flow lines.
- .2 Ensure clearance for removal of basket.

- .3 Install ahead of each pump.
- .4 Install ahead of each automatic control valve and as indicated.

3.5 AIR VENTS

- .1 Install at high points of systems.

3.6 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 00 10 00 – General Instructions.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 00 10 00 – General Instructions.
- .3 Waste Management: in accordance with Section 00 10 00 – General Instructions.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Materials and application of electric duct heaters.
- .2 Related Sections:
 - .1 Section 00 10 00 – General Instructions.
 - .2 Section 00 15 45 – General Safety Section and Fire Instructions.
 - .3 Section 26 05 00 - Common Work Results - for Electrical.

1.2 REFERENCES

- .1 Canadian Standards Association (CSA International).
 - .1 CSA C22.2 No.46, Electric Air-Heaters.
- .2 Department of Justice Canada (Jus).
 - .1 Canadian Environmental Protection Act, 1999, c. 33 (CEPA).
 - .2 Transportation of Dangerous Goods Act, 1992, c. 34 (TDGA).

1.3 SUBMITTALS

- .1 Make submittals in accordance with Section 00 10 00 – General Instructions.
- .2 Submit product data and include:
 - .1 Element support details.
 - .2 Heater: total kW rating, voltage, phase.
 - .3 Rating of stage: rating, voltage, phase.
 - .4 Heater element watt/density and maximum sheath temperature.
 - .5 Maximum discharge temperature.
 - .6 Physical size.
 - .7 Unit support.
 - .8 Performance limitations.
 - .9 Clearance from combustible materials.
 - .10 Internal components wiring diagrams.
 - .11 Minimum operating airflow.

1.4 QUALITY ASSURANCE

- .1 Health and Safety.
 - .1 Do construction occupational health and safety in accordance with Section 00 15 45 – General Safety Section and Fire Instructions.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Waste Management and Disposal:
 - .1 Remove from site and dispose of packaging materials at appropriate recycling facilities.
 - .2 Handle and dispose of hazardous materials in accordance with CEPA, TDGA, and Ottawa regulations.
 - .3 Ensure emptied containers are sealed and stored safely.

Part 2 Products

2.1 DUCT HEATERS

- .1 Duct heaters: insert type.
- .2 Elements:
 - .1 Helical coils of nickel chrome alloy resistance wire.
 - .2 Finned tubular.
 - .3 Incoloy sheathed.
- .3 Staging:
 - .1 Staged heaters: balanced line current at each stage.
 - .2 Each stage: uniform face distribution.
- .4 Maximum temperature at discharge: 32.2 degrees Celcius.
- .5 Controls:
 - .1 Factory mounted and wired in control box. Use terminal blocks for power and control wiring to thermostat and sail switch.
 - .2 Remote mounted as indicated with terminal strips in heater terminal box for power and control wiring.
 - .3 Controls mounted in a CSA enclosure and to include:
 - .1 Control transformers.
 - .2 SCR controller.
 - .4 Where controls are mounted in heater, exercise care in mounting contactors to minimize switching noise transmission through ductwork.
 - .5 High temperature cutout and air proving switch.
- .6 Electrical:
 - .1 Duct heater rating:
 - .1 7.5 kW.
 - .2 575 voltage.
 - .3 3 phase.
- .7 Main isolation disconnect switch.

Part 3 Execution

3.1 INSTALLATION

- .1 Make power and control connections to CSA C22.2 No.46.

3.2 FIELD QUALITY CONTROL

- .1 Perform tests in presence of NRC Representative.
 - .1 Provide test report and include copy with Operations and Maintenance Manuals.

END OF SECTION

PART 1 - GENERAL

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 00 – Common Work Results for HVAC.

1.2 REFERENCES

- .1 Institute of Boiler and Radiator Manufacturers (IBR)
- .2 US Department of Commerce
 - .1 CS 140-47, Commercial Standard.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 00 10 00 – General Instructions.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for finned tube radiation heaters and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Indicate on drawings:
 - .1 Equipment, capacity, piping, and connections.
 - .2 Dimensions, internal and external construction details, recommended method of installation with proposed structural steel support, sizes and location of mounting bolt holes.
 - .3 Special enclosures.
- .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.

1.4 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 00 10 00- General Instructions.
- .2 Operation and Maintenance Data: submit operation and maintenance data for finned tube radiation heaters for incorporation into manual.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 00 10 00 – General Instructions and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging,

labelled with manufacturer's name and address.

- .3 Storage and Handling Requirements:
 - .1 Store materials indoors and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect finned tube radiation heaters from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Packaging Waste Management: in accordance with Section 00 10 00 – General Instructions.

PART 2 - PRODUCTS

2.1 FINNED TUBE RADIATION

- .1 General:
 - .1 The available space for each piece of equipment must be verified on site.
 - .2 Provide minimum 100mm clearance at the bottom of enclosure to finished floor.
 - .3 Exposed parts to be cleaned and phosphate coated before applying the paint.
 - .4 Finish colors to be selected from manufacturer's standard colors during the coordination process.
- .2 Non-ferrous element:
 - .1 Element fin and tube size and number of rows to be provided as per plan schedule.
 - .2 Element to be fabricated with seamless copper tube with aluminum fins where the tube is mechanically expanded into the fin collars. Tube to be swaged at one end.
 - .3 Minimum tube thickness to be 0.025inches and fin thickness to be 0.020inches.
 - .4 Elements to be rated for minimum 200psi working pressure.
 - .5 Manufacturer to have IBR listed finned tube.
- .3 Support of enclosure and element
 - .1 Die formed brackets to be provided for support of element. Bracket to interface with enclosures as needed to suit with the given enclosure style.
 - .2 Support cradles to allow lateral movement for expansion and contraction.
 - .3 Provide nylon washers for silent operation.
 - .4 Hanger strip to be provided in 6-foot lengths, minimum 18ga steel.
 - .5 Hanger strip and panel interface shall be designed such that removal of the panels will not cause any surface scuffing to the wall above the hanger strip.
 - .6 Provide 20ga steel full back plate and gasketing.
- .4 Enclosures:
 - .1 All enclosure panels and overlapping end accessories to be fabricated from galvanealed steel.
 - .2 Enclosure style and height to be as per plan schedule.
 - .3 Enclosure panels to be minimum 14 gauge.
 - .4 Extruded aluminum anodized grille.
 - .5 Die formed stiffeners to be spot welded at each end of panel and accept an internal panel joiner at adjoining panels.

PART 3 - EXECUTION

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for finned tube radiation convector heater installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 INSTALLATION

- .1 Install in accordance with manufacturer's instructions.
- .2 Install in accordance with piping layout and reviewed shop drawings.
- .3 Provide for pipe movement during normal operation.
- .4 Maintain sufficient clearance to permit performance of service maintenance.
- .5 Check final location with Departmental Representative if different from that indicated prior to installation. Should deviations beyond allowable clearances arise, request and follow Departmental Representative's directive.
- .6 Valves:
 - .1 Install valves with stems upright or horizontal unless approved otherwise.
 - .2 Install isolating valves and balancing valves as indicated on drawings.
- .7 Venting:
 - .1 Install screwdriver vent on cabinet convector, terminating flush with surface of cabinet.
 - .2 Install automatic air vent on continuous finned tube radiation.
- .8 Clean finned tubes and comb straight.
- .9 Install flexible expansion compensators as indicated.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 00 10 00 – General Instructions.
 - .1 Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 00 10 00 – General Instructions.
- .3 Waste Management: in accordance with Section 00 10 00 – General Instructions.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

PART 1 - GENERAL

1.1 RELATED REQUIREMENTS

- .1 Section 23 05 00 – Common Work Results for HVAC.
- .2 Section 25 90 01 – EMCS: Site Requirements, Applications and Systems.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 00 10 00 – General Instructions.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for unit heaters and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Indicate on drawings:
 - .1 Equipment, capacity and piping connections.
 - .2 Dimensions, internal and external construction details, recommended method of installation with proposed structural steel support, sizes and location of mounting bolt holes.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 00 10 00 –General Instructions and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect unit heaters from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.
- .4 Packaging Waste Management: in accordance with Section 00 10 00 –General Instructions.

PART 2 - PRODUCTS

2.1 UNIT HEATERS

- .1 Cabinets:
 - .1 Cabinets are constructed from heavy duty cold-rolled corrosion-resistant steel finished in

- grey baked enamel.
- .2 Fronts have integral double-folded discharge frame for additional cabinet rigidity.
- .3 Back panels have integral inlet collars for superior stiffness.
- .4 Suspension tapping securely fastened to top panel.
- .2 Fans:
 - .1 Fans are designed and selected for high efficiency.
 - .2 Fans are statically and dynamically balanced for quiet, low vibration operation.
- .3 Motors:
 - .1 Standard motors at 115V/1/Ph/60Hz, totally enclosed, with automatic thermal overload protection.
 - .2 Standard motors shall be resilient mounted onto fan guards for quite, low-vibration operation.
 - .3 Provide non-fused disconnect switch.
 - .4 Provide relay to enable unit heater.
 - .5 Provide explosion proof motor for selected unit heaters identified on the drawings.
- .4 Diffusers;
 - .1 Unit to be equipped with horizontal louvres with individually adjustable blades.
 - .2 The optional louvre fin diffuser consists of vertically arranged, individually adjustable blades for maximum air distribution adaptability.
- .5 Coils:
 - .1 Standard coils are constructed from heavy gauge 5/8" outside diameter copper tube with mechanically bonded aluminum fins.
 - .2 Coils to be pressure tested at 350psig.
- .6 Control:
 - .1 Low limit aquastat strapped on to hot water heating supply set to prevent fan operating below 27 degrees C.
 - .2 Control thermostat: to be provided by Division 25.
 - .3 Provide all components required to accomplish sequence specified in Section 25 90 01 – EMCS: Site Requirements, Applications and Systems.

PART 3 - EXECUTION

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for unit heaters installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 INSTALLATION

- .1 Install in accordance with manufacturer's instructions.
- .2 Include double swing pipe joints as indicated.
- .3 Check final location with Departmental Representative if different from that indicated prior to installation.
 - .1 Should deviations beyond allowable clearances arise, request and follow Departmental Representative's directive.
- .4 Hot water units: for each unit, install isolation valve and balancing valve as indicated on drawings. Install drain valve at low point.
 - .1 Install manual air vent at high point.
- .5 Clean finned tubes and comb straight.
- .6 Provide supplementary suspension steel as required.
- .7 Install thermostats in locations indicated.
- .8 Before acceptance, set discharge patterns and fan speeds to suit requirements.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 00 10 00 – General Instructions.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 00 10 00 – General Instructions.
- .3 Waste Management: in accordance with Section 00 10 00 – General Instructions.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

3.4 PROTECTION

- .1 Protect installed products and components from damage during construction.
- .2 Repair damage to adjacent materials caused by unit heaters installation.

END OF SECTION

PART 1 - GENERAL

1.1 SUMMARY

- .1 Related Requirements
 - .1 Section 25 05 01 – EMCS: General Requirements.

1.2 DEFINITIONS

- .1 For additional acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.
- .2 AEL: ratio between total test period less any system downtime accumulated within that period and test period.
- .3 Downtime: results whenever EMCS is unable to fulfill required functions due to malfunction of equipment defined under responsibility of EMCS contractor. Downtime is measured by duration, in time, between time that Contractor is notified of failure and time system is restored to proper operating condition. Downtime not to include following:
 - .1 Outage of main power supply in excess of back-up power sources, provided that:
 - .1 Automatic initiation of back-up was accomplished.
 - .2 Automatic shut-down and re-start of components was as specified.
 - .2 Failure of communications link, provided that:
 - .1 Controller automatically and correctly operated in stand-alone mode.
 - .2 Failure was not due to failure of any specified EMCS equipment.
 - .3 Functional failure resulting from individual sensor inputs or output devices, provided that:
 - .1 System recorded said fault.
 - .2 Equipment defaulted to fail-safe mode.
 - .3 AEL of total of all input sensors and output devices is at least 99% during test period.

1.3 DESIGN REQUIREMENTS

- .1 Confirm with Departmental Representative that Design Criteria and Design Intents are still applicable.
- .2 Commissioning personnel to be fully aware of and qualified to interpret Design Criteria and Design Intents.

1.4 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals in accordance with Section 00 10 00 – General Instructions.
- .2 Final Report: submit report to Departmental Representative.
 - .1 Include measurements, final settings and certified test results.
 - .2 Bear signature of commissioning technician and supervisor
 - .3 Report format to be approved by Departmental Representative before commissioning is started.
 - .4 Revise "as-built" documentation, commissioning reports to reflect changes, adjustments and modifications to EMCS as set during commissioning and submit to Departmental Representative in accordance with Section 00 10 00 – General Instructions.
 - .5 Recommend additional changes and/or modifications deemed advisable in order to improve performance, environmental conditions or energy consumption.

1.5 CLOSEOUT SUBMITTALS

- .1 Provide documentation, O&M Manuals, and training of O&M personnel for review of Departmental Representative before interim acceptance in accordance with Section 00 10 00 – General Instructions.

1.6 COMMISSIONING

- .1 Carry out commissioning under direction of Departmental Representative and in presence of Departmental Representative.
- .2 Inform, and obtain approval from, Departmental Representative in writing at least 14 days prior to commissioning or each test. Indicate:
 - .1 Location and part of system to be tested or commissioned.
 - .2 Testing/commissioning procedures, anticipated results.
 - .3 Names of testing/commissioning personnel.
- .3 Correct deficiencies, re-test in presence of Departmental Representative until satisfactory performance is obtained.
- .4 Acceptance of tests will not relieve Contractor from responsibility for ensuring that complete systems meet every requirement of Contract.
- .5 Load system with project software.
- .6 Perform tests as required.

1.7 COMPLETION OF COMMISSIONING

- .1 Commissioning to be considered as satisfactorily completed when objectives of commissioning have been achieved and reviewed by Departmental Representative.

1.8 ISSUANCE OF FINAL CERTIFICATE OF COMPLETION

- .1 Final Certificate of Completion will not be issued until receipt of written approval indicating successful completion of specified commissioning activities including receipt of commissioning documentation.

PART 2 - PRODUCTS

2.1 EQUIPMENT

- .1 Provide sufficient instrumentation to verify and commission the installed system. Provide two-way radios.
- .2 Instrumentation accuracy tolerances: higher order of magnitude than equipment or system being tested.
- .3 Independent testing laboratory to certify test equipment as accurate to within approved tolerances no more than 2 months prior to tests.
- .4 Locations to be approved, readily accessible and readable.
- .5 Application: to conform to normal industry standards.

PART 3 - EXECUTION

3.1 PROCEDURES

- .1 Test each system independently and then in unison with other related systems.
- .2 Commission each system using procedures prescribed by the Departmental Representative.
- .3 Commission integrated systems using procedures prescribed by Departmental Representative.
- .4 Debug system software.
- .5 Optimize operation and performance of systems by fine-tuning PID values and modifying

CDLs as required.

- .6 Test full scale emergency evacuation and life safety procedures including operation and integrity of smoke management systems under normal and emergency power conditions as applicable.

3.2 FIELD QUALITY CONTROL

- .1 Pre-Installation Testing.
 - .1 General: consists of field tests of equipment just prior to installation.
 - .2 Testing may be on site or at Contractor's premises as approved by Departmental Representative.
 - .3 Configure major components to be tested in same architecture as designed system. Include BECC equipment and 2 sets of Building Controller's including MCU's, LCU's, and TCU's.
 - .4 Equip each Building Controller with sensor and controlled device of each type (AI, AO, DI, DO).
 - .5 In addition to test equipment, provide inclined manometer, digital micro-manometer, milli-amp meter, source of air pressure infinitely adjustable between 0 and 500 Pa, to hold steady at any setting and with direct output to miller-amp meter at source.
 - .6 After setting, test zero and span in 10 % increments through entire range while both increasing and decreasing pressure.
 - .7 Departmental Representative to mark instruments tracking within 0.5% in both directions as "approved for installation".
 - .8 Transmitters above 0.5% error will be rejected.
 - .9 DP switches to open and close within 2% of setpoint.
- .2 Completion Testing.
 - .1 General: test after installation of each part of system and after completion of mechanical and electrical hook-ups, to verify correct installation and functioning.
 - .2 Include following activities:
 - .1 Test and calibrate field hardware including stand-alone capability of each controller.
 - .2 Verify each A-to-D convertor.
 - .3 Test and calibrate each AI using calibrated digital instruments.
 - .4 Test each DI to ensure proper settings and switching contacts.
 - .5 Test each DO to ensure proper operation and lag time.
 - .6 Test each AO to ensure proper operation of controlled devices. Verify tight closure and signals.
 - .7 Test operating software.
 - .8 Test application software and provide samples of logs and commands.
 - .9 Debug software.
 - .10 Provide point verification list in table format including point identifier, point identifier expansion, point type and address, low and high limits and engineering units. Include space on

commissioning technician and Departmental Representative.
This document will be used in final startup testing.

- .3 Final Startup Testing: Upon satisfactory completion of tests, perform point-by-point test of entire system under direction of Departmental Representative and provide:
 - .1 1 technical personnel capable of re-calibrating field hardware and modifying software.
 - .2 Detailed daily schedule showing items to be tested and personnel available.
 - .3 Departmental Representative's acceptance signature to be on executive and applications programs.
 - .4 Commissioning to commence during final startup testing.
 - .5 O&M personnel to assist in commissioning procedures as part of training.
 - .6 Commissioning to be supervised by qualified supervisory personnel and Departmental Representative.
 - .7 Commission systems considered as life safety systems before affected parts of the facility are occupied.
 - .8 Operate systems as long as necessary to commission entire project.
 - .9 Monitor progress and keep detailed records of activities and results.

- .4 Final Operational Testing: to demonstrate that EMCS functions in accordance with contract requirements.
 - .1 Prior to beginning of 30 day test demonstrate that operating parameters (setpoints, alarm limits, operating control software, sequences of operation, trends, graphics and CDL's) have been implemented to ensure proper operation and operator notification in event of off-normal operation.
 - .1 Repetitive alarm conditions to be resolved to minimize reporting of nuisance conditions.
 - .2 Test to last at least 30 consecutive 24 hour days.
 - .3 Tests to include:
 - .1 Demonstration of correct operation of monitored and controlled points.
 - .2 Operation and capabilities of sequences, reports, special control algorithms, diagnostics, software.
 - .4 System will be accepted when:
 - .1 EMCS equipment operates to meet overall performance requirements. Downtime as defined in this Section must not exceed allowable time calculated for this site.
 - .2 Requirements of Contract have been met.
 - .5 In event of failure to attain specified AEL during test period, extend test period on day-to-day basis until specified AEL is attained for test period.
 - .6 Correct defects when they occur and before resuming tests.

- .2 Departmental Representative to verify reported results.

3.3 ADJUSTING

- .1 Final adjusting: upon completion of commissioning as reviewed by Departmental Representative, set and lock devices in final position and permanently mark settings.

3.4 DEMONSTRATION

- .1 Demonstrate to Departmental Representative operation of systems including sequence of operations in regular and emergency modes, under normal and emergency conditions, start-up, shut-down interlocks and lock-outs.

END OF SECTION

PART 1 - GENERAL

1.1 REFERENCES

- .1 American National Standards Institute (ANSI)/The Instrumentation, Systems and Automation Society (ISA).
 - .1 ANSI/ISA 5.5-1985, Graphic Symbols for Process Displays.
- .2 American National Standards Institute (ANSI)/ Institute of Electrical and Electronics Engineers (IEEE).
 - .1 ANSI/IEEE 260.1-1993, American National Standard Letter Symbols Units of Measurement (SI Units, Customary Inch-Pound Units, and Certain Other Units).
- .3 American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE).
 - .1 ASHRAE STD 135-R2001, BACNET - Data Communication Protocol for Building Automation and Control Network.
- .4 Canadian Standards Association (CSA International).
 - .1 CAN/CSA-Z234.1-89(R1995), Canadian Metric Practice Guide.
- .5 Consumer Electronics Association (CEA).
 - .1 CEA-709.1-B-2002, Control Network Protocol Specification.
- .6 Department of Justice Canada (Jus).
 - .1 Canadian Environmental Assessment Act (CEAA), 1995, c. 37.
 - .2 Canadian Environmental Protection Act (CEPA), 1999, c. 33.
- .7 Electrical and Electronic Manufacturers Association (EEMAC).
 - .1 EEMAC 2Y-1-1958, Light Gray Colour for Indoor Switch Gear.
- .8 Health Canada/Workplace Hazardous Materials Information System (WHMIS).
 - .1 Material Safety Data Sheets (MSDS).
- .9 Transport Canada (TC).
 - .1 Transportation of Dangerous Goods Act (TDGA), 1992, c. 34.

1.2 DESIGNATED CONTRACTOR

- .1 Hire the services of Ainsworth to complete the work of all EMCS sections.

1.3 ACRONYMS AND ABBREVIATIONS

- .1 Acronyms used in EMCS:
 - .1 AEL - Average Effectiveness Level.
 - .2 AI - Analog Input.

- .3 AIT - Agreement on International Trade.
- .4 AO - Analog Output.
- .5 BACnet - Building Automation and Control Network.
- .6 BC(s) - Building Controller(s).
- .7 BECC - Building Environmental Control Center.
- .8 CAD - Computer Aided Design.
- .9 CDL - Control Description Logic.
- .10 CDS - Control Design Schematic.
- .11 COSV - Change of State or Value.
- .12 CPU - Central Processing Unit.
- .13 DI - Digital Input.
- .14 DO - Digital Output.
- .15 DP - Differential Pressure.
- .16 ECU - Equipment Control Unit.
- .17 EMCS - Energy Monitoring and Control System.
- .18 HVAC - Heating, Ventilation, Air Conditioning.
- .19 IDE - Interface Device Equipment.
- .20 I/O - Input/Output.
- .21 ISA - Industry Standard Architecture.
- .22 LAN - Local Area Network.
- .23 LCU - Local Control Unit.
- .24 MCU - Master Control Unit.
- .25 NAFTA - North American Free Trade Agreement.
- .26 NC - Normally Closed.
- .27 NO - Normally Open.
- .28 OS - Operating System.
- .29 O&M - Operation and Maintenance.
- .30 OWS - Operator Work Station.
- .31 PC - Personal Computer.
- .32 PCI - Peripheral Control Interface.
- .33 PCMCIA - Personal Computer Micro-Card Interface Adapter.
- .34 PID - Proportional, Integral and Derivative.
- .35 RAM - Random Access Memory.
- .36 SP - Static Pressure.
- .37 ROM - Read Only Memory.
- .38 TCU - Terminal Control Unit.
- .39 USB - Universal Serial Bus.
- .40 UPS - Uninterruptible Power Supply.
- .41 VAV - Variable Air Volume.

1.4 DEFINITIONS

- .1 Point: may be logical or physical.
 - .1 Logical points: values calculated by system such as setpoints, totals, counts, derived corrections and may include, but not limited to result of and statements in CDL's.
 - .2 Physical points: inputs or outputs which have hardware wired to controllers which are measuring physical properties, or providing status conditions of

contacts or relays which provide interaction with related equipment (stop, start) and valve or damper actuators.

- .2 Point Name: composed of two parts, point identifier and point expansion.
 - .1 Point identifier: comprised of three descriptors, "area" descriptor, "system" descriptor and "point" descriptor, for which database to provide 25 character field for each point identifier. "System" is system that point is located on.
 - .1 Area descriptor: building or part of building where point is located.
 - .2 System descriptor: system that point is located on.
 - .3 Point descriptor: physical or logical point description. For point identifier "area", "system" and "point" will be shortforms or acronyms. Database must provide 25 character field for each point identifier.
 - .2 Point expansion: comprised of three fields, one for each descriptor. Expanded form of shortform or acronym used in "area", "system" and "point" descriptors is placed into appropriate point expansion field. Database must provide 32 character field for each point expansion.
 - .3 Bilingual systems to include additional point identifier expansion fields of equal capacity for each point name for second language.
 - .1 System to support use of numbers and readable characters including blanks, periods or underscores to enhance user readability for each of the above strings.
- .3 Point Object Type: points fall into following object types:
 - .1 AI (analog input).
 - .2 AO (analog output).
 - .3 DI (digital input).
 - .4 DO (digital output).
 - .5 Pulse inputs.
- .4 Symbols and engineering unit abbreviations utilized in displays: to ANSI/ISA S5.5.
 - .1 Printouts: to ANSI/IEEE 260.1.
 - .2 Refer also to Section 25 05 54 - EMCS: Identification.

1.5 SYSTEM DESCRIPTION

- .1 Refer to control schematics for system architecture.
- .2 Work covered by sections referred to above consists of fully operational EMCS, including, but not limited to, following:
 - .1 Building Controllers.
 - .2 Control devices as listed in I/O point summary tables.
 - .3 Data communications equipment necessary to effect EMCS data transmission system.
 - .4 Field control devices.
 - .5 Software/Hardware complete with full documentation.
 - .6 Complete operating and maintenance manuals.
 - .7 Training of personnel.
 - .8 Acceptance tests, technical support during commissioning, full documentation.
 - .9 Wiring interface co-ordination of equipment supplied by others.

- .10 Miscellaneous work as specified in these sections and as indicated.
- .3 Design Requirements:
 - .1 Design and provide conduit and wiring linking elements of system.
 - .2 Supply sufficient programmable controllers of types to meet project requirements. Quantity and points contents as reviewed by Departmental Representative prior to installation.
 - .3 Location of controllers as reviewed by Departmental Representative prior to installation.
 - .4 Provide utility power to EMCS as indicated.
 - .5 Metric references: in accordance with CAN/CSA Z234.1.
- .4 Language Operating Requirements:
 - .1 Provide English operator selectable access codes.
 - .2 Use non-linguistic symbols for displays on graphic terminals wherever possible. Other information to be in English.
 - .3 Operating system executive: provide primary hardware-to-software interface with associated documentation to be in English.
 - .4 System manager software: include in English system definition point database, additions, deletions or modifications, control loop statements, use of high level programming languages, report generator utility and other OS utilities used for maintaining optimal operating efficiency.
 - .5 Include, in English:
 - .1 Input and output commands and messages from operator-initiated functions, field related changes, alarms as defined in CDL's or assigned limits (i.e. commands relating to day-to-day operating functions and not related to system modifications, additions, or logic re-definitions).
 - .2 Graphic "display" functions, point commands to turn systems on or off, manually override automatic control of specified hardware points. To be in English at specified OWS and to be able to operate one terminal in English and second in French. Point name expansions in both languages.
 - .3 Reporting function such as trend log, trend graphics, alarm report logs, energy report logs, maintenance generated logs.

1.6 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Make submittals in accordance with Section 00 10 00 – General Instructions and 25 05 02 - EMCS: Shop Drawings, Product Data and Review Process.
- .2 Submit for review:
 - .1 Equipment list and systems manufacturers within 10 days after award of contract.
- .3 Quality Control:
 - .1 Provide equipment and material from manufacturer's regular production, CSA certified, manufactured to standard quoted plus additional specified requirements.
 - .2 Where CSA certified equipment is not available submit such equipment to inspection authorities for special inspection and approval before delivery to site.
 - .3 Submit proof of compliance to specified standards with shop drawings and product data in accordance with Section 25 05 02 - EMCS: Shop Drawings,

Product Data and Review Process. Label or listing of specified organization is acceptable evidence.

- .4 In lieu of such evidence, submit certificate from testing organization, approved by Departmental Representative, certifying that item was tested in accordance with their test methods and that item conforms to their standard/code.
- .5 For materials whose compliance with organizational standards/codes/specifications is not regulated by organization using its own listing or label as proof of compliance, furnish certificate stating that material complies with applicable referenced standard or specification.
- .6 Submit certificate of acceptance from authority having jurisdiction to Departmental Representative.
- .7 Existing devices intended for re-use: submit test report.

1.7 DELIVERY, STORAGE AND HANDLING

- .1 Material Delivery Schedule: provide Departmental Representative with schedule within 2 weeks after award of Contract.
- .2 Waste Management and Disposal:
 - .1 Separate waste materials in accordance with Section 00 10 00 – General Instructions.
 - .2 Remove from site and dispose of packaging materials at appropriate recycling facilities.

1.8 EXISTING- CONTROL COMPONENTS

- .1 Utilize existing control wiring as indicated.
- .2 Re-use field control devices that are usable in their original configuration provided that they conform to applicable codes, standards specifications.
 - .1 Do not modify original design of existing devices without written permission from Departmental Representative.
 - .2 Provide for new, properly designed device where re-usability of components is uncertain.
- .3 Inspect and test existing devices intended for re-use within 30 days of award of contract, and prior to installation of new devices.
 - .1 Furnish test report within 40 days of award of contract listing each component to be re-used and indicating whether it is in good order or requires repair by Departmental Representative.
 - .2 Failure to produce test report will constitute acceptance of existing devices by contractor.
- .4 Non-functioning items:
 - .1 Provide with report specification sheets or written functional requirements to support findings.
 - .2 Departmental Representative will repair or replace existing items judged defective yet deemed necessary for EMCS.

- .5 Submit written request for permission to disconnect controls and to obtain equipment downtime before proceeding with Work.
- .6 Assume responsibility for controls to be incorporated into EMCS after written receipt of approval from Departmental Representative.
 - .1 Be responsible for items repaired or replaced by Departmental Representative.
 - .2 Be responsible for repair costs due to negligence or abuse of equipment.
 - .3 Responsibility for existing devices terminates upon final acceptance of applicable portions of EMCS as approved by Departmental Representative.
- .7 Remove existing controls not re-used or not required. Place in approved storage for disposition as directed.

PART 2 - PRODUCTS

2.1 EQUIPMENT

- .1 There is an existing Ainsworth system presently installed in the building. All materials must be selected to ensure compatibility with the existing systems.
- .2 Control Network Protocol and Data Communication Protocol: to ASHRAE STD 135.
- .3 Complete list of equipment and materials to be used on project and forming part of tender documents by adding manufacturer's name, model number and details of materials, and submit for approval.

2.2 ADAPTORS

- .1 Provide adaptors between metric and imperial components.

PART 3 - EXECUTION

3.1 MANUFACTURER'S RECOMMENDATIONS

- .1 Installation: to manufacturer's recommendations.

END OF SECTION

PART 1 - GENERAL

1.1 DEFINITIONS

- .1 Acronyms and definitions: refer to Section 25 05 01 - EMCS: General Requirements.

1.2 DESIGN REQUIREMENTS

- .1 Preliminary Design Review: to contain following contractor and systems information.
 - .1 Location of local office.
 - .2 Description and location of installing and servicing technical staff.
 - .2 Location and qualifications of programming design and programming support staff.
 - .3 List of spare parts.
 - .4 Location of spare parts stock.
 - .5 Names of sub-contractors and site-specific key personnel.
 - .6 Sketch of site-specific system architecture.
 - .7 Specification sheets for each item including memory provided, programming language, speed, type of data transmission.
 - .8 Descriptive brochures.
 - .9 Sample CDL and graphics (systems schematics).
 - .10 Response time for each type of command and report.
 - .11 Item-by-item statement of compliance.
 - .12 Proof of demonstrated ability of system to communicate utilizing BACnet.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals in accordance with Section 00 10 00 – General Instructions and coordinate with requirements in this Section.
- .2 Submit preliminary design document within 5 working days after contract award, for review by Departmental Representative.
- .3 Shop Drawings to consist of 3 hard copies and 1 soft copy of design documents, shop drawings, product data and software.
- .4 Hard copy to be completely indexed and coordinated package to assure compliance with contract requirements and arranged in same sequence as specification and cross-referenced to specification section and paragraph number.
- .5 Soft copy to be in AutoCAD - latest version and Microsoft Word latest version format, structured using menu format for easy loading and retrieval on OWS.

1.4 PRELIMINARY SHOP DRAWING REVIEW

- .1 Submit preliminary shop drawings within 30 working days of award of contract and include following:
 - .1 Specification sheets for each item. To include manufacturer's descriptive literature, manufacturer's installation recommendations, specifications, drawings, diagrams, performance and characteristic curves, catalogue cuts, manufacturer's name, trade name, catalogue or model number, nameplate data, size, layout, dimensions, capacity, other data to establish compliance.
 - .2 Detailed system architecture showing all points associated with each controller including signal levels, pressures where new EMCS ties into existing control equipment.
 - .3 Spare point capacity of each controller by number and type.
 - .4 Controller locations.
 - .5 Auxiliary control cabinet locations.
 - .6 Single line diagrams showing cable routings, conduit sizes, spare conduit capacity between control centre, field controllers and systems being controlled.
 - .7 Valves: complete schedule listing including following information: designation, service, manufacturer, model, point ID, design flow rate, design pressure drop, required Cv, Valve size, actual Cv, spring range, pilot range, required torque, actual torque and close off pressure (required and actual).

1.5 DETAILED SHOP DRAWING REVIEW

- .1 Submit detailed shop drawings within 60 working days after award of contract and before start of installation and include following:
 - .1 Corrected and updated versions (hard copy only) of submissions made during preliminary review.
 - .2 Wiring diagrams.
 - .3 Piping diagrams and hook-ups.
 - .4 Interface wiring diagrams showing termination connections and signal levels for equipment to be supplied by others.
 - .5 Shop drawings for each input/output point, sensors, transmitters, showing information associated with each particular point including:
 - .1 Sensing element type and location.
 - .2 Transmitter type and range.
 - .3 Associated field wiring schematics, schedules and terminations.
 - .4 Complete Point Name Lists.
 - .5 Setpoints, curves or graphs and alarm limits (high and low, 3 types critical, cautionary and maintenance), signal range.
 - .6 Software and programming details associated with each point.
 - .7 Manufacturer's recommended installation instructions and procedures.
 - .8 Input and output signal levels or pressures where new system ties into existing control equipment.
 - .6 Control schematics, narrative description, CDL's fully showing and describing automatic and manual procedure required to achieve proper operation of project, including under complete failure of EMCS.
 - .7 Graphic system schematic displays of air and water systems with point identifiers

- and textual description of system, and typical floor plans as specified.
- .8 Complete system CDL's including companion English language explanations on same sheet but with different font and italics. CDL's to contain specified energy optimization programs.
- .9 Listing and example of specified reports.
- .10 Listing of time of day schedules.
- .11 Mark up to-scale construction drawing to detail control room showing location of equipment and operator work space.
- .12 Type and size of memory with statement of spare memory capacity.
- .13 Full description of software programs provided.
- .14 Sample of "Operating Instructions Manual" to be used for training purposes.
- .15 Outline of proposed start-up and verification procedures. Refer to Section 25 01 11 - EMCS: Start-up, Verification and Commissioning.

1.6 QUALITY ASSURANCE

- .1 Preliminary Design Review Meeting: Convene meeting within 45 working days of award of contract to:
 - .1 Undertake functional review of preliminary design documents, resolve inconsistencies.
 - .2 Resolve conflicts between contract document requirements and actual items (e.g.: points list inconsistencies).
 - .3 Review interface requirements of materials supplied by others.
 - .4 Review "Sequence of Operations".
- .2 Contractor's programmer to attend meeting.
- .3 Departmental Representative retains right to revise sequence or subsequent CDL prior to software finalization without cost to Departmental Representative.

PART 2 - PRODUCTS

2.1 NOT USED

- .1 Not Used.

PART 3 - EXECUTION

3.1 NOT USED

- .1 Not Used.

NRC-CNRC
Project No.
S77-6032

Section 25 05 02
EMCS: SUBMITTALS AND REVIEW PROCESS
Page 4 of 4

END OF SECTION

PART 1 - GENERAL

1.1 SUMMARY

- .1 Related Requirements
 - .1 Section 25 05 01 – EMCS: General Requirements.

1.2 REFERENCES

- .1 Canadian Standards Association (CSA International).
 - .1 CSA C22.1-2015, The Canadian Electrical Code, Part I (19th Edition), Safety Standard for Electrical Installations.

1.3 DEFINITIONS

- .1 For acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.

1.4 SYSTEM DESCRIPTION

- .1 Language Operating Requirements: provide identification for control items in English.

1.5 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals in accordance with Section 00 10 00 – General Instructions supplemented and modified by requirements of this Section.
- .2 Submit to Departmental Representative for approval samples of nameplates, identification tags and list of proposed wording.

PART 2 - PRODUCTS

2.1 NAMEPLATES FOR PANELS

- .1 Identify by Plastic laminate, 3 mm thick, matt white finish, black core, square corners, lettering accurately aligned and engraved into core.
- .2 Sizes: 25 x 67 mm minimum.
- .3 Lettering: minimum 7 mm high, black.
- .4 Inscriptions: machine engraved to identify function.

2.2 NAMEPLATES FOR FIELD DEVICES

- .1 Identify by plastic encased cards attached by chain.
- .2 Sizes: 50 x 100 mm minimum.
- .3 Lettering: minimum 5 mm high produced from laser printer in black.
- .4 Data to include: point name and point address.
- .5 Companion cabinet: identify interior components using plastic enclosed cards with point name and point address.

2.3 WARNING SIGNS

- .1 Equipment including motors, starters under remote automatic control: supply and install orange coloured signs warning of automatic starting under control of EMCS.
- .2 Sign to read: "Caution: This equipment is under automatic remote control of EMCS" as reviewed by Departmental Representative's.

2.4 WIRING

- .1 Supply and install numbered tape markings on wiring at panels, junction boxes, splitters, cabinets and outlet boxes.
- .2 Colour coding: to CSA C22.1. Use colour coded wiring in communications cables, matched throughout system.
- .3 Power wiring: identify circuit breaker panel/circuit breaker number inside each EMCS panel.

2.5 CONDUIT

- .1 Colour code EMCS conduit.
- .2 Pre-paint box covers and conduit fittings.
- .3 Coding: use fluorescent orange paint and confirm colour with Departmental Representative during "Preliminary Design Review".

PART 3 - EXECUTION

3.1 NAMEPLATES AND LABELS

- .1 Ensure that manufacturer's nameplates, CSA labels and identification nameplates are

visible and legible at all times.

3.2 EXISTING PANELS

- .1 Correct existing nameplates and legends to reflect changes made during Work.

END OF SECTION

PART 1 - GENERAL

1.1 SUMMARY

- .1 Related Requirements
 - .1 Section 25 05 01 – EMCS: General Requirements.
- .2 References.
 - .1 Canada Labour Code (R.S. 1985, c. L-2)/Part I - Industrial Relations.
 - .2 Canadian Standards Association (CSA International).
 - .1 CSA Z204-94(R1999), Guidelines for Managing Indoor Air Quality in Office Buildings.

1.2 DEFINITIONS

- .1 BC(s) - Building Controller(s).
- .2 OWS - Operator Work Station.
- .3 For additional acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals in accordance with Section 00 10 00 – General Instructions.
- .2 Submit detailed preventative maintenance schedule for system components to Departmental Representative.
- .3 Submit detailed inspection reports to Departmental Representative.
- .4 Submit dated, maintenance task lists to Departmental Representative and include the following sensor and output point detail, as proof of system verification:
 - .1 Point name and location.
 - .2 Device type and range.
 - .3 Measured value.
 - .4 System displayed value.
 - .5 Calibration detail
 - .6 Indication if adjustment required,
 - .7 Other action taken or recommended.
- .5 Submit network analysis report showing results with detailed recommendations to correct problems found.
- .6 Records and logs: in accordance with Section 00 10 00 – General Instructions.
 - .1 Maintain records and logs of each maintenance task on site.

- .2 Organize cumulative records for each major component and for entire EMCS chronologically.
- .3 Submit records to Departmental Representative, after inspection indicating that planned and systematic maintenance have been accomplished.

- .7 Revise and submit to Departmental Representative in accordance with Section 00 10 00 – General Instructions "As-built drawings" documentation and commissioning reports to reflect changes, adjustments and modifications to EMCS made during warranty period.

1.4 MAINTENANCE SERVICE DURING WARRANTY PERIOD

- .1 Provide services, materials, and equipment to maintain EMCS for specified warranty period. Provide detailed preventative maintenance schedule for system components as described in Submittal article.
- .2 Emergency Service Calls:
 - .1 Initiate service calls when EMCS is not functioning correctly.
 - .2 Qualified control personnel to be available during warranty period to provide service to "CRITICAL" components whenever required at no extra cost.
 - .3 Furnish Departmental Representative with telephone number where service personnel may be reached at any time.
 - .4 Service personnel to be on site ready to service EMCS [within 2 hours] after receiving request for service.
 - .5 Perform Work continuously until EMCS restored to reliable operating condition.
- .3 Operation: foregoing and other servicing to provide proper sequencing of equipment and satisfactory operation of EMCS based on original design conditions and as recommended by manufacturer.
- .4 Work requests: record each service call request, when received separately on approved form and include:
 - .1 Serial number identifying component involved.
 - .2 Location, date and time call received.
 - .3 Nature of trouble.
 - .4 Names of personnel assigned.
 - .5 Instructions of work to be done.
 - .6 Amount and nature of materials used.
 - .7 Time and date work started.
 - .8 Time and date of completion.
- .5 Provide system modifications in writing.
 - .1 No system modification, including operating parameters and control settings, to be made without prior written approval of Departmental Representative.

PART 2- PRODUCTS

2.1 NOT USED

- .1 Not Used.

PART 3 - EXECUTION

3.1 FIELD QUALITY CONTROL

- .1 Perform as minimum (3) three minor inspections and one major inspection (more often if required by manufacturer) per year. Provide detailed written report to Departmental Representative as described in Submittal article.
- .2 Perform inspections during regular working hours, 0800 to 1630 h, Monday through Friday, excluding statutory holidays.
- .3 Following inspections are minimum requirements and should not be interpreted to mean satisfactory performance:
 - .1 Perform calibrations using test equipment having traceable, certifiable accuracy at minimum 50% greater than accuracy of system displaying or logging value.
 - .2 Check each field input/output device in accordance with Canada Labour Code - Part I and CSA Z204.
 - .3 Provide dated, maintenance task lists, as described in Submittal article, as proof of execution of complete system verification.
- .4 Minor inspections to include, but not limited to:
 - .1 Perform visual, operational checks to BC's, peripheral equipment, interface equipment and other panels.
 - .2 Check equipment cooling fans as required.
 - .3 Visually check for mechanical faults, air leaks and proper pressure settings on pneumatic components.
 - .4 Review system performance with Operations Supervisor to discuss suggested or required changes.
- .5 Major inspections to include, but not limited to:
 - .1 Minor inspection.
 - .2 Clean OWS(s) peripheral equipment, BC(s), interface and other panels, micro-processor interior and exterior surfaces.
 - .3 Check signal, voltage and system isolation of BC(s), peripherals, interface and other panels.
 - .4 Verify calibration/accuracy of each input and output device and recalibrate or replace as required.
 - .5 Provide mechanical adjustments, and necessary maintenance on printers.
 - .6 Run system software diagnostics as required.
 - .7 Install software and firmware enhancements to ensure components are operating at most current revision for maximum capability and reliability.
 - .1 Perform network analysis and provide report as described in Submittal article.

- .6 Rectify deficiencies revealed by maintenance inspections and environmental checks.
- .7 Continue system debugging and optimization.
- .8 Testing/verification of occupancy and seasonal-sensitive systems to take place during four (4) consecutive seasons, after facility has been accepted, taken over and fully occupied.
 - .1 Test weather-sensitive systems twice: first at near winter design conditions and secondly under near summer design conditions.

END OF SECTION

PART 1 - GENERAL

1.1 SUMMARY

- .1 Related Requirements
 - .1 Section 25 05 01 – EMCS: General Requirements.

1.2 REFERENCES

- .1 Canadian Standards Association (CSA International).
 - .1 CSA T529-95(R2000), Telecommunications Cabling Systems in Commercial Buildings (Adopted ANSI/TIA/EIA-568-A with modifications).
 - .2 CSA T530-99(R2004), Commercial Building Standard for Telecommunications Pathways and Spaces (Adopted ANSI/TIA/EIA-569-A with modifications).
- .2 Institute of Electrical and Electronics Engineers (IEEE)/Standard for Information technology - Telecommunications and information exchange between systems - Local and metropolitan area networks - Specific requirements.
 - .1 IEEE Std 802.3TM -2002, Part 3: Carrier sense multiple access with collision detection (CSMA/CD) access method and physical layer specifications.
- .3 Telecommunications Industries Association (TIA)/Electronic Industries Alliance (EIA)
 - .1 TIA/EIA-568, Commercial Building Telecommunications Cabling Standards Set, Part 1 General Requirements Part 2 Balanced Twisted-Pair Cabling Components Part 3 Optical Fiber Cabling Components Standard.
 - .2 TIA/EIA-569-A, Commercial Building Standard for Telecommunications Pathways and Spaces.
- .4 Treasury Board Information Technology Standard (TBITS).
 - .1 TBITS 6.9-2000, Profile for the Telecommunications Wiring System in Government Owned and Leased Buildings - Technical Specifications.

1.3 DEFINITIONS

- .1 Acronyms and definitions: refer to Section 25 05 01 - EMCS - General Requirements.

1.4 SYSTEM DESCRIPTION

- .1 Data communication network to link Operator Workstations and Master Control Units (MCU) in accordance with CSA T530.
 - .1 Provide reliable and secure connectivity of adequate performance between different sections (segments) of network.
 - .2 Allow for future expansion of network, with selection of networking technology and communication protocols.

- .2 Data communication network to include, but not limited to:
 - .1 EMCS-LAN.
 - .2 Modems.
 - .3 Network interface cards.
 - .4 Network management hardware and software.
 - .5 Network components necessary for complete network.

1.5 DESIGN REQUIREMENTS

- .1 EMCS Local Area Network (EMCS-LAN).
 - .1 High speed, high performance, local area network over which MCUs and OWSs communicate with each other directly on peer to peer basis in accordance with IEEE 802.3/Ethernet Standard.
 - .1 EMCS-LAN to: BACnet.
 - .2 Each EMCS-LAN to be capable of supporting at least 50 devices.
 - .3 Support of combination of MCUs and OWSs directly connected to EMCS-LAN.
 - .4 High speed data transfer rates for alarm reporting, quick report generation from multiple controllers, upload/download information between network devices. Bit rate to be 10 Megabits per second minimum.
 - .5 Detection and accommodation of single or multiple failures of either OWSs, MCUs or network media. Operational equipment to continue to perform designated functions effectively in event of single or multiple failures.
 - .6 Commonly available, multiple sourced, networking components and protocols to allow system to co-exist with other networking applications including office automation.
- .2 Dynamic Data Access.
 - .1 LAN to provide capabilities for OWSs, either network resident or connected remotely, to access point status and application report data or execute control functions for other devices via LAN.
 - .2 Access to data to be based upon logical identification of building equipment.
- .3 Network Medium.
 - .1 Network medium: twisted cable, compatible with network protocol to be used within buildings.

PART 2 - PRODUCTS

2.1 NOT USED

- .1 Not Used.

NRC-CNRC
Project No.
S77-6032

Section 25 10 01
EMCS: LOCAL AREA NETWORK (LAN)
Page 3 of 3

PART 3 - EXECUTION

3.1 NOT USED

.1 Not Used.

END OF SECTION

PART 1 - GENERAL

1.1 SUMMARY

- .1 Related Requirements
 - .1 Section 25 05 01 – EMCS – General Requirements.
 - .2 Section 25 05 02 - EMCS: Shop Drawings, Product Data and Review Process.
 - .3 Section 25 05 03 - EMCS: Project Record Documents.

1.2 REFERENCES

- .1 American Society of Heating, Refrigeration and Air-Conditioning Engineers, Inc. (ASHRAE).
 - .1 ASHRAE 2003, Applications Handbook, SI Edition.
- .2 Canadian Standards Association (CSA International).
 - .1 C22.2 No.205-M1983(R1999), Signal Equipment.
- .3 Institute of Electrical and Electronics Engineers (IEEE).
 - .1 IEEE C37.90.1-02, Surge Withstand Capabilities (SWC) Tests for Relays and Relay Systems Associated with Electric Power Apparatus.
- .4 Public Works and Government Services Canada (PWGSC)/Real Property Branch/Architectural and Engineering Services.
 - .1 MD13800, Energy Management and Control Systems (EMCS) Design Manual. English: <ftp://ftp.pwgsc.gc.ca/rps/doccentre/mechanical/me214-e.pdf>

1.3 DEFINITIONS

- .1 Acronyms and definitions: refer to Section 25 05 01 - EMCS: General Requirements.

1.4 DESCRIPTION

- .1 General: Network of controllers comprising of LCU('s) to be provided to support building systems and associated sequence(s) of operations as detailed in these specifications.
 - .1 Provide sufficient controllers to meet intents and requirements of this section.
 - .2 Controller quantity, and point contents to be approved by Departmental Representative at time of preliminary design review.
- .2 Controllers: stand-alone intelligent Control Units.
 - .1 Incorporate programmable microprocessor, non-volatile program memory, RAM, power supplies, as required to perform specified functions.
 - .2 Incorporate communication interface ports for communication to LANs to exchange information with other Controllers.
 - .3 Capable of interfacing with operator interface device.
 - .4 Execute its logic and control using primary inputs and outputs connected directly to its onboard input/output field terminations or slave devices, and without need to interact with other controller. Secondary input used for reset such as outdoor air temperature may be

located in other Controller(s).

- .1 Secondary input used for reset such as outdoor air temperature may be located in other Controller(s).
- .3 Interface to include provisions for use of dial-up modem for interconnection with remote modem.
 - .1 Dial-up communications to use 56 Kbit modems and voice grade telephone lines.
 - .2 Each stand-alone panel may have its own modem or group of stand-alone panels may share modem.

1.5 DESIGN REQUIREMENTS

- .1 To include:
 - .1 Scanning of AI and DI connected inputs for detection of change of value and processing detection of alarm conditions.
 - .2 Perform On-Off digital control of connected points, including resulting required states generated through programmable logic output.
 - .3 Perform Analog control using programmable logic, (including PID) with adjustable dead bands and deviation alarms.
 - .4 Control of systems as described in sequence of operations.
 - .5 Execution of optimization routines as listed in this section.
- .2 Total spare capacity for LCUs: at least 25 % of each point type distributed throughout the MCUs and LCUs.
- .3 Field Termination and Interface Devices:
 - .1 To: CSA C22.2 No.205.
 - .2 Electronically interface sensors and control devices to processor unit.
 - .3 Include, but not be limited to, following:
 - .1 Programmed firmware or logic circuits to meet functional and technical requirements.
 - .2 Power supplies for operation of logics devices and associated field equipment.
 - .3 Lockable wall cabinet.
 - .4 Required communications equipment and wiring (if remote units).
 - .5 Leave controlled system in "fail-safe" mode in event of loss of communication with, or failure of, processor unit.
 - .6 Input Output interface to accept as minimum AI, AO, DI, DO functions as specified.
 - .7 Wiring terminations: use conveniently located screw type or spade lug terminals.
 - .4 AI interface equipment to:
 - .1 Convert analog signals to digital format with [10] bit analog-to-digital resolution.
 - .2 Provide for following input signal types and ranges:
 - .1 4 - 20 mA;
 - .2 0 - 10V DC;
 - .3 Meet IEEE C37.90.1 surge withstand capability.
 - .4 Have common mode signal rejection greater than 60dB to 60Hz.
 - .5 Where required, dropping resistors to be certified precision devices which complement accuracy of sensor and transmitter range specified.
 - .5 AO interface equipment:
 - .1 Convert digital data from controller processor to acceptable analog output signals using 8bit digital-to-analog resolution.
 - .2 Provide for following output signal types and ranges:
 - .1 4 - 20 mA.

- .2 0 - 10 V DC.
- .3 Meet IEEE C37.90.1 surge withstand capability.
- .6 DI interface equipment:
 - .1 Able to reliably detect contact change of sensed field contact and transmit condition to controller.
 - .2 Meet IEEE C37.90.1 surge withstand capability.
 - .3 Accept pulsed inputs up to 2kHz.
- .7 DO interface equipment:
 - .1 Respond to controller processor output, switch respective outputs. Each DO hardware to be capable of switching up to 0.5amps at 24V AC.
 - .2 Switch up to 5amps at 220V AC using optional interface relay.
- .4 Controllers and associated hardware and software: operate in conditions of 0 degrees C to 44 degrees C and 20 % to 90 % non-condensing RH.
- .5 Controllers (LCU): mount in wall mounted cabinet with hinged, keyed-alike locked door.
 - .1 Provide for conduit entrance from top, bottom or sides of panel.
 - .2 ECUs and TCUs to be mounted in equipment enclosures or separate enclosures.
 - .3 Mounting details as approved by Departmental Representative for ceiling mounting.
- .6 Cabinets to provide protection from water dripping from above, while allowing sufficient airflow to prevent internal overheating.
- .7 Provide surge and low voltage protection for interconnecting wiring connections.

1.6 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Make submittals in accordance with Section 00 10 00 – General Instructions and Section 25 05 02 - EMCS: Shop Drawings, Product Data and Review Process.
 - .1 Submit product data sheets for each product item proposed for this project.

1.7 MAINTENANCE

- .1 Provide manufacturers recommended maintenance procedures for insertion in Section 25 05 03 - EMCS: Project Record Documents.

PART 2 - PRODUCTS

2.1 LOCAL CONTROL UNIT (LCU)

- .1 Provide multiple control functions for typical built-up and package HVAC systems, hydronic systems and electrical systems.
- .2 Minimum of 16 I/O points of which minimum be 4 AOs, 4 AIs, 4 DIs, 4 DOs.
- .3 Points integral to one Building System to be resident on only one controller.
- .4 Microprocessor capable of supporting necessary software and hardware to meet specified requirements as listed in previous MCU article with following additions:

- .1 Include minimum 2 interface ports for connection of local computer terminal.
- .2 Design so that shorts, opens or grounds on input or output will not interfere with other input or output signals.
- .3 Physically separate line voltage (70V and over) circuits from DC logic circuits to permit maintenance on either circuit with minimum hazards to technician and equipment.
- .4 Include power supplies for operation of LCU and associated field equipment.
- .5 In event of loss of communications with, or failure of, MCU, LCU to continue to perform control. Controllers that use defaults or fail to open or close positions not acceptable.
- .6 Provide conveniently located screw type or spade lug terminals for field wiring.

2.2 POINT NAME SUPPORT

- .1 Controllers (LCU) to support point naming convention as defined in Section 25 05 01 - EMCS: General Requirements.

PART 3 - EXECUTION

3.1 LOCATION

- .1 Location of Controllers to be approved by Departmental Representative.

3.2 INSTALLATION

- .1 Install Controllers in secure locking enclosures as directed by Departmental Representative.
- .2 Provide necessary power from local 120V branch circuit panel for equipment.
- .3 Install tamper locks on breakers of circuit breaker panel.

END OF SECTION

PART 1 - GENERAL

1.1 SUMMARY

- .1 Related Sections:
 - .1 Section 00 10 00 – General Instructions.
 - .2 Section 00 15 45 – General and Fire Safety Requirements
 - .3 Section 25 01 11 - EMCS: Start-Up, Verification and Commissioning.
 - .4 Section 25 05 01 - EMCS: General Requirements.
 - .5 Section 25 05 02 - EMCS: Shop Drawings, Product Data and Review Process.
 - .6 Section 25 05 54 - EMCS: Identification.
 - .7 Section 25 90 01 - EMCS: Site Requirements Applications and Systems Sequences of Operation.
 - .8 Section 26 05 00 - Common Work Results for Electrical.
 - .9 Section 26 27 26 - Wiring Devices.

1.2 REFERENCES

- .1 American National Standards Institute (ANSI).
 - .1 ANSI C12.7-1993(R1999), Requirements for Watthour Meter Sockets.
 - .2 ANSI/IEEE C57.13-1993, Standard Requirements for Instrument Transformers.
- .2 American Society for Testing and Materials International, (ASTM).
 - .1 ASTM B 148-97(03), Standard Specification for Aluminum-Bronze Sand Castings.
- .3 National Electrical Manufacturer's Association (NEMA).
 - .1 NEMA 250-03, Enclosures for Electrical Equipment (1000 Volts Maximum).
- .4 Air Movement and Control Association, Inc. (AMCA).
 - .1 AMCA Standard 500-D-98, Laboratory Method of Testing Dampers For Rating.
- .5 Canadian Standards Association (CSA International).
 - .1 CSA-C22.1-02, Canadian Electrical Code, Part 1 (19th Edition), Safety Standard for Electrical Installations.

1.3 DEFINITIONS

- .1 Acronyms and Definitions: refer to Section 25 05 01 - EMCS: General Requirements.

1.4 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit shop drawings and manufacturer's installation instructions in accordance with Section 25 05 02 - EMCS: Submittals and Review Process.
- .2 Pre-Installation Tests.
 - .1 Submit samples at random from equipment shipped, as requested by Departmental

- Representative, for testing before installation. Replace devices not meeting specified performance and accuracy.
- .3 Manufacturer's Instructions:
 - .1 Submit manufacturer's installation instructions for specified equipment and devices.

1.5 EXISTING CONDITIONS

- .1 Cutting and Patching: in accordance with Section 00 10 00 – General Instruction supplemented as specified herein.
- .2 Repair surfaces damaged during execution of Work.
- .3 Turn over to Departmental Representative existing materials removed from Work not identified for re-use.

PART 2 - PRODUCTS

2.1 GENERAL

- .1 Control devices of each category to be of same type and manufacturer.
- .2 External trim materials to be corrosion resistant. Internal parts to be assembled in watertight, heat resistant assembly.
- .3 Operating conditions: 0 - 32 degrees C with 10 - 90% RH (non-condensing) unless otherwise specified.
- .4 Terminations: use standard conduit box with slot screwdriver compression connector block unless otherwise specified.
- .5 Transmitters and sensors to be unaffected by external transmitters including walkie talkies.
- .6 Account for hysteresis, relaxation time, maximum and minimum limits in applications of sensors and controls.
- .7 Outdoor installations: use weatherproof construction in NEMA 4 enclosures.
- .8 Devices installed in user occupied space not exceed Noise Criteria (NC) of 35. Noise generated by any device must not be detectable above space ambient conditions.
- .9 Range: including temperature, as indicated in I/O summary in Section 25 90 01 - EMCS: Site Requirements, Applications and System Sequences of Operation.

2.2 TEMPERATURE SENSORS

- .1 Room temperature sensors and display wall modules.
 - .1 Temperature sensing and display wall module.
 - .1 LCD display to show space temperature and temperature setpoint.
 - .2 Buttons for occupant selection of temperature setpoint.
 - .3 Jack connection for plugging in laptop personal computer for access to zone bus.
 - .4 Integral thermistor sensing element 10,000ohm at 24degrees.
 - .5 Accuracy 0.2 degrees C over range of 0 to 70 degrees C.
 - .6 Stability 0.02 degrees C drift per year.
 - .7 Separate mounting base for ease of installation.

2.3 CONTROL VALVES

- .1 Body: globe.
 - .1 Flow characteristic as indicated on control valve schedule: linear.
 - .2 Flow factor (KV) as indicated on control valve schedule: CV in imperial units.
 - .3 Normally open, as indicated.
 - .4 Two port, as indicated.
 - .5 Leakage rate ANSI class IV, 0.01% of full open valve capacity.
 - .6 Packing easily replaceable.
 - .7 Stem, stainless steel ASTM A582 Type 303.
 - .8 Seat style: metal-to-metal.
 - .9 Disc, replaceable, material to suit application.
 - .10 NPS 2 and under:
 - .1 Screwed National Pipe Thread (NPT) tapered female connections.
 - .2 Valves to ANSI Class 250, valves to bear ANSI mark.
 - .3 Rangeability 50:1 minimum.
 - .11 Acceptable products: Siemens Zone Valves 599 Series.

2.4 ELECTRONIC / ELECTRIC VALVE ACTUATORS

- .1 Requirements:
 - .2 Construction: steel, cast iron, aluminum.
 - .3 Control signal: 0-10V DC.
 - .4 Positioning time: to suit application. 90 sec maximum.
 - .5 Scale or dial indication of actual control valve position.
 - .6 Size actuator to meet requirements and performance of control valve specifications.
 - .7 For interior and perimeter terminal heating and cooling applications floating control actuators are acceptable.

2.5 PANELS

- .1 Wall mounted enamelled steel cabinets with hinged and key-locked front door.
- .2 Multiple panels as required to handle requirements with additional space to accommodate 25% additional capacity as required by Departmental Representative without adding additional cabinets.
- .3 Panels to be lockable with same key.

2.6 WIRING

- .1 In accordance with Section 26 27 26 - Wiring Devices.
- .2 For wiring under 70 volts use FT6 rated wiring where wiring is not run in conduit. Other cases use FT4 wiring.
- .3 Wiring must be continuous without joints.
- .4 Sizes:
 - .1 Field wiring to digital device: #18AWG or 20AWG stranded twisted pair.
 - .2 Analog input and output: shielded #18 minimum solid copper or #20 minimum stranded twisted pair.

PART 3 - EXECUTION

3.1 INSTALLATION

- .1 Install equipment, components so that manufacturer's and CSA labels are visible and legible after commissioning is complete.
- .2 Install field control devices in accordance with manufacturers recommended methods, procedures and instructions.
- .3 Fire stopping: provide space for fire stopping in accordance with Section 00 15 45 – General and Fire Safety Requirements. Maintain fire rating integrity.
- .4 Electrical:
 - .1 Complete installation in accordance with Section 26 05 00 - Common Work Results for Electrical.
 - .2 Modify existing starters to provide for EMCS as indicated in I/O Summaries and as indicated.
 - .3 Refer to electrical control schematics included as part of control design schematics in Section 25 90 01 - EMCS: Site Requirements Applications and Systems Sequences of Operation. Trace existing control wiring installation and provide updated wiring schematics including additions, deletions to control circuits for review by Departmental Representative before beginning Work.
 - .4 Terminate wires with screw terminal type connectors suitable for wire size, and number of terminations.
 - .5 Install communication wiring in conduit.
 - .1 Provide complete conduit system to link Building Controllers, field panels and OWS(s).
 - .2 Conduit sizes to suit wiring requirements and to allow for future expansion capabilities specified for systems.
 - .3 Maximum conduit fill not to exceed 40%.
 - .4 Design drawings do not show conduit layout.
 - .6 Do not run exposed conduits in normally occupied spaces unless otherwise indicated or unless impossible to do otherwise. Departmental Representative to review before starting Work. Wiring in mechanical rooms, wiring in service rooms and exposed wiring must be in conduit.

3.2 PANELS

- .1 Arrange for conduit and tubing entry from top, bottom or either side.
- .2 Wiring and tubing within panels: locate in trays or individually clipped to back of panel.
- .3 Identify wiring and conduit clearly.

3.3 IDENTIFICATION

- .1 Identify field devices in accordance with Section 25 05 54 - EMCS: Identification.

3.4 TESTING AND COMMISSIONING

- .1 Calibrate and test field devices for accuracy and performance in accordance with Section 25 01 11 - EMCS: Start-up, Verification and Commissioning.

NRC-CNRC
Project No.
S77-6032

Section 25 30 02
EMCS: FIELD CONTROL DEVICES
Page 5 of 5

END OF SECTION

PART 1 - GENERAL

1.1 REFERENCES

- .1 Public Works and Government Services Canada (PWGSC) / Real Property Branch / Architectural and Engineering Services.
 - .1 MD13800-September 2000, Energy Management and Control Systems (EMCS) Design Manual. English: <ftp://ftp.pwgsc.gc.ca/rps/docentre/mechanical/me214-e.pdf>

1.2 SEQUENCING

- .1 Present sequencing of operations for systems, in accordance with MD13800 - Energy Management and Control Systems (EMCS) Design Manual.
- .2 Sequencing of operations for systems as follows:
 - .1 Unit Heaters:
 - .1 System stopped:
 - .1 Unit heater is off.
 - .2 Control valve is closed.
 - .2 System start-up :
 - .1 LCU starts the unit heater through contact/relay.
 - .2 LCU opens controls valve.
 - .3 Normal mode:
 - .1 The control valve is modulated by the LCU to maintain temperature setpoint (adjustable).
 - .2 Room temperature is reported back to the BAS.
 - .4 Alarm:
 - .1 General an alarm at the BAS if room temperature falls below 10°C.
 - .2 Finned tube radiation:
 - .1 System stopped:
 - .1 Control valve is closed.
 - .2 System start-up – upon a call for heating:
 - .1 LCU opens control valve.
 - .3 Normal mode:
 - .1 The control valve is modulated by the LCU to maintain the temperature setpoint (adjustable).
 - .2 Room temperature is reported back to the BAS.
 - .4 Alarm:
 - .1 Generate an alarm at the BAS if room temperature falls below 10°C.
 - .5 For Rooms 87, 97 and 99:
 - .1 Associated control valve is to modulate based on highest heating demand.

PART 2 - PRODUCTS

2.1 NOT USED

.1 Not Used.

PART 3 - EXECUTION

3.1 NOT USED

.1 Not Used.

END OF SECTION

1 REFERENCES

- .1 Perform all work to meet or exceed the requirements of the Canadian Electrical Code, CSA Standard C22.1 - (latest edition).
- .2 Consider CSA Electrical Bulletins in force at time of tender submission, while not identified and specified by number in this Division, to be forming part of related CSA Part II standard.
- .3 Do overhead and underground systems in accordance with CSA C22.3 except where specified otherwise.
- .4 Where requirements of this specification exceed those of above mentioned standards, this specification shall govern.
- .5 Notify the NRC Departmental Representative as soon as possible when requested to connect equipment supplied by NRC which is not CSA approved.
- .6 Refer to Sections 01 10 00 & 01 35 30.

2 PERMITS AND FEES

- .1 Submit to Electrical Inspection Department and Supply Authority necessary number of drawings and specifications for examination and approval prior to commencement of work.
- .2 Pay all fees required for the performance of the work.

3 START-UP

- .1 Instruct the NRC Departmental Representative and operating personnel in the operation, care and maintenance of equipment supplied under this contract.

4 INSPECTION AND FEES

- .1 Furnish a Certificate of Acceptance from the Authorized Electrical Inspection Department on completion of work.
- .2 Request and obtain Special Inspection approval from the Authorized Electrical Inspection Department for any non-CSA approved control panels or other equipment fabricated by the contractor as part of this contract.
- .3 Pay all fees required for inspections.

5 OPERATION & MAINTENANCE (O&M) MANUALS

- .1 O&M manuals to include but not limited to
 - .1 Letter of warranty
 - .2 ESA inspection certificate
 - .3 Fire alarm ventilation report
 - .4 Updated panel schedule c/w circuit breaker size
 - .5 Shop drawings

- .6 As-builts
 - .7 Load balancing report
 - .8 Mechanical equipment start up reports
 - .9 Seismic review letter
- .2 Refer to 00 10 00 for additional information.

6 FINISHES

- .1 Shop finish metal enclosure surfaces by removal of rust and scale, cleaning, application of rust resistant primer inside and outside, and at least two coats of finish enamel.
- .1 Outdoor electrical equipment "equipment green" finish to EEMAC Y1-1-1955.
 - .2 Indoor switchgear and distribution enclosures light grey to EEMAC 2Y-1-1958.
- .2 Clean and touch up surfaces of shop-painted equipment scratched or marred during shipment or installation, to match original paint.

7 ACOUSTICAL PERFORMANCE

- .1 In general provide equipment producing minimal sound levels in accordance with the best and latest practices established by the electrical industry.
- .2 Do not install any device or equipment containing a magnetic flux path metallic core, such as gas discharge lamp ballasts, dimmers, solenoids, etc., which are found to produce a noise level exceeding that of comparable available equipment.

8 EQUIPMENT IDENTIFICATION

- .1 Identify with 3mm (1/8") Brother, P-Touch non-smearing tape, or an alternate approved by the NRC Departmental Representative, all electrical outlets shown on drawings and/or mentioned in the specifications. These are the lighting switches, exit signs, recessed and surface mounted receptacles such as those in offices and service rooms and used to plug in office equipment, telecommunication equipment or small portable tools. Indicate only the source of power (Ex. for a receptacle fed from panel L32 circuit #1: "L32-1").
- .2 P-Touch label to be:
- .1 Black letters on a white background for normal power circuits.
 - .2 Black letters on a yellow background for emergency power circuits.
 - .3 White letters on a red background for fire alarm device.
- .3 Light fixtures are the only exceptions for electrical equipment identification (except as noted in 8.14 below). They are not to be identified.
- .4 Identify with lamicoid nameplates all electrical equipment shown on the drawings and/or mentioned in the specification such as motor control centers, switchgear, splitters, fused switches, isolation switches, motor starting switches, starters, panelboards, transformers, high voltage cables, industrial type receptacles, junction boxes, control panels, etc., regardless of whether or not the electrical equipment was furnished under this section of the specification.

- .5 Coordinate names of equipment and systems with other Divisions to ensure that names and numbers match.
- .6 Wording on lamicoïd nameplates to be approved by the NRC Departmental Representative prior to fabrication.
- .7 Provide two sets of lamicoïd nameplates for each piece of equipment; one in English and one in French.
- .8 Lamicoïd nameplates shall identify the equipment, the voltage characteristics and the power source for the equipment. Example: A new 120/240 volt single phase circuit breaker panelboard, L16, is fed from panelboard LD1 circuit 10.

"PANEL L16
120/240 V
FED FROM LD1-10"

PANNEAU L16
120/240 V
ALIMENTE PAR LD1-10

- .9 Provide warning labels for equipment fed from two or more sources - "DANGER MULTIPLE POWER FEED" black letters on a yellow background. These labels are available from NRC's Facilities Maintenance group in building M-19.
- .10 Lamicoïd nameplates shall be rigid lamicoïd, minimum 1.5 mm (1/16") thick with:
 - .1 Black letters engraved on a white background for normal power circuits.
 - .2 Black letters engraved on a yellow background for emergency power circuits.
 - .3 White letters engraved on a red background for fire alarm equipment.
- .11 For all interior lamicoïd nameplates, mount nameplates using two-sided tape.
- .12 For all exterior lamicoïd nameplates, mount nameplates using self-tapping 2.3 mm (3/32") dia. slot head screws - two per nameplate for nameplates under 75 mm (3") in height and a minimum of 4 for larger nameplates. Holes in lamicoïd nameplates to be 3.7 mm (3/16") diameter to allow for expansion of lamicoïd due to exterior conditions.
 - .1 No drilling is to be done on live equipment.
 - .2 Metal filings from drilling are to be vacuumed from the enclosure interiors.
- .13 All lamicoïd nameplates shall have a minimum border of 3 mm (1/8"). Characters shall be 9 mm (3/8") in size unless otherwise specified.
- .14 Identify lighting fixtures which are connected to emergency power with a label "EMERGENCY LIGHTING/ÉCLAIRAGE D'URGENCE", black letters on a yellow background. These labels are available from NRC's Facilities Maintenance group in building M-19.
- .15 Provide neatly typed updated circuit directories in a plastic holder on the inside door of new panelboards.
- .16 Carefully update panelboard circuit directories whenever adding, deleting, or modifying existing circuitry.


- .17 Identify molded case breaker with lamicoïd nameplate.

9 WIRING IDENTIFICATION

- .1 Unless otherwise specified, identify wiring with permanent indelible identifying markings, using either numbered or coloured plastic tapes on both ends of phase conductors of feeders and branch circuit wiring.
- .2 Maintain phase sequence and colour coding throughout.

10 CONDUIT AND CABLE IDENTIFICATION

- .1 All new conduits to be factory painted, colour-coded EMT, type as follows:
- .1 Fire alarm – red conduit
 - .2 Emergency power circuits – yellow conduit
 - .3 Voice/data – blue conduit
 - .4 Gas detection system – purple conduit
 - .5 Building Automation system – orange conduit
 - .6 Other base building low voltage control system – white conduit
 - .7 Security system – green conduit
 - .8 Research center control system – black conduit
- .2 Apply paint to the covers of junction boxes and condulets of existing conduits as follows:
- .1 Fire alarm – red
 - .2 Emergency power circuits – yellow
 - .3 Voice/data – blue
 - .4 Gas detection system – purple
 - .5 Building Automation system – orange
 - .6 Other base building low voltage control system - white
 - .7 Security system – green
 - .8 Research center control system - black
- .3 For system running with cable, half-lap wrap with dedicated coloured PVC tape to 100 mm width, tape every 5 m and both sides where cable penetrates a wall.
- .4 All other systems to follow site instruction from NRC departmental representative.
- .5 Identify all electrical circuits in every junction box and pull box on the box cover with 9mm letter size P-touch label. Identify all electrical circuits on each conduit end where conduit penetrates a wall ,enclosure ,junction box or pull box , and halfway of each conduit run between walls ,enclosures ,junction boxes or pull boxes with 3mm letter size P-touch label..
- .6 Identify electrical circuit on each cable 250MCM or larger with lamacoïd nameplate, or cable 4/0 or smaller with P-touch label, on every splitter, every 30m of each cable run and cable end where cable penetrates a wall, enclosure, junction box or pull box.
- .7 Sample diagram shown as below:



11 MANUFACTURER'S & APPROVALS LABELS

- .1 Ensure that manufacturer's registration plates are properly affixed to all apparatus showing the size, name of equipment, serial number, and all information usually provided, including voltage, cycle, phase and the name and address of the manufacturer.
- .2 Do not paint over registration plates or approval labels. Leave openings through insulation for viewing the plates. Contractor's or sub-contractor's nameplate not acceptable.

12 WARNING SIGNS AND PROTECTION

- .1 Provide warning signs, as specified or to meet requirements of Authorized Electrical Inspection Department and NRC Departmental Representative.
- .2 Accept the responsibility to protect those working on the project from any physical danger due to exposed live equipment such as panel mains, outlet wiring, etc. Shield and mark all live parts with the appropriate voltage. Caution notices shall be worded in both English and French.

13 LOAD BALANCE

- .1 Measure phase current to new panelboards with normal loads operating at time of acceptance. Adjust branch circuit connections as required to obtain best balance of current between phases and record changes, and revise panelboard schedules.
- .2 Measure phase voltages at loads and adjust transformer taps to within 2% of rated voltage of equipment.

14 MOTOR ROTATION

- .1 For new motors, ensure that motor rotation matches the requirements of the driven equipment.
- .2 For existing motors, check rotation before making wiring changes in order to ensure correct rotation upon completion of the job.

15 GROUNDING

- .1 Thoroughly ground all electrical equipment, cabinets, metal supporting frames, ventilating ducts and other apparatus where grounding is required in accordance with the requirements of the latest edition of the Canadian Electrical Code Part 1, C.S.A. C22.1 and corresponding Provincial and Municipal regulations. Do not depend upon conduits to provide the ground circuits.

- .2 Run separate green insulated stranded copper grounding conductors in all electrical conduits including those feeding toggle switches and receptacles.

16 TESTS

- .1 Provide any materials, equipment and labour required and make such tests deemed necessary to show proper execution of this work, in the presence of the NRC Departmental Representative.
- .2 Correct any defects or deficiencies discovered in the work in an approved manner at no additional expense to the Owner.
- .3 Megger all branch circuits and feeders using a 600V tester for 240V circuits and a 1000V tester for 600V circuits. If the resistance to ground is less than permitted by Table 24 of the Code, consider such circuits defective and do not energize.
- .4 The final approval of insulation between conductors and ground, and the efficiency of the grounding system is left to the discretion of the local Electrical Inspection Department.

17 COORDINATION OF PROTECTIVE DEVICES

- .1 Ensure circuit protective devices such as overcurrent trips, fuses, are installed to values and settings as indicated on the Drawings.

18 WORK ON LIVE EQUIPMENT & PANELS

- .1 NRC requires that work be performed on non-energized equipment, installation, conductors and power panels. For purposes of quotation assume that all work is to be done after normal working hours and that equipment, installation, conductors and power panels are to be de-energized when worked upon.
- .2 Coordinate all shutdowns with the NRC departmental representative. High voltage (more than 1KV) grounding must be provided by certified electrician.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 This Section includes requirements for selective demolition and removal of electrical, communications and safety and security components including removal of conduit, junction boxes, and panels to source (home run removal) and incidentals required to complete work described in this Section ready for new construction.

1.2 RELATED REQUIREMENTS

- .1 Section 01 10 00 – General Instructions
- .2 Section 01 74 19 – Waste Management and Disposal
- .3 Section 02 41 19.16 - Selective Interior Demolition
- .4 Section 02 42 00 - Removal and Salvage of Construction Materials

1.3 REFERENCE STANDARDS

- .1 CSA Group (CSA)
 - .1 CSA S350 M1980 (R2003), Code of Practice for Safety in Demolition of Structures

1.4 DEFINITIONS

- .1 Demolish: Detach items from existing construction and legally dispose of items off site, unless indicated as removed and salvaged, or removed and reinstalled.
- .2 Remove: Planned deconstruction and disassembly of electrical items from existing construction including removal of conduit, junction boxes, cabling and wiring from electrical component to panel taking care not to damage adjacent assemblies designated to remain; legally dispose of items off site, unless indicated as removed and salvaged, or removed and reinstalled.
- .3 Remove and Salvage: Detach items from existing construction and deliver them to Departmental Representative ready for reuse.
- .4 Remove and Reinstall: Detach items from existing construction, prepare them for reuse, and reinstall them where indicated.
- .5 Existing to Remain: Existing items of construction that are not removed and that are not otherwise indicated as being removed and salvaged, or removed and reinstalled.

1.5 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Action Submittals: Provide in accordance with Section 01 10 00 – General Instructions before starting work of this Section:
 - .1 Construction Waste Management Plan (CWM Plan): Submit plan addressing opportunities for reduction, reuse, or recycling of materials prepared in accordance with Section 01 74 19 - Waste Management and Disposal.
 - .2 Landfill Records: Indicate receipt and acceptance of selective demolition waste and hazardous wastes by a landfill facility licensed to accept hazardous wastes.

1.6 ADMINISTRATIVE REQUIREMENTS

- .1 Coordination: Coordinate work of this Section to avoid interference with work by other Sections.
- .2 Scheduling: Account for Departmental Representative continued occupancy requirements during selective demolition with Section 02 41 19.16 - Selective Interior Demolition.

1.7 QUALITY ASSURANCE

- .1 Regulatory Requirements: Perform work of this Section in accordance with:
 - .1 Federal Workers' Compensation Service.
 - .2 Government of Canada, Labour Program: Workplace Safety.

1.8 SITE CONDITIONS

- .1 Existing Conditions: Condition of materials identified as being salvaged or demolished are based on their observed condition on their observed condition at time of site examination before tendering.
- .2 Discovery of Hazardous Substances: It is not expected that Hazardous Substances will be encountered in Work; immediately notify Departmental Representative if materials suspected of containing hazardous substances are encountered and perform following activities:
 - .1 Refer to Section 01 10 00 – General Instructions for directives associated with specific material types.
 - .2 Hazardous substances will be as defined in Hazardous Products Act.
 - .3 Stop work in area of suspected hazardous substances.
 - .4 Take preventative measures to limit users' and workers' exposure, provide barriers and other safety devices and do not disturb.
 - .5 Hazardous substances will be removed by Departmental Representative under a separate contract or as a change to Work.
 - .6 Proceed only after written instructions have been received from Departmental Representative.

1.9 SALVAGE AND DEBRIS MATERIALS

- .1 Demolished items become Contractor's property and will be removed from Project site; except for items indicated as being reused, salvaged, or otherwise indicated to remain Departmental Representative's property.
- .2 Carefully remove materials and items designated for salvage and store in a manner to prevent damage or devaluation of materials in accordance with Section 02 42 00 - Removal and Salvage of Construction Materials.
 - .1 Leave main electrical distribution panel in place; panel can be used for temporary construction power for this and subsequent contracts in accordance with Section 01 10 00 – General Instructions; coordinate temporary power connections with Departmental Representative.

Part 2 Products

2.1 MATERIALS

- .1 General Patching and Repair Materials: Refer to Section 02 41 19.16 - Selective Interior Demolition or listing of patching and repair materials incidental to removal or demolition of components associated with work of this Section.
- .2 Electrical Repair Materials: Use only new materials, CSA or ULC labelled as appropriate and matching components remaining after work associated with components identified for removal or demolition are completed.
- .3 Fire stopping Repair Materials: Use fire stopping materials compatible with existing fire stopping systems where removal or demolition work affects rated assemblies, restore to match existing fire rated performance.

Part 3 Execution

3.1 EXAMINATION

- .1 Verification of Existing Conditions: Visit site, thoroughly examine and become familiar with conditions that may affect the work of this Section before tendering the Bid; Departmental Representative will not consider claims for extras for work or materials necessary for proper execution and completion of the contract that could have been determined by a site visit.

3.2 PREPARATION

- .1 Protection of Existing Systems to Remain: Protect systems and components indicated to remain in place during selective demolition operations and as follows:
 - .1 Prevent movement and install bracing to prevent settlement or damage of adjacent services and parts of existing buildings scheduled to remain.

- .2 Departmental Representative and cease operations where safety of buildings being demolished, adjacent structures or services appears to be endangered and await additional instructions before resuming demolition work specified in this Section.
- .3 Prevent debris from blocking drainage inlets.
- .4 Protect mechanical systems that will remain in operation.
- .2 Protection of Building Occupants: Sequence demolition work so that interference with the use of the building by the Departmental Representative and users is minimized and as follows:
 - .1 Prevent debris from endangering safe access to and egress from occupied buildings.
 - .2 Notify Departmental Representative and cease operations where safety of occupants appears to be endangered and await additional instructions before resuming demolition work specified in this Section.

3.3 EXECUTION

- .1 Demolition and Removal: Coordinate requirements of this Section with information contained in Section 02 41 19.16 - Selective Interior Demolition and as follows:
 - .1 Maintain electrical service and main distribution panel as is, ready for subsequent Work.
 - .2 Remove existing luminaires, electrical devices and equipment including associated conduits, boxes, wiring, and similar items unless specifically noted otherwise.
 - .3 Disconnect and remove existing fire alarm system including associated conduits, boxes, wiring, and similar items unless specifically noted otherwise.
 - .4 Disconnect and remove communication systems including associated conduits, boxes, cabling, and similar items unless specifically noted otherwise.
 - .5 Disconnect and remove telephone outlets, associated conduit, cabling and sub terminal backboards and related accessories; maintain telephone service and main terminal backboard as is.
 - .6 Perform demolition work in a neat and workmanlike manner:
 - .1 Remove tools or equipment after completion of work, and leave site clean and ready for subsequent renovation work.
 - .2 Repair and restore damages caused as a result of work of this Section to match existing materials and finishes.
 - .7 Place weatherproof blank cover plates on exterior outlet boxes remaining after demolition and removal activities.
 - .8 Remove existing conduits, boxes, cabling and wiring associated with removed luminaires, electrical devices and equipment.
 - .9 Grind off conduits and make flush with surface of concrete where conduits are cast into concrete; seal open ends of conduit with silicone sealant and leave in place.
 - .10 Seal open ends of conduit with silicone sealant and leave in place where they are inaccessible or cannot be removed without damaging adjacent construction.

3.4 CLOSEOUT ACTIVITIES

- .1 Demolition Waste Disposal: Arrange for legal disposal and remove demolished materials to accredited provincial landfill site or alternative disposal site (recycle centre) except where

explicitly noted otherwise for materials being salvaged for re use in new construction in accordance with Section 02 42 00 - Removal and Salvage of Construction Materials.

END OF SECTION

Part 1 General

1.1 RELATED WORK SPECIFIED ELSEWHERE

- .1 Common Work Results - Electrical Section 26 05 00

1.2 MATERIALS

- .1 Provide only new equipment and materials, without blemish or defect, bearing Canadian Standards Association or Authorized Electrical Inspection Department labels, and subject to the approval of the NRC Departmental Representative.
- .2 After a contract is awarded, utilize alternative methods and/or materials only after receiving the NRC Departmental Representative's approval.

Part 2 Products

2.1 BUILDING WIRES AND GENERAL REQUIREMENTS

- .1 Conductor material for branch circuit wiring and grounding:
 - .1 Stranded copper.
 - .2 Neutral wire: continuous throughout its length without breaks.
 - .3 Separate insulated green grounding conductors in all electrical conduits.
 - .4 All wire and cable insulation shall meet the C.S.A. Standards for the types and services hereinafter specified. Colours as per section 4-036 of Electrical Code.
 - .5 Unless otherwise specified, use wire and cable types as follows:
 - .1 Type R90 XLPE cross-link polyethylene stranded for applications using wires sized No. 8 and larger.
 - .2 Type T90 stranded for applications using wires sized No. 10 and smaller.
 - .3 For fire alarm wiring refer to Section 283100.
 - .4 Approved heat resistant wire for wiring through and at lighting and heating fixtures. Where insulation types are shown on the drawings other types shall not be used unless the specification is more restrictive.
 - .6 Use AC90 (BX) cable **only** under the following conditions:
 - .1 Wiring from a junction box to a recessed lighting fixture in suspended ceilings. Cable length not to exceed 1.5 m (5'), or
 - .2 Wiring switches or receptacles in existing or new hollow gypsum partitions, vertical runs only with cable length not to exceed 3.5m (12'), or
 - .3 When specifically called for on drawings or approved in writing by departmental representative.
 - .4 AC90 shall not be used in isolated walls or masonry walls.
 - .5 Only AC90 cable of No. 12 AWG will be accepted.
 - .7 Use stranded wire no smaller than No. 12 AWG for lighting and power and no smaller than No. 16 AWG for control wiring.

- .8 Conductors shall be soft copper properly refined and tinned having a minimum conductivity of 98%.

Part 3 Execution

3.1 BUILDING WIRES

- .1 Install building wires as follows:
 - .1 Make joints, taps and splices in approved boxes with solderless connectors. Joints and/or splices are not acceptable inside a panelboard.
 - .2 Ensure the lugs accommodate all the strands of the conductor.
 - .3 Replace any wire or cable showing evidence of mechanical injury.
 - .4 Use No. 10 AWG for branch circuit wiring extending more than 30 m (100 ft.) to farthest outlet from panel.
 - .5 Circuit numbers indicated on the drawing are intended as a guide for the proper connection of multi-wire circuits at the panel.
 - .6 Take care to keep the conductors free from twisting.
 - .7 Use an approved lubricant for pulling in conduit.
 - .8 Leave sufficient slack on all runs to permit proper splicing and connection of electrical devices.
 - .9 Branch circuit wiring of 120 volt applications to be multi-wire utilizing common neutrals. Under no condition shall any switch break a neutral conductor.
 - .10 Provide and install an approved fire- retardant wrap or coating for PVC jacketed cables installed in a grouped configuration of two or more.

END OF SECTION

Part 1 General

1.1 RELATED WORK SPECIFIED ELSEWHERE

- .1 Common Work Results - Electrical Section 26 05 00

1.2 MATERIALS

- .1 Provide only new equipment and materials, without blemish or defect, bearing Canadian Standards Association or Authorized Electrical Inspection Department labels, and subject to the approval of the NRC Departmental Representative.
- .2 After a contract is awarded, utilize alternative methods and/or materials only after receiving the NRC Departmental Representative's approval.

Part 2 Products

2.1 WIRE AND BOX CONNECTORS

- .1 Pressure type wire connectors sized to fit conductors.

2.2 WIRING TERMINATIONS

- .1 Provide first grade wire and cable connectors suitable for the service on which they are used and install them in accordance with the latest trade practice.
- .2 Provide high quality extruded copper-free aluminium (0.4% or less) connectors for single and multi conductor cable. Steel and then zinc plated connectors for multi conductor cables.
- .3 When used in hazardous area, connectors should be certified for such location in Class, Division and Group.
- .4 For large conductor sizes, use bolted or compression solderless type connectors.
- .5 Use high temperature connectors and insulation on all connections of high temperature conductors.
- .6 Where connector types are called for on the drawings or in the specification, do not use other types.
- .7 Lugs, terminals, screws used for termination of wiring to be suitable for copper conductors.
- .8 For fire alarm wiring refer to Section 28 31 00.

Part 3 Execution

3.1 INSTALLATION

- .1 Install stress cones, terminations, and splices in accordance with manufacturer's instructions.
- .2 Bond and ground as required [to CSA C22.2No.41].

END OF SECTION

WASTE AUDIT worksheet for NRC Construction, Renovation and Demolition Projects

Worksheet for: Total Inventory Specific Stage Individual Floor

Create one worksheet for the entire project or multiple worksheets for each stage of the project, or per floor (where needed). Mark each worksheet accordingly

Project Name	
Project Type (Construction, Renovation or Demolition)	
Area (sq. m)	
Site Address	
Contact Person & Telephone	
Date	

For Project Planning Purposes (i.e. number of bins required)

* Add or delete materials as project requires

WASTE CATEGORY AND MATERIAL TYPE	Units	Total Units	Weight (kg) per unit of measurement	Estimated Weight (Metric Tonnes)	Potential Reuse (Metric Tonnes)	Potential Recycle (Metric Tonnes)	Potential Landfill (Metric Tonnes)	Volume (cubic yards)
Masonry and Pavement								
Asphalt (cu. m.)	cu. m.		2400.00	0.00				
Concrete (walls, floors, stairs)	cu. m.		2400.00	0.00				
Brick, block, etc.	cu. m.		1840.00	0.00				
Stone (foundation)	cu. m.		1473.80	0.00				
Glass masonry	cu. m.			0.00				
Marble	cu. m.		2563.00	0.00				
Granite	cu. m.		2750.00	0.00				
Clay tile	cu. m.			0.00				
Other	cu. m.			0.00				
			TOTAL	0.00	0.00	0.00	0.00	0
Walls and Ceilings								
Drywall (12.5 mm)	sq. m.		9.74	0.00				
Drywall (19 mm)	sq. m.		12.25	0.00				
Cellulose insulation	sq. m.		6.41	0.00				
Fiberglass insulation	sq. m.		6.41	0.00				
Solid SM insulation	sq. m.		11.54	0.00				
Ceiling tile (19 mm standard)	sq. m.		6.82	0.00				
Glass (5 - 6 mm)	sq. m.			0.00				
Acoustic composite (ceilings, walls)	sq. m.		0.30	0.00				
Other	sq. m.			0.00				
			TOTAL	0.00	0.00	0.00	0.00	0
Metal								
Steel (structural, stairs, fabrications, joists, deck, siding)	weight		600.00	0.00				
Aluminum (structural, siding)			2700.00	0.00				
Light Metal				0.00				
Studs	lm. of wall			0.00				
Ceiling grid	sq. m.		1.41	0.00				
Steel mesh				0.00				
Miscellaneous				0.00				
Other				0.00				
			TOTAL	0.00	0.00	0.00	0.00	0
Mechanical								
HVAC								
Solid ducts	weight		26238.00	0.00				
Flex ducts	weight		5180.00	0.00				
Metal diffuser (600 X600)	each			0.00				
Light diffuser (boot only)	each			0.00				
Plastic grilles (600 X 600)	each			0.00				
VAV boxes	weight			0.00				
Heat coils	weight			0.00				
A/C units	weight		90.00	0.00				
			TOTAL	0.00	0.00	0.00	0.00	0
Plumbing								
Copper piping (12.5 to 19mm)	lin. m.		1833.30	0.00				
Steel piping (38 to 50mm)	lin. m.		220.00	0.00				
Plastic piping (38 to 50mm)	lin. m.			0.00				
			TOTAL	0.00	0.00	0.00	0.00	0
Fixtures								

Sinks (ceramic/porcelain)	each		10.00	0.00					
Sinks (metal)	each		10.00	0.00					
Faucets	each			0.00					
Water Closet	each		46.00	0.00					
Urinals (wall hung)	each		29.00	0.00					
			TOTAL	0.00	0.00	0.00	0.00		0
Other									
			TOTAL	0.00	0.00	0.00	0.00		0
Windows and Doors									
Doors									
Wood (solid or hollow core)	each		20.00	0.00					
Metal (hollow metal)	each		30.00	0.00					
Garage	each		135.00	0.00					
Frame (wood)	each		23.33	0.00					
Frame (metal)	each		2.33	0.00					
Windows				0.00					
Wood frame	each		216.36	0.00					
Plastic frame	each		125.10	0.00					
Aluminum frame	each		216.67	0.00					
Door Hardware				0.00					
Locksets	each		2.50	0.00					
Hinges, plates, stops, etc.	each		2.50	0.00					
Other (closers, operators, etc.)	each		2.50	0.00					
Other				0.00					
			TOTAL	0.00	0.00	0.00	0.00		0
Wood									
Rough (crating, timber, etc.)	weight			0.00					
Dimension (3 m studs)	each		2.83	0.00					
Plywood (17mm)	sq. m.		0.08	0.00					
Hardwood (floor)	sq. m.		0.02	0.00					
Other				0.00					
			TOTAL	0.00	0.00	0.00	0.00		0
Millwork and Finish Carpentry									
Baseboards and casing (50 mm ht.)	each			0.00					
Lower cabinets (c/w doors)	each		44.10	0.00					
Upper cabinets (c/w doors)	each			0.00					
Counters (9' sections)	each		45.65	0.00					
Other				0.00					
			TOTAL	0.00	0.00	0.00	0.00		0
Flooring									
Carpet (roll)	sq. m.		2.44	0.00					
Carpet tile	sq. m.		2.98	0.00					
Sheet vinyl and linoleum	sq. m.		2.98	0.00					
Rubber cove or carpet base	lin. m.		0.52	0.00					
Terrazzo - 25 mm	sq. m.		0.02	0.00					
Ceramic Tiles	sq. m.		0.21	0.00					
Other				0.00					
			TOTAL	0.00	0.00	0.00	0.00		0
Electrical									
Wiring									
Data	weight			0.00					
Electrical (aluminum, copper, iron, etc)	weight			0.00					
Junction and outlet boxes (standard)	each		3800.00	0.00					
Cover plates	each			0.00					
Electrical panels	weight			0.00					
Conduit (25 mm)	lin. m.			0.00					
Conduit (50 mm)	lin. m.			0.00					
			TOTAL	0.00	0.00	0.00	0.00		0
Lighting									
Fluorescent fixture (600 X 1200)	each		0.82	0.00					
Fluorescent fixture (300 X 1200)	each		0.08	0.00					
Ballast	each		4432.00	0.00					
Lamps	each			0.00					
Complete fixture (600 X 1200)	each			0.00					
Complete fixture (300 X 1200)	each			0.00					
Emergency battery lights	each		6.66	0.00					
Exit lights	each		1.00	0.00					

NRC Construction, Renovation and Demolition PRE-WASTE AUDIT SUMMARY

Project Name	0
Project Type (Construction, Renovation or Demolition)	0
Area (sq. m)	0
Site Address	0
Contact Person & Telephone	0
Date	

Waste Audit Summary					
WASTE CATEGORY	Estimated Quantity Generated (Metric Tonnes)	Potential Quantity (Metric Tonnes)			Potential Diversion Rate
		Reuse	Recycle	Landfill	
Masonry and Pavement	0.00	0.00	0.00	0.00	#DIV/0!
Walls and Ceilings	0.00	0.00	0.00	0.00	#DIV/0!
Metal	0.00	0.00	0.00	0.00	#DIV/0!
Mechanical:					
HVAC	0.00	0.00	0.00	0.00	#DIV/0!
Plumbing	0.00	0.00	0.00	0.00	#DIV/0!
Fixtures	0.00	0.00	0.00	0.00	#DIV/0!
Other	0.00	0.00	0.00	0.00	#DIV/0!
Windows and Doors	0.00	0.00	0.00	0.00	#DIV/0!
Wood	0.00	0.00	0.00	0.00	#DIV/0!
Millwork and Finish Carpentry	0.00	0.00	0.00	0.00	#DIV/0!
Flooring	0.00	0.00	0.00	0.00	#DIV/0!
Electrical:				0.00	#DIV/0!
Wiring	0.00	0.00	0.00		
Lighting	0.00	0.00	0.00	0.00	#DIV/0!
Other	0.00	0.00	0.00	0.00	#DIV/0!
Roofing	0.00	0.00	0.00	0.00	#DIV/0!
Specialties & Miscellaneous	0.00	0.00	0.00	0.00	#DIV/0!
Packaging	0.00	0.00	0.00	0.00	#DIV/0!
Other	0.00	0.00	0.00	0.00	#DIV/0!
TOTALS	0.00	0.00	0.00	0.00	#DIV/0!

NRC Construction, Renovation and Demolition WASTE REDUCTION WORK PLAN

Project Name	0
Project Type (Construction, Renovation or Demolition)	0
Area (sq. m)	0
Site Address	0
Contact Person & Telephone	0
Date	

WASTE CATEGORY AND MATERIAL	Estimated Quantity (Metric Tonnes)	Proposed Action to Reduce, Reuse or Recycle Material (including end-destination)	Projected Quantity (Metric Tonnes)		
			Reuse	Recycle	Landfill
Masonry and Pavement					
Asphalt (cu. m.)	0.00				0.00
Concrete (walls, floors, stairs)	0.00				0.00
Brick, block, etc.	0.00				0.00
Stone (foundation)	0.00				0.00
Glass masonry	0.00				0.00
Marble	0.00				0.00
Granite	0.00				0.00
Clay tile	0.00				0.00
Other	0.00				0.00
Walls and Ceilings					
Drywall (12.5 mm)	0.00				0.00
Drywall (19 mm)	0.00				0.00
Cellulose insulation	0.00				0.00
Fiberglass insulation	0.00				0.00
Solid SM insulation	0.00				0.00
Ceiling tile (19 mm standard)	0.00				0.00
Glass (5 - 6 mm)	0.00				0.00
Acoustic composite (ceilings, walls)	0.00				0.00
Other	0.00				0.00
Windows and Doors					
Doors					
Wood (solid or hollow core)	0.00				0.00
Metal (hollow metal)	0.00				0.00
Garage	0.00				0.00
Windows	0.00				0.00
Wood frame	0.00				0.00
Plastic frame	0.00				0.00
Aluminum frame	0.00				0.00
Door Hardware	0.00				0.00
Locksets	0.00				0.00
Hinges, plates, stops, etc.	0.00				0.00
Other (closers, operators, etc.)	0.00				0.00
Other	0.00				0.00
Wood					
Rough (crating, timber, etc.)	0.00				0.00
Dimension (3 m studs)	0.00				0.00
Plywood (17mm)	0.00				0.00
Hardwood (floor)	0.00				0.00
Other	0.00				0.00
Millwork and Finish Carpentry					
Baseboards and casing (50 mm ht.)	0.00				0.00
Lower cabinets (c/w doors)	0.00				0.00
Upper cabinets (c/w doors)	0.00				0.00
Counters	0.00				0.00
Other	0.00				0.00

Flooring				
Carpet (roll)	0.00			0.00
Carpet tile	0.00			0.00
Sheet vinyl and linoleum	0.00			0.00
Rubber cove or carpet base	0.00			0.00
Terrazzo - 25 mm	0.00			0.00
Ceramic Tiles	0.00			0.00
Other	0.00			0.00
Metal				
Steel (structural, stairs, fabrications, joists, deck, siding)	0.00			0.00
Aluminum (structural, siding)	0.00			0.00
Light Metal	0.00			0.00
Studs	0.00			0.00
Ceiling grid	0.00			0.00
Miscellaneous	0.00			0.00
Other	0.00			0.00
Mechanical				
HVAC				
Solid ducts	0.00			0.00
Flex ducts	0.00			0.00
Metal diffuser	0.00			0.00
Light diffuser (boot only)	0.00			0.00
Plastic grilles	0.00			0.00
VAV boxes	0.00			0.00
Heat coils	0.00			0.00
A/C units, fan coil units, exhaust fans	0.00			0.00
Plumbing	0.00			0.00
Copper piping (12.5 to 19mm)	0.00			0.00
Steel piping (38 to 50mm)	0.00			0.00
Plastic piping (38 to 50mm)	0.00			0.00
Fixtures	0.00			0.00
Sinks (ceramic/porcelain)	0.00			0.00
Sinks (metal)	0.00			0.00
Faucets	0.00			0.00
Water Closet	0.00			0.00
Urinals (wall hung)	0.00			0.00
Other (drinking water fountain, insulation)	0.00			0.00
Electrical				
Wiring				
Data	0.00			0.00
Electrical (aluminum, copper, iron, etc)	0.00			0.00
Junction and outlet boxes (standard)	0.00			0.00
Cover plates	0.00			0.00
Electrical panels	0.00			0.00
Conduit (25 mm)	0.00			0.00
Conduit (50 mm)	0.00			0.00
Lighting				
Fluorescent fixture (600 X 1200)	0.00			0.00
Fluorescent fixture (300 X 1200)	0.00			0.00
Ballast	0.00			0.00
Lamps	0.00			0.00
Complete fixture (600 X 1200)	0.00			0.00
Complete fixture (300 X 1200)	0.00			0.00
Emergency battery lights	0.00			0.00
Exit lights	0.00			0.00
Fire bells/alarms	0.00			0.00
Miscellaneous (switches, sensors, etc.)	0.00			0.00
Other	0.00			0.00

Roofing					
Shingles - asphalt	0.00				0.00
Tin	0.00				0.00
Waterproof EDPM	0.00				0.00
Waterproof PVC	0.00				0.00
Tar and gravel	0.00				0.00
Other	0.00				0.00
Specialties & Miscellaneous					
Office Furnishings	0.00				0.00
Furniture (workstations and chairs)	0.00				0.00
Shelving & Filing Cabinets	0.00				0.00
Bulletin and white boards	0.00				0.00
Building Furnishings	0.00				0.00
Window Coverings (rolling shutters, blinds)	0.00				0.00
Signs	0.00				0.00
Lockers	0.00				0.00
Metal partition (toilet)	0.00				0.00
Plastic partition (toilet)	0.00				0.00
Stud-type partition (dismountable)	0.00				0.00
Specialized Equipment	0.00				0.00
Food service equipment	0.00				0.00
Parking control equipment	0.00				0.00
Waste/cleaning equipment	0.00				0.00
Refrigeration equipment	0.00				0.00
Lifts	0.00				0.00
Elevators	0.00				0.00
Escalators	0.00				0.00
Dumbwaiters	0.00				0.00
Communications	0.00				0.00
Telecom raceways/cables	0.00				0.00
Terminals and connectors	0.00				0.00
Other	0.00				0.00
Packaging					
Cardboard Packaging	0.00				0.00
Plastic packaging	0.00				0.00
Other	0.00				0.00
Other					
	0.00				0.00
	0.00				0.00
	0.00				0.00
	0.00				0.00
	0.00				0.00
	0.00				0.00
Total	0.00		0.00	0.00	0.00

NRC Construction, Renovation and Demolition WASTE REDUCTION WORK PLAN SUMMARY

Project Name	0
Project Type (Construction, Renovation or Demolition)	0
Area (sq. m)	0
Site Address	0
Contact Person & Telephone	0
Date	

Waste Management Summary								
WASTE CATEGORY	Estimated Quantity (Metric Tonnes)	Proposed Action to Reduce, Reuse or Recycle Material (including end-destination)	Projected Quantity (Metric Tonnes)			Potential Diversion Rate	Start date	End Date
			Reuse	Recycle	Landfill			
Masonry and Pavement	0.00		0.00	0.00	0.00	#DIV/0!		
Walls and Ceilings	0.00		0.00	0.00	0.00	#DIV/0!		
Windows and Doors	0.00		0.00	0.00	0.00	#DIV/0!		
Wood	0.00		0.00	0.00	0.00	#DIV/0!		
Millwork and Finish Carpentry	0.00		0.00	0.00	0.00	#DIV/0!		
Flooring	0.00		0.00	0.00	0.00	#DIV/0!		
Metal	0.00		0.00	0.00	0.00	#DIV/0!		
Mechanical:								
HVAC	0.00		0.00	0.00	0.00	#DIV/0!		
Plumbing	0.00		0.00	0.00	0.00	#DIV/0!		
Fixtures	0.00		0.00	0.00	0.00	#DIV/0!		
Other	0.00		0.00	0.00	0.00	#DIV/0!		
Electrical:								
Wiring	0.00		0.00	0.00	0.00	#DIV/0!		
Lighting	0.00		0.00	0.00	0.00	#DIV/0!		
Other	0.00		0.00	0.00	0.00	#DIV/0!		
Roofing	0.00		0.00	0.00	0.00	#DIV/0!		
Specialties & Miscellaneous	0.00		0.00	0.00	0.00	#DIV/0!		
Packaging	0.00		0.00	0.00	0.00	#DIV/0!		
Other	0.00		0.00	0.00	0.00	#DIV/0!		
TOTAL	0.00		0.00	0.00	0.00	#DIV/0!		

NRC Construction, Renovation and Demolition FINAL DIVERSION REPORT

Project Name	0
Project Type (Construction, Renovation or Demolition)	0
Area (sq. m)	0
Site Address	0
Contact Person & Telephone	0
Date	

Material	Actual Weight Diverted (metric tonnes)		Final Destination and End-Use of Diverted Materials	Total Weight Landfilled (metric tonnes)	TOTAL WEIGHT (metric tonnes)	Diversion Rate
	Re-used	Recycled				
Masonry and Pavement					0	#DIV/0!
Walls and Ceilings					0	#DIV/0!
Metal					0	#DIV/0!
Mechanical:						
HVAC					0	#DIV/0!
Plumbing					0	#DIV/0!
Fixtures					0	#DIV/0!
Other					0	#DIV/0!
Windows and Doors					0	#DIV/0!
Wood					0	#DIV/0!
Millwork and Finish Carpentry					0	#DIV/0!
Flooring					0	#DIV/0!
Electrical:						
Wiring					0	#DIV/0!
Lighting					0	#DIV/0!
Other					0	#DIV/0!
Roofing					0	#DIV/0!
Specialties & Miscellaneous					0	#DIV/0!
Cardboard					0	#DIV/0!
Other Packaging					0	#DIV/0!
Mixed Recycling					0	#DIV/0!
General Waste					0	#DIV/0!
Other					0	#DIV/0!
TOTAL	0	0		0	0	#DIV/0!

Project Control

[Control Sheet](#)
[Revision Control](#)

Heating / Cooling Systems

[Air-Cooled Chiller](#) x
[Boiler](#)
[Chilled Beam](#)
[Cooling Tower](#)
[Electric Domestic Hot Water Tank](#)
[Electric Duct Heater](#)
[Expansion Tank](#) x
[Gas Domestic Hot Water Tank](#)
[Glycol Fill Station](#)
[Heat Exchanger](#)
[Heating/Cooling Coil](#)
[Make-up Water Assembly](#)
[Pump](#) x
[Radiation Unit](#)
[Split System AC Unit](#)
[Underfloor Radiant Heating](#)
[Unit Heater](#)
[Water-Cooled Chiller](#)

Ventilation

[AHU \(Built-up\)](#)
[Fan Coil Unit](#)
[Fan](#)
[Heat Pump with VRF](#)
[Humidifier](#)
[Lab Ventilation \(Air Valves & Fume Hoods\)](#)
[Motorized Damper](#)
[Unit Ventilator](#)
[VAV & Fan Powered Boxes](#)

Gas Monitoring

[Gas Monitoring Systems](#)

Building Automation Verifications

[BAS Field Equipment Checklist](#) x
[BAS Graphics Standards Checklist](#) x
[BAS Sequence Standards Checklist](#) x

Metering

[Water Meter](#)
[Water Meter - Table 1: Meter Flow Ranges](#)
[Water Meter - Table 2: Validation Format](#)
[Steam Meter](#)
[Steam Meter - Table 1: Meter Flow Ranges kg/h](#)
[Steam Meter - Table 2: Meter Flow Ranges MJ/h](#)
[Steam Meter - Table 3: Validation Format](#)



Commissioning (Cx) Project Control Sheet

6032 S-77- Steam to HW Conversion

Project Designers:	Name - Architectural Designer	RPPM-Engineering	cell number	email
	Kevin Li	RPPM-Engineering	cell number	email
	John Goodwin	RPPM-Engineering	613-299-0591	john.goodwin@nrc-cnrc.gc.ca
	Structural Engineer	Consulting Firm Name	cell number	email
	Other A&E Support Names	Consulting Firm Name	cell number	email
Project Manager:	Allan Smith	RPPM-Project Delivery	cell number	allan.smith@nrc-cnrc.gc.ca
Project Coordinator:	Name	RPPM-Project Delivery	cell number	email
BAS Control Specialist:	Name	O&M BAS Team	cell number	email
Building Coordinator:	Name	O&M Client Services	cell number	email
Client Contact:	Name	CBI	cell number	email
PMO:	9100XXXX	WBS Element:	A1-XXXXXX-XX-XX	
General Contractor:	Company Name			
	Primary Contact Name	Title	cell number	email
Commissioning Authority (Agent):	Company Name			
	Primary Contact Name	Title	cell number	email
Controls (Ainsworth) Contact:	Ainsworth Canada			
	Primary Contact Name	Title	cell number	email



Commissioning (Cx) List of Participants Execution (E), Verification (V), and Approval (A)

Systems for Cx	Company	Participant Name	Activity	Signature and Date
Plumbing	Company Name	Participant(s) Name	Execution <input type="checkbox"/> Verification <input type="checkbox"/> Approval <input type="checkbox"/>	
Ventilation	Company Name	Participant(s) Name	Execution <input type="checkbox"/> Verification <input type="checkbox"/> Approval <input type="checkbox"/>	
BAS	Company Name	Participant(s) Name	Execution <input type="checkbox"/> Verification <input type="checkbox"/> Approval <input type="checkbox"/>	
Electrical	Company Name	Participant(s) Name	Execution <input type="checkbox"/> Verification <input type="checkbox"/> Approval <input type="checkbox"/>	
Balancing	Company Name	Participant(s) Name	Execution <input type="checkbox"/> Verification <input type="checkbox"/> Approval <input type="checkbox"/>	
Witness - General Contractor	Company Name	Participant(s) Name	Execution <input type="checkbox"/> Verification <input type="checkbox"/> Approval <input type="checkbox"/>	
Witness - RPPM Departmental Rep(s)	Company Name	Participant(s) Name	Execution <input type="checkbox"/> Verification <input type="checkbox"/> Approval <input type="checkbox"/>	
Commissioning Authority (Agent)	Company Name	Participant(s) Name	Execution <input type="checkbox"/> Verification <input type="checkbox"/> Approval <input type="checkbox"/>	



Commissioning (Cx) Sign-Off

EQUIPMENT INFORMATION			
SAP Equipment ID	Tasks Complete (select Yes, No or N/A)	Supervised By	Date
PREREQUISITES			
SAP Equipment ID	Tasks Complete (select Yes, No or N/A)	Supervised By	Date
EQUIPMENT ITEMS TO BE VERIFIED			
SAP Equipment ID	Tasks Complete (select Yes, No or N/A)	Supervised By	Date

ELEMENTS TO BE MEASURED FOR DESIGN VALIDATION			
SAP Equipment ID	Tasks Complete (select Yes, No or N/A)	Supervised By	Date
CONTROL SYSTEM ITEMS TO BE VERIFIED			
SAP Equipment ID	Tasks Complete (select Yes, No or N/A)	Supervised By	Date
CONTROL SYSTEM PRE-FUNCTIONAL CHECKS			
SAP Equipment ID	Tasks Complete (select Yes, No or N/A)	Supervised By	Date



CONTROL SYSTEM FUNCTIONAL PERFORMANCE TESTS			
SAP Equipment ID	Tasks Complete (select Yes, No or N/A)	Supervised By	Date
FINAL SIGNATURES			
Project Manager:		O&M Project Acceptance Representative:	
Design Engineer:			
BAS Control Specialist:		E&C Handover Representative:	
O&M Supervisor:			

NRC BAS Field Equipment Checklist

[return to index](#)

To be completed by BAS Contractor and submitted to NRC team for review prior to start of commissioning.			
Item	Qty	Yes/No	Deficiencies
Nameplates for panel/cabinets - Standard is black on white melamine - 1" x 2-3/4"			
Nameplates for controllers - Standard is black on white stick-on label			
Field controllers - Controllers located in finished ceiling space must have an orange circle on t-bar below the controller identifying its location			
Nameplate for Field Devices - Standard is plastic encased card			
Nameplates for room sensors - Standard is black on white stick-on label			
Warning signs - Starters under remote automatic control			
Wiring:			
Tape markings on wiring inside panels to identify BAS point name			
Power wiring - identify circuit breaker panel/circuit breaker number inside each EMCS panel			
Conduit:			
New conduit to be in pre-painted orange conduit			
Existing conduit to use florescent orange paint to identify control wiring			
Prepaint box covers and fittings in florescent orange			

NRC BAS Graphics Standard Checklist

To be completed by BAS Contractor and submitted NRC for review prior to start of commissioning.						
Item	Building Name					
	System Name	i.e 19AHU01	System Name	i.e 19AHU01	System Name	i.e 19AHU01
Building name, system name and system description to be identified on each i.e. M24 - 24AHU01 – Environmental Lab						
Location of system to be identified on each graphic (directly under the system name). (i.e. Basement Mechanical Room 02)						
NRC equipment names used to identify mechanical equipment. Format to be black on white consistent with NRCs equipment tags. (except bacnet points- black on blue background)						
Network point path to display when mouse is over BAS point. Applicable for all points						
Provide unique sequence of operation graphic or pop-up window in plain English for each graphic that is depicted on OWS. Provide access to plain English sequence of operation graphic by link button on each system graphic. Sequences operation to be stored on the RPPM BAS server						
Written sequences to use the same naming convention as on the graphics						
Each system to have a link to the appropriate floor plan						
Floor plan graphics (complete with roof plans) are required showing the following:						
Equipment locations						
Controllers and their wiring runs. (location specifics must be included on graphics such as ceiling, closet, etc.						
Sensor locations						
Separate floor plans for temperature locations, controller locations and equipment locations to be the template to accommodate larger buildings						
Floor plan graphics to be colour coded to identify the areas served by each air handling unit						
Each building to have a heating, cooling and ventilation summary table						
Each converted building to have a lighting page						
Items grouped under miscellaneous alarms must also have equipment locations identified						
Each system to have identified schedules						

NRC BAS Sequence Standard Checklist

To be completed by BAS Contractor and submitted NRC for review prior to start of commissioning.																		
Item	Building Name																	
	System Name	i.e 19AHU01	System Name	i.e 19AHU01	System Name	i.e 19AHU01												
<p>Enthalpy for all applicable systems. The economizer flag is used to signal the damper economizer so that the outdoor air is not to be used as a cooling source. Calculate the value of the Outdoor Enthalpy using the current Outdoor Air Temperature and relative humidity. Calculate the Enthalpy for the Indoor condition of 72F and 45%RH. This is the Indoor Enthalpy Setpoint. Set the economizer flag to OFF when the outdoor enthalpy is greater than the Indoor Enthalpy Setpoint. Set the Economizer flag to ON when the outdoor enthalpy is less than the (Indoor Setpoint * 0.9)</p> $OAE_{nth} = 9 + 0.27 * (\text{Site_Oat} - 35) + 0.5 * (\text{Site_Oat} - 35) * (\text{Site_Oah} / 100) \text{ Btu/lb}$ $OAE_{nthSp} = \text{based on a space setpoint of 72F and RH of 45\%} = 8 + 0.27 * (72 - 35) + 0.5 * (72 - 35) * 45 / 100 = 26.3 \text{ Btu/lb}$ $\text{Enthalpy} = ((Oa_{nth} \geq Oa_{nthSp}) \text{ or } (\text{Enthalpy and } (Oa_{nth} \geq (Oa_{nthSp} * 0.9))))$																		
<p>SSTO - Start Stop Time Optimization. Identify occupancy time and use BAS to calculate the required system start time. Systems to operate in full recirculation until occupancy time unless free cooling is available. During the heating season, when system is heated solely via perimeter radiation/reheats, system occupancy will be the system start</p>																		
<p>Occupied/Unoccupied Set Points -</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Occupied</th> <th>Summer</th> <th>Winter</th> </tr> </thead> <tbody> <tr> <td>Temperature (Occupied)</td> <td>24 +/-1C</td> <td>22 +/-1C</td> </tr> <tr> <td>Temperature (Unoccupied)</td> <td>28C</td> <td>18C</td> </tr> <tr> <td>Humidity</td> <td colspan="2">60% - 25%</td> </tr> </tbody> </table> <p>Essentially we would have a winter set-point (22C) and a summer set-point (24C) that are toggled when we move from cooling to heating season and vice versa. The individual room controls would allow local control up or down 1C. During unoccupied hours, system to operate in full recirculation to maintain the unoccupied setpoints unless free cooling is available</p>	Occupied	Summer	Winter	Temperature (Occupied)	24 +/-1C	22 +/-1C	Temperature (Unoccupied)	28C	18C	Humidity	60% - 25%							
Occupied	Summer	Winter																
Temperature (Occupied)	24 +/-1C	22 +/-1C																
Temperature (Unoccupied)	28C	18C																
Humidity	60% - 25%																	
<p>GTA - Global Temperature Adjustment. Systems to be programmed to allow for GTA that can be used on a call for curtailment</p>																		
<p>SAT Reset - Implement a supply air temperature reset based on the return or outside air temperature</p>																		
<p>MAD - Mixing air dampers to be controlled by SAT. Mixed air dampers to modulate to maintain supply air temperature at set point. If the unit goes into enthalpy mode, MAD will go to minimum position</p>																		

Item	Building Name											
	System Name	i.e 19AHU01	System Name	i.e 19AHU01	System Name	i.e 19AHU01						
PHC - Preheat coil reset based on outside air temperature <table border="1" style="margin-left: auto; margin-right: auto;"> <thead> <tr> <th>OAT °F</th> <th>PHC %</th> </tr> </thead> <tbody> <tr> <td>30</td> <td>100</td> </tr> <tr> <td>53</td> <td>0</td> </tr> </tbody> </table>	OAT °F	PHC %	30	100	53	0						
OAT °F	PHC %											
30	100											
53	0											
CO₂ - The MAD minimum will be overridden if the return or floor CO ₂ sensor is above the setpoint. If there is more than one floor CO ₂ sensor, the MAD will be overridden by the maximum CO ₂ sensed on the floors												
RAH - Return air humidity - The humidifier valve will modulate to maintain the return air humidity RAH at setpoint												
APL - All Points Log - Scheduled BAS points to be added to the APL in order to capture equipment left on that should be off												

Electric Duct Heater Cx Checklist

EQUIPMENT INFORMATION

SAP Equipment ID:	
Project No:	6032
Drawing No:	
Manufacturer:	
Model No.:	
Serial No.:	
Safeties Included:	<input type="checkbox"/> freeze stat <input type="checkbox"/> air flow switch <input type="checkbox"/> other (identify):
Area Served:	
Location:	
Duct Heater Application:	<input type="checkbox"/> OA preheat <input type="checkbox"/> reheat <input type="checkbox"/> other (identify):
	Size (Width x Length):
	Capacity (kW)
	Electrical: V/ ϕ / Hz

PREREQUISITE (check to confirm that the following prerequisites are documented)

<input type="checkbox"/> Shop Drawing Received	<input type="checkbox"/> Installation Complete
<input type="checkbox"/> Start-up Process per Manufacturer's Instructions Complete	<input type="checkbox"/> Connected to BAS
<input type="checkbox"/> Sequence Complete	<input type="checkbox"/> Seismic Review Letter Received
Comments:	

EQUIPMENT ITEMS TO BE VERIFIED

This checklist does not take the place of the manufacturer's recommended checkout and start-up procedures or report.

Equipment Items	Yes / No	Comments
Duct heater installation & start-up completed and form/report attached		
Equipment identification label has been applied and follows NRC naming convention		
Local protection/interlocks/alarms are functional		
Verifications of abnormal noise and vibration		
Comments:		

ELEMENTS TO BE MEASURED FOR DESIGN VALIDATION

This checklist does not take the place of the manufacturer's recommended checkout and start-up procedures or report.

Measured Element	Instrument (portable/BAS/local)	Design	Measured 1	Measured 2
Entering Air Temp (°C - °F)				
Leaving Air Temp (°C - °F)				
Voltage (T_1-T_2 , T_2-T_3 , T_3-T_1)				
Amperage (I_1 , I_2 , I_3)				
Fuse/Breaker Rating				
O/L Protection - Adjustment				
Comments:				

CONTROL SYSTEM ITEMS TO BE BE VERIFIED

Control System Items	Yes / No	Comments
NRC Graphics Standard Checklist Completed		
NRC BAS Field Equipment Checklist Completed		
Controller online		
Graphics created		
Link to written sequence on system graphic		
Equipment shown on BAS floor plan		
Network layout shown on BAS floor plan		
SAP Equipment ID used in BAS		
Nametags for electric duct heater and BAS control points installed		
BAS Controller labelled		
Power source labelled on controller		
Comments:		

CONTROL SYSTEM PRE-FUNCTIONAL CHECKS - TBC

Observations, Notes & Comments

Initial Conditions:

Manually command heater to obtain:

From BAS, command heater ON

Record (mA):

Physically check heater is ON:

Y N

From BAS, command heater OFF

Record (mA):

Physically check heater is OFF:

Y N

Back to automatic

Return all changed control parameters and conditions to their pre-functional check values.

Comments:

TBC - To be completed by Cx Agent and Contractor based on the control sequence.

CONTROL SEQUENCE FUNCTIONAL PERFORMANCE TEST - TBC

Functional Performance Test Procedure	Expected, Actual Response & Comments	Pass (Y / N)
System stopped:		
System start-up:		
Normal mode:		
Control points:		
Local protection:		
Alarms:		

Return all changed control parameters and conditions to their pre-functional performance test values.

Comments:

TBC - To be completed by Cx Agent and Contractor based on the control sequence.

Heating or Cooling Coil Cx Checklist

EQUIPMENT INFORMATION

SAP Equipment ID:	
Project No:	6032
Drawing No:	
Manufacturer:	
Model No.:	
Serial No.:	
Area Served:	
Location:	
Service:	
Type:	<input type="checkbox"/> Glycol <input type="checkbox"/> Electric
Seasonal Draining Required:	<input type="checkbox"/> Yes <input type="checkbox"/> No
Fluid Flow:	
Fluid Pressure Drop:	
Airflow velocity:	
Airflow:	
Airside Pressure Drop:	
Capacity:	
Actuator:	
Control Valve:	<input type="checkbox"/> 2-Way <input type="checkbox"/> 3-Way

PREREQUISITE (check to confirm that the following prerequisites are documented)

<input type="checkbox"/> Shop Drawing Received	<input type="checkbox"/> Installation Complete
<input type="checkbox"/> Start-up Process per Manufacturer's Instructions Complete	<input type="checkbox"/> Connected to BAS
<input type="checkbox"/> Sequence Complete	<input type="checkbox"/> System Balanced
<input type="checkbox"/> System Cleaned and Strainer Clean	Control Valve: <input type="checkbox"/> Yes (spec. attached) <input type="checkbox"/> No

Comments:

EQUIPMENT ITEMS TO BE VERIFIED

This checklist does not take the place of the manufacturer's recommended checkout and start-up procedures or report.

Equipment Items	Yes / No	Comments
Coil installation & start-up completed and form/report attached		
Equipment identification label has been applied and follows NRC naming convention		
No evidence of damage		
Comments:		

ELEMENTS TO BE MEASURED FOR DESIGN VALIDATION

This checklist does not take the place of the manufacturer's recommended checkout and start-up procedures or report.

Measured Element	Instrument (portable/BAS/local)	Design	Measured 1	Measured 2
Airside:				
Airflow (l/s - cfm)				
Entering Air Temp (°C - °F)				
Leaving Air Temp (°C - °F)				
Temperature Difference (°C - °F)				
Airside Pressure Drop (Pa - "H ₂ O)				
Capacity (kW - BTU/h)				
Number of rows in coil				
Fins Per Inch (FPI)				
Fluid Side:				
Flow (l/s - gpm)				
Entering Fluid Temp (°C - °F)				
Leaving Fluid Temp (°C - °F)				
Temperature Difference (°C - °F)				
Fluid Pressure Drop (Pa - "H ₂ O)				
Capacity (kW - BTU/h)				

Number of rows in coil				
Fins Per Inch (FPI)				
Comments:				

CONTROL SYSTEM ITEMS TO BE BE VERIFIED

Control System Items	Yes / No	Comments
NRC Graphics Standard Checklist Completed		
NRC BAS Field Equipment Checklist Completed		
Graphics created		
Link to written sequence on system graphic		
Equipment shown on BAS floor plan		
SAP Equipment ID used in BAS		
Nametags for coil and BAS control points installed		
Comments:		

CONTROL SYSTEM PRE-FUNCTIONAL CHECKS - TBC

<i>Observations, Notes & Comments</i>		
Initial Conditions:		
Cooling Water Valve	Spring range in PSIG (if pneumatic):	
	Corresponding BAS signal (mA):	
	Cv	
Heating Water Valve	Spring range in PSIG (if pneumatic):	
	Corresponding BAS signal (mA):	
	Cv	
From BAS, command CWV closed to coil	Record I/P current transducers (mA):	
	Physically check valve is closed:	<input type="checkbox"/> Yes <input type="checkbox"/> No
From BAS, command CWV open to coil	Record I/P current transducers (mA):	
	Physically check valve is open:	<input type="checkbox"/> Yes <input type="checkbox"/> No
From BAS, command HWV closed to coil	Record I/P current transducers (mA):	
	Physically check valve is closed:	<input type="checkbox"/> Yes <input type="checkbox"/> No
From BAS, command HWV open to coil	Record I/P current transducers (mA):	
	Physically check valve is open:	<input type="checkbox"/> Yes <input type="checkbox"/> No
Back to automatic:		
Return all changed control parameters and conditions to their pre-functional check values.		

Comments:

TBC - To be completed by Cx Agent and Contractor based on the control sequence.

CONTROL SEQUENCE FUNCTIONAL PERFORMANCE TEST - TBC

Functional Performance Test Procedure	Expected, Actual Response & Comments	Pass (Y / N)
System stopped:		
System start-up:		
Normal mode:		
Control points:		
Local protection:		
Alarms:		

Return all changed control parameters and conditions to their pre-functional performance test values.

Comments:

TBC - To be completed by Cx Agent and Contractor based on the control sequence.

Radiation Unit Cx Checklist

EQUIPMENT INFORMATION

SAP Equipment ID:	
Project No:	6032
Drawing No:	
Manufacturer:	
Model No.:	
Serial No.:	
Area Served:	
Location:	
Heating Capacity kW (BTU):	
Identify System Rad Unit is Interlocked with (i.e. 20FCU04):	<input type="checkbox"/> Specify: _____ <input type="checkbox"/> None

PREREQUISITE (check to confirm that the following prerequisites are documented)

<input type="checkbox"/> Shop Drawing Received	<input type="checkbox"/> Installation Complete
<input type="checkbox"/> Start-up Process per Manufacturer's Instructions Complete	<input type="checkbox"/> Connected to BAS
<input type="checkbox"/> Sequence Complete	<input type="checkbox"/> System Balanced
<input type="checkbox"/> Seismic Review Letter Received	
Comments:	

EQUIPMENT ITEMS TO BE VERIFIED

This checklist does not take the place of the manufacturer's recommended checkout and start-up procedures or report.

Equipment Items	Yes / No	Comments
Unit installed to manufacturer's recommendations		
Manufacturer's start-up procedure and report attached		
Equipment identification label has been applied and follows NRC naming convention		
Approved isolation installed		
Unit interior clean and free of debris		
Heating coil combed		
Control valve installed		
Strainer, air vent and drain installed		
Circuit balancing valve installed to manufacturer's recommendations		
Comments:		

ELEMENTS TO BE MEASURED FOR DESIGN VALIDATION

This checklist does not take the place of the manufacturer's recommended checkout and start-up procedures or report.

Measured Element	Instrument (portable/BAS/local)	Design	Measured 1	Measured 2
Entering Air Temp (°C - °F)				
Leaving Air Temp (°C - °F)				
Entering Water Temp (°C - °F)				
Leaving Water Temp (°C - °F)				
Flow rate (L/s - GPM)				
Pressure drop (Pa - PSI)				
Comments:				

CONTROL SYSTEM ITEMS TO BE BE VERIFIED

Control System Items	Yes / No	Comments
NRC Graphics Standard Checklist Completed		
NRC BAS Field Equipment Checklist Completed		
NRC Sequence Standard Checklist Completed		
Have scheduled points been added to the All Points Log (APL)		
Controller online		
Has Global Temperature Adjustment (GTA) been incorporated into the program		
Graphics created		
Link to written sequence on system graphic		
Equipment shown on BAS floor plan		
Network layout shown on BAS floor plan		
SAP Equipment ID used in BAS		
Nametags for Radiation Unit and BAS control points installed		
BAS Controller labelled		
Power source labelled on controller		

If controller is mounted in ceiling space, has location of controller been identified on t-bar with an orange dot sticker		
Comments:		

CONTROL SYSTEM PRE-FUNCTIONAL CHECKS - TBC

Observations, Notes & Comments

Initial Conditions:		
Space Temp (°C):	BAS reading:	Thermocouple reading:
Heating Water Valve	Spring range in PSIG (if pneumatic):	
	Corresponding BAS signal (mA):	
	Cv	
Override the heating water valve to obtain:		
From BAS, command HWV closed	Record I/P current transducer or electronic valve (mA):	
	Physically check valve is closed:	<input type="checkbox"/> Yes <input type="checkbox"/> No
From BAS, command HWV open	Record I/P current transducer or electronic valve (mA):	
	Physically check valve is open:	<input type="checkbox"/> Yes <input type="checkbox"/> No
Return all changed control parameters and conditions to their pre-functional check values.		
Comments:		

TBC - To be completed by Cx Agent and Contractor based on the control sequence.

CONTROL SEQUENCE FUNCTIONAL PERFORMANCE TEST - TBC

Functional Performance Test Procedure	Expected, Actual Response & Comments	Pass (Y / N)
System stopped:		
System start-up:		
Normal mode:		
Lower room temperature set point to close perimeter HV and check if any are leaking using thermal camera	Thermal camera should not detect any leaks	
Control points:		
Local protection:		

Alarms:		
<i>Return all changed control parameters and conditions to their pre-functional performance test values.</i>		
Comments:		

TBC - To be completed by Cx Agent and Contractor based on the control sequence.

Unit Heater Cx Checklist

EQUIPMENT INFORMATION

SAP Equipment ID:	
Project No:	6032
Drawing No:	
Manufacturer:	
Model No.:	
Serial No.:	
Area Served:	
Location:	
g Capacity kW (BTU):	
Supply Fan L/s (CFM Range):	<input type="checkbox"/> Yes <input type="checkbox"/> No
Electrical: V/ ϕ / Hz	
Heating Type:	<input type="checkbox"/> Electric <input type="checkbox"/> Hydronic <input type="checkbox"/> Steam <input type="checkbox"/> Natural Gas
Fan Motor Type:	<input type="checkbox"/> ON/OFF <input type="checkbox"/> ECM
Motor HP:	

PREREQUISITE (check to confirm that the following prerequisites are documented)

<input type="checkbox"/> Shop Drawing Received	<input type="checkbox"/> Installation Complete
<input type="checkbox"/> Start-up Process per Manufacturer's Instructions Complete	<input type="checkbox"/> Connected to BAS
<input type="checkbox"/> Sequence Complete	<input type="checkbox"/> System Balanced
<input type="checkbox"/> Seismic Review Letter Received	

Comments:

EQUIPMENT ITEMS TO BE VERIFIED

This checklist does not take the place of the manufacturer's recommended checkout and start-up procedures or report.

Equipment Items	Yes / No	Comments
Equipment identification label has been applied and adheres to NRC naming convention		
Unit installed to manufacturer's recommendations		
Unit heater installation & start-up completed and form/report attached		
All maintenance access requirements met		
Approved isolation installed		
Unit transit bolts removed		
Unit interior clean and free of debris		
Heating coil combed		
Fan rotation correct		

Thermostat installed and wired		
Circuit balancing valve installed as manufacturer's recommendations		
Electrical wiring complete and tested		
Seismic bracing installed and approved by seismic Engineer		
Comments:		

ELEMENTS TO BE MEASURED FOR DESIGN VALIDATION

This checklist does not take the place of the manufacturer's recommended checkout and start-up procedures or report.

Measured Element	Instrument (portable/BAS/local)	Design	Measured 1	Measured 2
Entering air temp (°C - °F)				
Leaving air temp (°C - °F)				
Amperage draw				
Fuse/breaker rating (A)				
Hydronic Units:				
Entering water temp (°C - °F)				
Leaving water temp (°C - °F)				
Flowrate (GPM - L/s)				
Pressure drop (w.g - Pa)				
Electric Units:				
Capacity (BTU - kW)				
Number of steps				
SCR				
Comments:				

CONTROL SYSTEM ITEMS TO BE BE VERIFIED

Control System Items	Yes / No	Comments
NRC Graphics Standard Checklist Completed		
NRC BAS Field Equipment Checklist Completed		
NRC Sequence Standard Checklist Completed		
Have scheduled points been added to the All Points Log (APL)		

Controller online		
Has Global Temperature Adjustment (GTA) been incorporated into the program		
Graphics created		
Link to written sequence on system graphic		
Equipment shown on BAS floor plan		
Network layout shown on BAS floor plan		
SAP Equipment ID used in BAS		
Nametags for Unit Heater and BAS control points installed		
BAS Controller labelled		
Power source labelled on controller		
If controller is mounted in ceiling space, has location of controller been identified on t-bar with an orange dot sticker		
Comments:		

CONTROL SYSTEM PRE-FUNCTIONAL CHECKS - TBC

Observations, Notes & Comments

Initial Conditions:		
As-Found Space Temperature Set Point:		
As-Found Occupied Space Temperature Set Point:		
As-Found Unoccupied Space Temperature Set Point:		
Space Temp (°C):	BAS reading:	Thermocouple reading:
Manually override the heating valve to obtain:		
Heating Water Valve	Spring range in PSIG (if pneumatic):	
	Corresponding BAS signal (mA):	
	Cv:	
From BAS, command HWV closed	Record mA for I/P current transducer / electronic valve:	
	Physically check valve is closed:	<input type="checkbox"/> Y <input type="checkbox"/> N
From BAS, command HWV open	Record mA for I/P current transducer / electronic valve:	
	Physically check valve is open:	<input type="checkbox"/> Y <input type="checkbox"/> N
From BAS, command Fan On		
Return to automatic		
Return all changed control parameters and conditions to their pre-functional check values.		
Comments:		

--

TBC - To be completed by Cx Agent and Contractor based on the control sequence.

CONTROL SEQUENCE FUNCTIONAL PERFORMANCE TEST - TBC

Functional Performance Test Procedure	Expected, Actual Response & Comments	Pass (Y / N)
System stopped:	Fan OFF and HWV closed	
System start-up:		
Normal mode:		
Adjust space temperature set point from space sensor	Verify that temperature set point is operator adjustable from space (room) temperature sensor. Change should be viewed from BAS	
From BAS, change space temperature set point	Verify that temperature set point changed	
Decrease room temperature set point to below actual space temperature	Fan should be de-energized and HWV modulates closed. Check that there is no leakage using a thermal camera.	
Increase room temperature set point to above actual space temperature modulate HV to open and check if heating using thermal camera	Thermal camera should detect hot water on discharge. Fan should Start. If an ECM motor, fan should start in low speed and modulate to expected speed only after HWV has reached 100% open	
Control points:		
Local protection:		
Alarms:		
Back to automatic		
<i>Return all changed control parameters and conditions to their pre-functional performance test values.</i>		
Comments:		

TBC - To be completed by Cx Agent and Contractor based on the control sequence.



TP1 Amount Payable – General

1.1 Subject to any other provisions of the contract, Her Majesty shall pay the Contractor, at the times and in the manner hereinafter set out, the amount by which

1.1.1 the aggregate of the amounts described in TP2 exceeds

1.1.2 the aggregate of the amounts described in TP3

and the Contractor shall accept that amount as payment in full satisfaction for everything furnished and done by him in respect of the work to which the payment relates.

TP2 Amounts Payable to the Contractor

2.1 The amounts referred to in TP1.1.1 are the aggregate of

2.1.1 the amounts referred to in the Articles of Agreement, and

2.1.2 the amounts, if any, that are payable to the Contractor pursuant to the General Conditions.

TP3 Amounts Payable to Her Majesty

3.1 The amounts referred to in TP1.1.2 are the aggregate of the amounts, in any, that the Contractor is liable to pay Her Majesty pursuant to the contract.

3.2 When making any payments to the Contractor, the failure of Her Majesty to deduct an amount referred to in TP3.1 from an amount referred to in TP2 shall not constitute a waiver of the right to do so, or an admission of lack of entitlement to do so in any subsequent payment to the Contractor.

TP4 Time of Payment

4.1 In these Terms of Payment

4.1.1 The “payment period” means a period of 30 consecutive days or such other longer period as is agreed between the Contractor and the Departmental Representative.

4.1.2 An amount is “due and payable” when it is due and payable by Her Majesty to the Contractor according to TP4.4, TP4.7 or TP4.10.

4.1.3 An amount is overdue when it is unpaid on the first day following the day upon which it is due and payable.

4.1.4 The “date of payment” means the date of the negotiable instrument of an amount due and payable by the Receiver General for Canada and given for payment.

4.1.5 The “Bank Rate” means the discount rate of interest set by the Bank of Canada in effect at the opening of business on the date of payment.



- 4.2 The Contractor shall, on the expiration of a payment period, deliver to the Departmental Representative in respect of that payment period a written progress claim that fully describes any part of the work that has been completed, and any material that was delivered to the work site but not incorporated into the work during that payment period.
- 4.3 The Departmental Representative shall, not later than ten days after receipt by him of a progress claim referred to in TP4.2,
- 4.3.1 inspect the part of the work and the material described in the progress claim; and
- 4.3.2 issue a progress report, a copy of which the Departmental Representative will give to the Contractor, that indicates the value of the part of the work and the material described in the progress claim that, in the opinion of the Departmental Representative,
- 4.3.2.1 is in accordance with the contract, and
- 4.3.2.2 was not included in any other progress report relating to the contract.
- 4.4 Subject to TP1 and TP4.5 Her Majesty shall, not later than 30 days after receipt by the Departmental Representative of a progress claim referred to in TP4.2, pay the Contractor
- 4.4.1 an amount that is equal to 95% of the value that is indicated in the progress report referred to in TP4.3.2 if a labour and material payment bond has been furnished by the Contractor, or
- 4.4.2 an amount that is equal to 90% of the value that is indicated in the progress report referred to in TP4.3.2 if a labour and material payment bond has not been furnished by the Contractor.
- 4.5 It is a condition precedent to Her Majesty's obligation under TP4.4 that the Contractor has made and delivered to the Departmental Representative,
- 4.5.1 a statutory declaration described in TP4.6 in respect of a progress claim referred to in TP4.2,
- 4.5.2 in the case of the Contractor's first progress claim, a construction schedule in accordance with the relevant sections of the Specifications, and
- 4.5.3 if the requirement for a schedule is specified, an update of the said schedule at the times identified in the relevant sections of the Specifications.
- 4.6 A statutory declaration referred to in TP4.5 shall contain a deposition by the Contractor that
- 4.6.1 up to the date of the Contractor's progress claim, the Contractor has complied with all his lawful obligations with respect to the Labour Conditions; and
- 4.6.2 up to the date of the Contractor's immediately preceding progress claim, all lawful obligations of the Contractor to subcontractors and suppliers of material in respect of the



work under the contract have been fully discharged.

- 4.7 Subject to TP1 and TP4.8, Her Majesty shall, not later than 30 days after the date of issue of an Interim Certificate of Completion referred to in GC44.2, pay the Contractor the amount referred to in TP1 less the aggregate of
- 4.7.1 the sum of all payments that were made pursuant to TP4.4;
 - 4.7.2 an amount that is equal to the Departmental Representative's estimate of the cost to Her Majesty or rectifying defects described in the Interim Certificate of Completion; and
 - 4.7.3 an amount that is equal to the Departmental Representative's estimate of the cost to Her Majesty of completing the parts of the work described in the Interim Certificate of Completion other than the defects referred to in TP4.7.2.
- 4.8 It is a condition precedent to Her Majesty's obligation under TP4.7 that the Contractor has made and delivered to the Departmental Representative,
- 4.8.1 a statutory declaration described in TP4.9 in respect of an Interim Certificate of Completion referred to in GC44.2, and
 - 4.8.2 if so specified in the relevant sections of the Specifications, and update of the construction schedule referred to in TP4.5.2 and the updated schedule shall, in addition to the specified requirements, clearly show a detailed timetable that is acceptable to the Departmental Representative for the completion of any unfinished work and the correction of all defects.
- 4.9 A statutory declaration referred to in TP4.8 shall contain a deposition by the contractor that up to the date of the Interim Certificate of Completion the Contractor has
- 4.9.1 complied with all of the Contractor's lawful obligations with respect to the Labour Conditions;
 - 4.9.2 discharged all of the Contractor's lawful obligations to the subcontractors and suppliers of material in respect of the work under the contract; and
 - 4.9.3 discharged the Contractor's lawful obligations referred to in GC14.6.
- 4.10 Subject to TP1 and TP4.11, Her Majesty shall, not later than 60 days after the date of issue of a Final Certificate of Completion referred to in GC44.1, pay the Contractor the amount referred to in TP1 less the aggregate of
- 4.10.1 the sum of all payments that were made pursuant to TP4.4; and
 - 4.10.2 the sum of all payments that were made pursuant to TP4.7.
- 4.11 It is a condition precedent to Her Majesty's obligation under TP4.10 that the Contractor has made and delivered a statutory declaration described in TP4.12 to the Departmental Representative.



- 4.12 A statutory declaration referred to in TP4.11 shall, in addition to the depositions described in TP4.9, contain a deposition by the Contractor that all of the Contractor's lawful obligations and any lawful claims against the Contractor that arose out of the performance of the contract have been discharged and satisfied.

TP5 Progress Report and Payment Thereunder Not Binding on Her Majesty

- 5.1 Neither a progress report referred to in TP4.3 nor any payment made by Her Majesty pursuant to these Terms of Payment shall be construed as an admission by Her Majesty that the work, material or any part thereof is complete, is satisfactory or is in accordance with the contract.

TP6 Delay in Making Payment

- 6.1 Notwithstanding GC7 any delay by Her Majesty in making any payment when it is due pursuant to these Terms of Payment shall not be a breach of the contract by Her Majesty.
- 6.2 Her Majesty shall pay, without demand from the Contractor, simple interest at the Bank Rate plus 1 -1/4 per centum on any amount which is overdue pursuant to TP4.1.3, and the interest shall apply from and include the day such amount became overdue until the day prior to the date of payment except that
- 6.2.1 interest shall not be payable or paid unless the amount referred to in TP6.2 has been overdue for more that 15 days following
- 6.2.1.1 the date the said amount became due and payable, or
- 6.2.1.2 the receipt by the Departmental Representative of the Statutory Declaration referred to in TP4.5, TP4.8 or TP4.11,
- whichever is the later, and
- 6.6.2 interest shall not be payable or paid on overdue advance payments if any.

TP7 Right of Set-off

- 7.1 Without limiting any right of set-off or deduction given or implied by law or elsewhere in the contract, Her Majesty may set off any amount payable to Her Majesty by the Contractor under this contract or under any current contract against any amount payable to the Contractor under this contract.
- 7.2 For the purposes of TP7.1, "current contract" means a contract between Her Majesty and the Contractor
- 7.2.1 under which the Contractor has an undischarged obligation to perform or supply work, labour or material, or
- 7.2.2 in respect of which Her Majesty has, since the date of which the Articles of Agreement were made, exercised any right to take the work that is the subject of the contract out of the Contractor's hands.



TP8 Payment in Event of Termination

- 8.1 If the contract is terminated pursuant to GC41, Her Majesty shall pay the Contractor any amount that is lawfully due and payable to the Contractor as soon as is practicable under the circumstances.

TP9 Interest on Settled Claims

- 9.1 Her Majesty shall pay to the Contractor simple interest on the amount of a settled claim at an average Bank Rate plus 1 ¼ per centum from the date the settled claim was outstanding until the day prior to the date of payment.
- 9.2 For the purposes of TP9.1,
- 9.2.1 a claim is deemed to have been settled when an agreement in writing is signed by the Departmental Representative and the Contractor setting out the amount of the claim to be paid by Her Majesty and the items or work for which the said amount is to be paid.
- 9.2.2 an "average Bank Rate" means the discount rate of interest set by the Bank of Canada in effect at the end of each calendar month averaged over the period the settled claim was outstanding.
- 9.2.3 a settled claim is deemed to be outstanding from the day immediately following the date the said claim would have been due and payable under the contract had it not been disputed.
- 9.3 For the purposes of TP9 a claim means a disputed amount subject to negotiation between Her Majesty and the Contractor under the contract.



Section	Page	Heading
GC1	1	Interpretation
GC2	2	Successors and Assigns
GC3	2	Assignment of Contract
GC4	2	Subcontracting by Contractor
GC5	2	Amendments
GC6	3	No Implied Obligations
GC7	3	Time of Essence
GC8	3	Indemnification by Contractor
GC9	3	Indemnification by Her Majesty
GC10	3	Members of House of Commons Not to Benefit
GC11	4	Notices
GC12	4	Material, Plant and Real Property Supplied by Her Majesty
GC13	5	Material, Plant and Real Property Become Property of Her Majesty
GC14	5	Permits and Taxes Payable
GC15	6	Performance of Work under Direction of Departmental Representative
GC16	6	Cooperation with Other Contractors
GC17	7	Examination of Work
GC18	7	Clearing of Site
GC19	7	Contractor's Superintendent
GC20	8	National Security
GC21	8	Unsuitable Workers
GC22	8	Increased or Decreased Costs
GC23	9	Canadian Labour and Material
GC24	9	Protection of Work and Documents
GC25	10	Public Ceremonies and Signs
GC26	10	Precautions against Damage, Infringement of Rights, Fire, and Other Hazards
GC27	11	Insurance
GC28	11	Insurance Proceeds
GC29	12	Contract Security
GC30	12	Changes in the Work
GC31	13	Interpretation of Contract by Departmental Representative
GC32	14	Warranty and Rectification of Defects in Work
GC33	14	Non-Compliance by Contractor
GC34	14	Protesting Departmental Representative's Decisions
GC35	15	Changes in Soil Conditions and Neglect or Delay by Her Majesty
GC36	16	Extension of Time
GC37	16	Assessments and Damages for Late Completion
GC38	17	Taking the Work Out of the Contractor's Hands
GC39	18	Effect of Taking the Work Out of the Contractor's Hands
GC40	18	Suspension of Work by Minister
GC41	19	Termination of Contract
GC42	19	Claims Against and Obligations of the Contractor or Subcontractor
GC43	21	Security Deposit – Forfeiture or Return
GC44	22	Departmental Representative's Certificates
GC45	23	Return of Security Deposit
GC46	24	Clarification of Terms in GC47 to GC50
GC47	24	Additions or Amendments to Unit Price Table
GC48	24	Determination of Cost – Unit Price Table
GC49	25	Determination of Cost – Negotiation
GC50	25	Determination of Cost – Failing Negotiation
GC51	26	Records to be kept by Contractor
GC52	27	Conflict of Interest
GC53	27	Contractor Status



GC1 Interpretation

1.1 In the contract

- 1.1.1 where reference is made to a part of the contract by means of numbers preceded by letters, the reference shall be construed to be a reference to the particular part of the contract that is identified by that combination of letters and numbers and to any other part of the contract referred to therein;
- 1.1.2 “contract” means the contract document referred to in the Articles of Agreement;
- 1.1.3 “contract security” means any security given by the Contractor to Her Majesty in accordance with the contract;
- 1.1.4 “Departmental Representative” means the officer or employee of Her Majesty who is designated pursuant to the Articles of Agreement and includes a person specially authorized by him to perform, on his behalf, any of his functions under the contract and is so designated in writing to the Contractor;
- 1.1.5 “material” includes all commodities, articles and things required to be furnished by or for the Contractor under the contract for incorporation into the work;
- 1.1.6 “Minister” includes a person acting for, or if the office is vacant, in place of the Minister and his successors in the office, and his or their lawful deputy and any of his or their representatives appointed for the purposes of the contract;
- 1.1.7 “person” includes, unless the context otherwise requires, a partnership, proprietorship, firm, joint venture, consortium and a corporation;
- 1.1.8 “plant” includes all animals, tools, implements, machinery, vehicles, buildings, structures, equipment and commodities, articles and things other than material, that are necessary for the due performance of the contract;
- 1.1.9 “subcontractor” means a person to whom the Contractor has, subject to GC4, subcontracted the whole or any part of the work;
- 1.1.10 “superintendent” means the employee of the Contractor who is designated by the Contractor to act pursuant to GC19;
- 1.1.11 “work includes, subject only to any express stipulation in the contract to the contrary, everything that is necessary to be done, furnished or delivered by the Contractor to perform the contract.

1.2 The headings in the contract documents, other than in the Plans and Specifications, form no part of the contract but are inserted for convenience of reference only.

1.3 In interpreting the contract, in the event of discrepancies or conflicts between anything in the Plans and Specifications and the General Conditions, the General Conditions govern.



- 1.4 In interpreting the Plans and Specifications, in the event of discrepancies or conflicts between
- 1.4.1 the Plans and Specifications, the Specifications govern;
 - 1.4.2 the Plans, the Plans drawn with the largest scale govern; and
 - 1.4.3 figured dimensions and scaled dimensions, the figured dimensions govern.

GC2 Successors and Assigns

- 2.1 The contract shall inure to the benefit of and be binding upon the parties hereto and their lawful heirs, executors, administrators, successors and assigns.

GC3 Assignment of Contract

- 3.1 The contract may not be assigned by the Contractor, either in whole or in part, without the written consent of the Minister.

GC4 Subcontracting by Contractor

- 4.1 Subject to this General Condition, the Contractor may subcontract any part of the work.
- 4.2 The Contractor shall notify the Departmental Representative in writing of his intention to subcontract.
- 4.3 A notification referred to in GC4.2 shall identify the part of the work, and the subcontractor with whom it is intended to subcontract.
- 4.4 The Departmental Representative may object to the intended subcontracting by notifying the Contractor in writing within six days of receipt by the Departmental Representative of a notification referred to in GC4.2.
- 4.5 If the Departmental Representative objects to a subcontracting pursuant to GC4.4, the Contractor shall not enter into the intended subcontract.
- 4.6 The contractor shall not, without the written consent of the Departmental Representative, change a subcontractor who has been engaged by him in accordance with this General Condition.
- 4.7 Every subcontract entered into by the Contractor shall adopt all of the terms and conditions of this contract that are of general application.
- 4.8 Neither a subcontracting nor the Departmental Representative's consent to a subcontracting by the Contractor shall be construed to relieve the Contractor from any obligation under the contract or to impose any liability upon Her Majesty.

GC5 Amendments



- 5.1 No amendment or change in any of the provisions of the contract shall have any force or effect until it is reduced to writing.

GC6 No Implied Obligations

- 6.1 No implied terms or obligations of any kind by or on behalf of Her Majesty shall arise from anything in the contract and the express covenants and agreements therein contained and made by Her Majesty are the only covenants and agreements upon which any rights against Her Majesty are to be founded.
- 6.2 The contract supersedes all communications, negotiations and agreements, either written or oral, relating to the work that were made prior to the date of the contract.

GC7 Time of Essence

- 7.1 Time is of the essence of the contract.

GC8 Indemnification by Contractor

- 8.1 The Contractor shall indemnify and save Her Majesty harmless from and against all claims, demand, losses, costs, damages, actions, suits, or proceedings by whomever made, brought or prosecuted and in any manner based upon, arising out of, related to, occasioned by or attributable to the activities of the Contractor, his servants, agents, subcontractors and sub-subcontractors in performing the work including an infringement or an alleged infringement of a patent of invention or any other kind of intellectual property.
- 8.2 For the purpose of GC8.1, "activities" includes any act improperly carried out, any omission to carry out an act and any delay in carrying out an act.

GC9 Indemnification by Her Majesty

- 9.1 Her Majesty shall, subject to the Crown Liability Act, the Patent Act, and any other law that affects Her Majesty's rights, powers, privileges or obligations, indemnify and save the Contractor harmless from and against all claims, demands, losses, costs, damage, actions, suits or proceedings arising out of his activities under the contract that are directly attributable to
- 9.1.1 lack of or a defect in Her Majesty's title to the work site whether real or alleged; or
- 9.1.2 an infringement or an alleged infringement by the Contractor of any patent of invention or any other kind of intellectual property occurring while the Contractor was performing any act for the purposes of the contract employing a model, plan or design or any other thing related to the work that was supplied by Her Majesty to the Contractor.

GC10 Members of House of Commons Not to Benefit



- 10.1 As required by the Parliament of Canada Act, it is an express condition of the contract that no member of the House of Commons shall be admitted to any share of part of the contract or to any benefit arising therefrom.

GC11 Notices

- 11.1 Any notice, consent, order, decision, direction or other communication, other than a notice referred to in GC11.4, that may be given to the Contractor pursuant to the contract may be given in any manner.
- 11.2 Any notice, consent, order, decision, direction or other communication required to be given in writing, to any party pursuant to the contract shall, subject to GC11.4, be deemed to have been effectively given
- 11.2.1 to the Contractor, if delivered personally to the Contractor or the Contractor's superintendent, or forwarded by mail, telex or facsimile to the Contractor at the address set out in A4.1, or
- 11.2.2 to Her Majesty, if delivered personally to the Departmental Representative, or forwarded by mail, telex or facsimile to the Departmental Representative at the address set out in A1.2.1.
- 11.3 Any such notice, consent, order, decision, direction or other communication given in accordance with GC11.2 shall be deemed to have been received by either party
- 11.3.1 if delivered personally, on the day that it was delivered,
- 11.3.2 if forwarded by mail, on the earlier of the day it was received and the sixth day after it was mailed, and
- 11.3.3 if forwarded by telex or facsimile, 24 hours after it was transmitted.
- 11.4 A notice given under GC38.1.1, GC40 and GC41, if delivered personally, shall be delivered to the Contractor if the Contractor is doing business as sole proprietor or, if the Contractor is a partnership or corporation, to an officer thereof.

GC12 Material, Plant and Real Property Supplied by Her Majesty

- 12.1 Subject to GC12.2, the Contractor is liable to Her Majesty for any loss of or damage to material, plant or real property that is supplied or placed in the care, custody and control of the Contractor by Her Majesty for use in connection with the contract, whether or not that loss or damage is attributable to causes beyond the Contractor's control.
- 12.2 The Contractor is not liable to Her Majesty for any loss or damage to material, plant or real property referred to in GC12.1 if that loss or damage results from and is directly attributable to reasonable wear and tear.
- 12.3 The Contractor shall not use any material, plant or real property referred to in GC12.1 except for



the purpose of performing this contract.

- 12.4 When the Contractor fails to make good any loss or damage for which he is liable under GC12.1 within a reasonable time after being required to do so by the Departmental Representative, the Departmental Representative may cause the loss or damage to be made good at the Contractor's expense, and the Contractor shall thereupon be liable to Her Majesty for the cost thereof and shall, on demand, pay to Her Majesty an amount equal to that cost.
- 12.5 The Contractor shall keep such records of all material, plant and real property referred to in GC12.1 as the Departmental Representative from time to time requires and shall satisfy the Departmental Representative, when requested, that such material, plant and real property are at the place and in the condition which they ought to be.

GC13 Material, Plant and Real Property Become Property of Her Majesty

- 13.1 Subject to GC14.7 all material and plant and the interest of the Contractor in all real property, licenses, powers and privileges purchased, used or consumed by the Contractor for the contract shall, after the time of their purchase, use or consumption be the property of Her Majesty for the purposes of the work and they shall continue to be the property of Her Majesty.
- 13.1.1 in the case of material, until the Departmental Representative indicates that he is satisfied that it will not be required for the work, and
- 13.1.2 in the case of plant, real property, licenses, powers and privileges, until the Departmental Representative indicates that he is satisfied that the interest vested in Her Majesty therein is no longer required for the purposes of the work.
- 13.2 Material or plant that is the property of Her Majesty by virtue of GC13.1 shall not be taken away from the work site or used or disposed of except for the purposes of the work without the written consent of the Departmental Representative.
- 13.3 Her Majesty is not liable for loss of or damage from any cause to the material or plant referred to in GC13.1 and the Contractor is liable for such loss or damage notwithstanding that the material or plant is the property of Her Majesty.

GC14 Permits and Taxes Payable

- 14.1 The Contractor shall, within 30 days after the date of the contract, tender to a municipal authority an amount equal to all fees and charges that would be lawfully payable to that municipal authority in respect of building permits as if the work were being performed for a person other than Her Majesty.
- 14.2 Within 10 days of making a tender pursuant to GC14.1, the Contractor shall notify the Departmental Representative of his action and of the amount tendered and whether or not the municipal authority has accepted that amount.
- 14.3 If the municipal authority does not accept the amount tendered pursuant to GC14.1 the Contractor shall pay that amount to Her Majesty within 6 days after the time stipulated in GC14.2.



- 14.4 For the purposes of GC14.1 to GC14.3 “municipal authority” means any authority that would have jurisdiction respecting permission to perform the work if the owner were not Her Majesty.
- 14.5 Notwithstanding the residency of the Contractor, the Contractor shall pay any applicable tax arising from or related to the performance of the work under the contract.
- 14.6 In accordance with the Statutory Declaration referred to in TP4.9, a Contractor who has neither residence nor place of business in the province in which work under the contract is being performed shall provide Her Majesty with proof of registration with the provincial sales tax authorities in the said province.
- 14.7 For the purpose of the payment of any applicable tax or the furnishing of security for the payment of any applicable tax arising from or related to the performance of the work under the contract, the Contractor shall, notwithstanding the fact that all material, plant and interest of the Contractor in all real property, licenses, powers and privileges, have become the property of Her Majesty after the time of purchase, be liable, as a user or consumer, for the payment or for the furnishing of security for the payment of any applicable tax payable, at the time of the use or consumption of that material, plant or interest of the Contractor in accordance with the relevant legislation.

GC15 Performance of Work under Direction of Departmental Representative

- 15.1 The Contractor shall
- 15.1.1 permit the Departmental Representative to have access to the work and its site at all times during the performance of the contract;
 - 15.1.2 furnish the Departmental Representative with such information respecting the performance of the contract as he may require; and
 - 15.1.3 give the Departmental Representative every possible assistance to enable the Departmental Representative to carry out his duty to see that the work is performed in accordance with the contract and to carry out any other duties and exercise any powers specially imposed or conferred on the Departmental Representative under the contract.

CG16 Cooperation with Other Contractors

- 16.1 Where, in the opinion of the Departmental Representative, it is necessary that other contractors or workers with or without plant and material, be sent onto the work or its site, the Contractor shall, to the satisfaction of the Departmental Representative, allow them access and cooperate with them in the carrying out of their duties and obligation.
- 16.2 If
- 16.2.1 the sending onto the work or its site of other contractors or workers pursuant to GC16.1 could not have been reasonably foreseen or anticipated by the Contractor when entering into the contract, and



16.2.2 the Contractor incurs, in the opinion of the Departmental Representative, extra expense in complying with GC16.1, and

16.2.3 The Contractor has given the Departmental Representative written notice of his claim for the extra expense referred to in GC16.2.2 within 30 days of the date that the other contractors or workers were sent onto the work or its site,

Her Majesty shall pay the Contractor the cost, calculated in accordance with GC48 to GC50, of the extra labour, plant and material that was necessarily incurred.

GC17 Examination of Work

17.1 If, at any time after the commencement of the work but prior to the expiry of the warranty or guarantee period, the Departmental Representative has reason to believe that the work or any part thereof has not been performed in accordance with the contract, the Departmental Representative may have that work examined by an expert of his choice.

17.2 If, as a result of an examination of the work referred to in GC17.1, it is established that the work was not performed in accordance with the contract, then, in addition to and without limiting or otherwise affecting any of Her Majesty's rights and remedies under the contract either at law or in equity, the Contractor shall pay Her Majesty, on demand, all reasonable costs and expenses that were incurred by Her Majesty in having that examination performed.

GC18 Clearing of Site

18.1 The Contractor shall maintain the work and its site in a tidy condition and free from the accumulation of waste material and debris, in accordance with any directions of the Departmental Representative.

18.2 Before the issue of an interim certificate referred to in GC44.2, the Contractor shall remove all the plant and material not required for the performance of the remaining work, and all waste material and other debris, and shall cause the work and its site to be clean and suitable for occupancy by Her Majesty's servants, unless otherwise stipulated in the contract.

18.3 Before the issue of a final certificate referred to in GC44.1, the Contractor, shall remove from the work and its site all of the surplus plant and material and any waste material and other debris.

18.4 The Contractor's obligations described in GC18.1 to GC18.3 do not extend to waste material and other debris caused by Her Majesty's servants or contractors and workers referred to in GC16.1.

GC19 Contractor's Superintendent

19.1 The Contractor shall, forthwith upon the award of the contract, designate a superintendent.

19.2 The Contractor shall forthwith notify the Departmental Representative of the name, address and telephone number of a superintendent designate pursuant to GC19.1.



- 19.3 A superintendent designated pursuant to GC19.1 shall be in full charge of the operations of the Contractor in the performance of the work and is authorized to accept any notice, consent, order, direction, decision or other communication on behalf of the Contractor that may be given to the superintendent under the contract.
- 19.4 The Contractor shall, until the work has been completed, keep a competent superintendent at the work site during working hours.
- 19.5 The Contractor shall, upon the request of the Departmental Representative, remove any superintendent who, in the opinion of the Departmental Representative, is incompetent or has been conducting himself improperly and shall forthwith designate another superintendent who is acceptable to the Departmental Representative.
- 19.6 Subject to GC19.5, the Contractor shall not substitute a superintendent without the written consent of the Departmental Representative.
- 19.7 A breach by the Contractor of GC19.6 entitles the Departmental Representative to refuse to issue any certificate referred to in GC44 until the superintendent has returned to the work site or another superintendent who is acceptable to the Departmental Representative has been substituted.

GC20 National Security

- 20.1 If the Minister is of the opinion that the work is of a class or kind that involves the national security, he may order the Contractor
- 20.1.1 to provide him with any information concerning persons employed or to be employed by him for purposes of the contract; and
 - 20.1.2 to remove any person from the work and its site if, in the opinion of the Minister, that person may be a risk to the national security.
- 20.2 The Contractor shall, in all contracts with persons who are to be employed in the performance of the contract, make provision for his performance of any obligation that may be imposed upon him under GC19 to GC21.
- 20.3 The Contractor shall comply with an order of the Minister under GC20.1

GC21 Unsuitable Workers

- 21.1 The Contractor shall, upon the request of the Departmental Representative, remove any person employed by him for purposes of the contract who, in the opinion of the Departmental Representative, is incompetent or has conducted himself improperly, and the Contractor shall not permit a person who has been removed to return to the work site.

GC22 Increased or Decreased Costs



- 22.1 The amount set out in the Articles of Agreement shall not be increased or decreased by reason of any increase or decrease in the cost of the work that is brought about by an increase or decrease in the cost of labour, plant or material or any wage adjustment arising pursuant to the Labour Conditions.
- 22.2 Notwithstanding GC22.1 and GC35, an amount set out in the Articles of Agreement shall be adjusted in the manner provided in GC22.3, if any change in a tax imposed under the Excise Act, the Excise Tax Act, the Old Age Security Act, the Customs Act, the Customs Tariff or any provincial sales tax legislation imposing a retail sales tax on the purchase of tangible personal property incorporated into Real Property
- 22.2.1 occurs after the date of the submission by the Contractor of his tender for the contract,
- 22.2.2 applies to material, and
- 22.2.3 affects the cost to the Contractor of that material.
- 22.3 If a change referred to in GC22.2 occurs, the appropriate amount set out in the Articles of Agreement shall be increased or decreased by an amount equal to the amount that is established by an examination of the relevant records of the Contractor referred to in GC51 to be the increase or decrease in the cost incurred that is directly attributable to that change.
- 22.4 For the purpose of GC22.2, where a tax is changed after the date of submission of the tender but public notice of the change has been given by the Minister of Finance before that date, the change shall be deemed to have occurred before the date of submission of the tender.

GC23 Canadian Labour and Material

- 23.1 The Contractor shall use Canadian labour and material in the performance of the work to the full extent to which they are procurable, consistent with proper economy and expeditious carrying out of the work.
- 23.2 Subject to GC23.1, the Contractor shall, in the performance of the work, employ labour from the locality where the work is being performed to the extent to which it is available, and shall use the offices of the Canada Employment Centres for the recruitment of workers wherever practicable.
- 23.3 Subject to GC23.1 and GC23.2, the Contractor shall, in the performance of the work, employ a reasonable proportion of persons who have been on active service with the armed forces of Canada and have been honourably discharged therefrom.

GC24 Protection of Work and Documents

- 24.1 The Contractor shall guard or otherwise protect the work and its site, and protect the contract, specifications, plans, drawings, information, material, plant and real property, whether or not they are supplied by Her Majesty to the Contractor, against loss or damage from any cause, and he shall not use, issue, disclose or dispose of them without the written consent of the Minister, except as may be essential for the performance of the work.



- 24.2 If any document or information given or disclosed to the Contractor is assigned a security rating by the person who gave or disclosed it, the Contractor shall take all measures directed by the Departmental Representative to be taken to ensure the maintenance of the degree of security that is ascribed to that rating.
- 24.3 The Contractor shall provide all facilities necessary for the purpose of maintaining security, and shall assist any person authorized by the Minister to inspect or to take security measures in respect of the work and its site.
- 24.4 The Departmental Representative may direct the Contractor to do such things and to perform such additional work as the Departmental Representative considers reasonable and necessary to ensure compliance with or to remedy a breach of GC24.1 to GC24.3.

GC25 Public Ceremonies and Signs

- 25.1 The Contractor shall not permit any public ceremony in connection with the work without the prior consent of the Minister.
- 25.2 The Contractor shall not erect or permit the erection of any sign or advertising on the work or its site without the prior consent of the Departmental Representative.

GC26 Precautions against Damage, Infringement of Rights, Fire, and Other Hazards

- 26.1 The Contractor shall, at his own expense, do whatever is necessary to ensure that
- 26.1.1 no person, property, right, easement or privilege is injured, damaged or infringed by reasons of the Contractor's activities in performing the contract;
 - 26.1.2 pedestrian and other traffic on any public or private road or waterway is not unduly impeded, interrupted or endangered by the performance or existence of the work or plant;
 - 26.1.3 fire hazards in or about the work or its site are eliminated and, subject to any direction that may be given by the Departmental Representative, any fire is promptly extinguished;
 - 26.1.4 the health and safety of all persons employed in the performance of the work is not endangered by the method or means of its performance;
 - 26.1.5 adequate medical services are available to all persons employed on the work or its site at all times during the performance of the work;
 - 26.1.6 adequate sanitation measures are taken in respect of the work and its site; and
 - 26.1.7 all stakes, buoys and marks placed on the work or its site by or under the authority of the Departmental Representative are protected and are not removed, defaced, altered or destroyed.
- 26.2 The Departmental Representative may direct the Contractor to do such things and to perform such additional work as the Departmental Representative considers reasonable and necessary to ensure



compliance with or to remedy a breach of GC26.1.

- 26.3 The Contractor shall, at his own expense, comply with a direction of the Departmental Representative made under GC26.2.

GC27 Insurance

- 27.1 The Contractor shall, at his own expense, obtain and maintain insurance contracts in respect of the work and shall provide evidence thereof to the Departmental Representative in accordance with the requirements of the Insurance Conditions "E".

- 27.2 The insurance contracts referred to in GC27.1 shall

27.2.1 be in a form, of the nature, in the amounts, for the periods and containing the terms and conditions specified in Insurance Conditions "E", and

27.2.2 provide for the payment of claims under such insurance contracts in accordance with GC28.

GC28 Insurance Proceeds

- 28.1 In the case of a claim payable under a Builders Risk/Installation (All Risks) insurance contract maintained by the Contractor pursuant to GC27, the proceeds of the claim shall be paid directly to Her Majesty, and

28.1.1 the monies so paid shall be held by Her Majesty for the purposes of the contract, or

28.1.2 if Her Majesty elects, shall be retained by Her Majesty, in which event they vest in Her Majesty absolutely.

- 28.2 In the case of a claim payable under a General Liability insurance contract maintained by the Contractor pursuant to GC27, the proceeds of the claim shall be paid by the insurer directly to the claimant.

- 28.3 If an election is made pursuant to GC28.1, the Minister may cause an audit to be made of the accounts of the Contractor and of Her Majesty in respect of the part of the work that was lost, damaged or destroyed for the purpose of establishing the difference, if any, between

28.3.1 the aggregate of the amount of the loss or damage suffered or sustained by Her Majesty, including any cost incurred in respect of the clearing and cleaning of the work and its site and any other amount that is payable by the Contractor to Her Majesty under the contract, minus any monies retained pursuant to GC28.12, and

28.3.2 the aggregate of the amounts payable by Her Majesty to the Contractor pursuant to the contract up to the date of the loss or damage.

- 28.4 A difference that is established pursuant to GC28.3 shall be paid forthwith by the party who is determined by the audit to be the debtor to the party who is determined by the audit to be the



creditor.

- 28.5 When payment of a deficiency has been made pursuant to GC28.4, all rights and obligations of Her Majesty and the Contractor under the contract shall, with respect only to the part of the work that was the subject of the audit referred to in GC28.3, be deemed to have been expended and discharged.
- 28.6 If an election is not made pursuant to GC28.1.2 the Contractor shall, subject to GC28.7, clear and clean the work and its site and restore and replace the part of the work that was lost, damaged or destroyed at his own expense as if that part of the work had not yet been performed.
- 28.7 When the Contractor clears and cleans the work and its site and restores and replaces the work referred to in GC 28.6, Her Majesty shall pay him out of the monies referred to in GC28.1 so far as they will thereunto extend.
- 28.8 Subject to GC28.7, payment by Her Majesty pursuant to GC28.7 shall be made in accordance with the contract but the amount of each payment shall be 100% of the amount claimed notwithstanding TP4.4.1 and TP4.4.2.

GC29 Contract Security

- 29.1 The Contractor shall obtain and deliver contract security to the Departmental Representative in accordance with the provisions of the Contract Security Conditions.
- 29.2 If the whole or a part of the contract security referred to in GC29.1 is in the form of a security deposit, it shall be held and disposed of in accordance with GC43 and GC45.
- 29.3 If a part of the contract security referred to in GC29.1 is in the form of a labour and material payment bond, the Contractor shall post a copy of that bond on the work site.

GC30 Changes in the Work

- 30.1 Subject to GC5, the Departmental Representative may, at any time before he issues his Final Certificate of Completion,
- 30.1.1 order work or material in addition to that provided for in the Plans and Specifications;
and
- 30.1.2 delete or change the dimensions, character, quantity, quality, description, location or position of the whole or any part of the work or material provided for in the Plans and Specifications or in any order made pursuant to GC30.1.1,
- if that additional work or material, deletion, or change is, in his opinion, consistent with the general intent of the original contract.
- 30.2 The Contractor shall perform the work in accordance with such orders, deletions and changes that are made by the Departmental Representative pursuant to GC30.1 from time to time as if they had appeared in and been part of the Plans and Specifications.



- 30.3 The Departmental Representative shall determine whether or not anything done or omitted by the Contractor pursuant to an order, deletion or change referred to in GC30.1 increased or decreased the cost of the work to the Contractor.
- 30.4 If the Departmental Representative determines pursuant to GC30.3 that the cost of the work to the Contractor has been increased, Her Majesty shall pay the Contractor the increased cost that the Contractor necessarily incurred for the additional work calculated in accordance with GC49 or GC50.
- 30.5 If the Departmental Representative determines pursuant to GC30.3 that the cost of the work to the Contractor has been decreased, Her Majesty shall reduce the amount payable to the Contractor under the contract by an amount equal to the decrease in the cost caused by the deletion or change referred to in GC30.1.2 and calculated in accordance with GC49.
- 30.6 GC30.3 to GC30.5 are applicable only to a contract or a portion of a contract for which a Fixed Price Arrangement is stipulated in the contract.
- 30.7 An order, deletion or change referred to in GC30.1 shall be in writing, signed by the Departmental Representative and given to the Contractor in accordance with GC11.

GC31 Interpretation of Contract by Departmental Representative

- 31.1 If, at any time before the Departmental Representative has issued a Final Certificate of Completion referred to in GC44.1, any question arises between the parties about whether anything has been done as required by the contract or about what the Contractor is required by the contract to do, and, in particular but without limiting the generality of the foregoing, about
- 31.1.1 the meaning of anything in the Plans and Specification,
 - 31.1.2 the meaning to be given to the Plans and Specifications in case of any error therein, omission therefrom, or obscurity or discrepancy in their working or intention,
 - 31.1.3 whether or not the quality or quantity of any material or workmanship supplied or proposed to be supplied by the Contractor meets the requirements of the contract,
 - 31.1.4 whether or not the labour, plant or material provided by the Contractor for performing the work and carrying out the contract are adequate to ensure that the work will be performed in accordance with the contract and that the contract will be carried out in accordance with its terms,
 - 31.1.5 what quantity of any kind of work has been completed by the Contractor, or
 - 31.1.6 the timing and scheduling of the various phases of the performance of the work,
- the question shall be decided by the Departmental Representative whose decision shall be final and conclusive in respect of the work.
- 31.2 The Contractor shall perform the work in accordance with any decisions of the Departmental



Representative that are made under GC31.1 and in accordance with any consequential directions given by the Departmental Representative.

GC32 Warranty and Rectification of Defects in Work

32.1 Without restricting any warranty or guarantee implied or imposed by law or contained in the contract documents, the Contractor shall, at his own expense,

32.1.1 rectify and make good any defect or fault that appears in the work or comes to the attention of the Minister with respect to those parts of the work accepted in connection with the Interim Certificate of Completion referred to GC44.2 within 12 months from the date of the Interim Certificate of Completion;

32.1.2 rectify and make good any defect or fault that appears in or comes to the attention of the Minister in connection with those parts of the work described in the Interim Certificate of Completion referred to in GC44.2 within 12 months from the date of the Final Certificate of Completion referred to in GC44.1.

32.2 The Departmental Representative may direct the Contractor to rectify and make good any defect or fault referred to in GC32.1 or covered by any other expressed or implied warranty or guarantee.

32.3 A direction referred to in GC32.2 shall be in writing, may include a stipulation in respect of the time within which a defect or fault is required to be rectified and made good by the Contractor, and shall be given to the Contractor in accordance with GC11.

32.4 The Contractor shall rectify and make good any defect or fault described in a direction given pursuant to GC32.2 within the time stipulated therein.

GC33 Non-Compliance by Contractor

33.1 If the Contractor fails to comply with any decision or direction given by the Departmental Representative pursuant to GC18, GC24, GC26, GC31 or GC32, the Departmental Representative may employ such methods as he deems advisable to do that which the Contractor failed to do.

33.2 The Contractor shall, on demand, pay Her Majesty an amount that is equal to the aggregate of all cost, expenses and damage incurred or sustained by Her Majesty by reason of the Contractor's failure to comply with any decision or direction referred to in GC33.1, including the cost of any methods employed by the Departmental Representative pursuant to GC33.1.

GC34 Protesting Departmental Representative's Decisions

34.1 The Contractor may, within ten days after the communication to him of any decision or direction referred to in GC30.3 or GC33.1, protest that decision or direction.

34.2 A protest referred to in GC34.1 shall be in writing, contain full reasons for the protest, be signed



by the Contractor and be given to Her Majesty by delivery to the Departmental Representative.

- 34.3 If the Contractor gives a protest pursuant to GC34.2, any compliance by the Contractor with the decision or direction that was protested shall not be construed as an admission by the Contractor of the correctness of that decision or direction, or prevent the Contractor from taking whatever action he considers appropriate in the circumstances.
- 34.4 The giving of a protest by the Contractor pursuant to GC34.2 shall not relieve him from complying with the decision or direction that is the subject of the protest.
- 34.5 Subject to GC34.6, the Contractor shall take any action referred to in GC34.3 within three months after the date that a Final Certificate of Completion is issued under GC44.1 and not afterwards.
- 34.6 The Contractor shall take any action referred to in GC34.3 resulting from a direction under GC32 within three months after the expiry of a warranty or guarantee period and not afterwards.
- 34.7 Subject to GC34.8, if Her Majesty determines that the Contractor's protest is justified, Her Majesty shall pay the Contractor the cost of the additional labour, plant and material necessarily incurred by the Contractor in carrying out the protested decision or direction.
- 34.8 Costs referred to in GC34.7 shall be calculated in accordance with GC48 to GC50.

GC35 Changes in Soil Conditions and Neglect or Delay by Her Majesty

- 35.1 Subject to GC35.2 no payment, other than a payment that is expressly stipulated in the contract, shall be made by Her Majesty to the Contractor for any extra expense or any loss or damage incurred or sustained by the Contractor.
- 35.2 If the Contractor incurs or sustains any extra expense or any loss or damage that is directly attributable to
- 35.2.1 a substantial difference between the information relating to soil conditions at the work site that is contained in the Plans and Specifications or other documents supplied to the Contractor for his use in preparing his tender or a reasonable assumption of fact based thereon made by the Contractor, and the actual soil conditions encountered by the Contractor at the work site during the performance of the contract, or
- 35.2.2 any neglect or delay that occurs after the date of the contract on the part of Her Majesty in providing any information or in doing any act that the contract either expressly requires Her Majesty to do or that would ordinarily be done by an owner in accordance with the usage of the trade,

he shall, within ten days of the date the actual soil conditions described in GC35.2.1 were encountered or the neglect or delay described in GC35.2.2 occurred, give the Departmental Representative written notice of his intention to claim for that extra expense or that loss or damage.

- 35.3 When the Contractor has given a notice referred to in GC35.2, he shall give the Departmental Representative a written claim for extra expense or loss or damage within 30 days of the date that



a Final Certificate of Completion referred to in GC44.1 is issued and not afterwards.

- 35.4 A written claim referred to in GC35.3 shall contain a sufficient description of the facts and circumstances of the occurrence that is the subject of the claim to enable the Departmental Representative to determine whether or not the claim is justified and the Contractor shall supply such further and other information for that purpose as the Departmental Representative requires from time to time.
- 35.5 If the Departmental Representative determines that a claim referred to in GC35.3 is justified, Her Majesty shall make an extra payment to the Contractor in an amount that is calculated in accordance with GC47 to GC50.
- 35.6 If, in the opinion of the Departmental Representative, an occurrence described in GC35.2.1 results in a savings of expenditure by the Contractor in performing the contract, the amount set out in the Articles of Agreement shall, subject to GC35.7, be reduced by an amount that is equal to the saving.
- 35.7 The amount of the saving referred to in GC35.6 shall be determined in accordance with GC47 to GC49.
- 35.8 If the Contractor fails to give a notice referred to in GC35.2 and a claim referred to in GC35.3 within the times stipulated, an extra payment shall not be made to him in respect of the occurrence.

GC36 Extension of Time

- 36.1 Subject to GC36.2, the Departmental Representative may, on the application of the Contractor made before the day fixed by the Articles of Agreement for completion of the work or before any other date previously fixed under this General Condition, extend the time for its completion by fixing a new date if, in the opinion of the Departmental Representative, causes beyond the control of the Contractor have delayed its completion.
- 36.2 An application referred to in GC36.1 shall be accompanied by the written consent of the bonding company whose bond forms part of the contract security.

GC37 Assessments and Damages for Late Completion

- 37.1 For the purposes of this General Condition
- 37.1.1 the work shall be deemed to be completed on the date that an Interim Certificate of Completion referred to in GC44.2 is issued, and
- 37.1.2 "period of delay" means the number of days commencing on the day fixed by the Articles of Agreement for completion of the work and ending on the day immediately preceding the day on which the work is completed but does not include any day within a period of extension granted pursuant to GC36.1, and any other day on which, in the opinion of the Departmental Representative, completion of the work was delayed for reasons beyond the control of the Contractor.



- 37.2 If the Contractor does not complete the work by the day fixed for its completion by the Articles of Agreement but completes it thereafter, the Contractor shall pay Her Majesty an amount equal to the aggregate of
- 37.2.1 all salaries, wages and travelling expenses incurred by Her Majesty in respect of persons overseeing the performance of the work during the period of delay;
 - 37.2.2 the cost incurred by Her Majesty as a result of the inability to use the completed work for the period of delay; and
 - 37.2.3 all other expenses and damages incurred or sustained by Her Majesty during the period of delay as a result of the work not being completed by the day fixed for its completion.
- 37.3 The Minister may waive the right of Her Majesty to the whole or any part of the amount payable by the Contractor pursuant to GC37.2 I, in the opinion of the Minister, it is in the public interest to do so.

GC38 Taking the Work Out of the Contractor's Hands

- 38.1 The Minister may, at his sole discretion, by giving a notice in writing to the Contractor in accordance with GC11, take all or any part of the work out of the Contractor's hands, and may employ such means as he sees fit to have the work completed if the Contractor
- 38.1.1 Has not, within six days of the Minister or the Departmental Representative giving notice to the Contractor in writing in accordance with GC11, remedied any delay in the commencement or any default in the diligent performance of the work to the satisfaction of the Departmental Representative;
 - 38.1.2 has defaulted in the completion of any part of the work within the time fixed for its completion by the contract;
 - 38.1.3 has become insolvent;
 - 38.1.4 has committed an act of bankruptcy;
 - 38.1.5 has abandoned the work;
 - 38.1.6 has made an assignment of the contract without the consent required by GC3.1; or
 - 38.1.7 has otherwise failed to observe or perform any of the provisions of the contract.
- 38.2 If the whole or any part of the work is taken out of the Contractor's hands pursuant to GC38.1,
- 38.2.1 the Contractor's right to any further payment that is due or accruing due under the contract is, subject only to GC38.4, extinguished, and
 - 38.2.2 the Contractor is liable to pay Her Majesty, upon demand, an amount that is equal to the amount of all loss and damage incurred or sustained by Her Majesty in respect of the



Contractor's failure to complete the work.

- 38.3 If the whole or any part of the work that is taken out of the Contractor's hands pursuant to GC38.1 is completed by Her Majesty, the Departmental Representative shall determine the amount, if any, of the holdback or a progress claim that had accrued and was due prior to the date on which the work was taken out of the Contractor's hands and that is not required for the purposes of having the work performed or of compensating Her Majesty for any other loss or damage incurred or sustained by reason of the Contractor's default.
- 38.4 Her Majesty may pay the Contractor the amount determined not to be required pursuant to GC38.3.

GC39 Effect of Taking the Work Out of the Contractor's Hands

- 39.1 The taking of the work or any part thereof out of the Contractor's hands pursuant to GC38 does not operate so as to relieve or discharge him from any obligation under the contract or imposed upon him by law except the obligation to complete the performance of that part of the work that was taken out of his hands.
- 39.2 If the work or any part thereof is taken out of the Contractor's hands pursuant to GC38, all plant and material and the interest of the Contractor is all real property, licenses, powers and privileges acquired, used or provided by the Contractor under the contract shall continue to be the property of Her Majesty without compensation to the Contractor.
- 39.3 When the Departmental Representative certifies that any plant, material, or any interest of the Contractor referred to in GC39.2 is no longer required for the purposes of the work, or that it is not in the interest of Her Majesty to retain that plant, material or interest, it shall revert to the Contractor.

G40 Suspension of Work by Minister

- 40.1 The Minister may, when in his opinion it is in the public interest to do so, require the Contractor to suspend performance of the work either for a specified or an unspecified period by giving a notice of suspension in writing to the Contractor in accordance with GC11.
- 40.2 When a notice referred to in GC40.1 is received by the Contractor in accordance with GC11, he shall suspend all operations in respect of the work except those that, in the opinion of the Departmental Representative, are necessary for the care and preservation of the work, plant and material.
- 40.3 The Contractor shall not, during a period of suspension, remove any part of the work, plant or material from its site without the consent of the Departmental Representative.
- 40.4 If a period of suspension is 30 days or less, the Contractor shall, upon the expiration of that period, resume the performance of the work and he is entitled to be paid the extra cost, calculated in accordance with GC48 to GC50, of any labour, plant and material necessarily incurred by him as a result of the suspension.



- 40.5 If, upon the expiration of a period of suspension of more than 30 days, the Minister and the Contractor agree that the performance of the work will be continued by the Contractor, the Contractor shall resume performance of the work subject to any terms and conditions agreed upon by the Minister and the Contractor.
- 40.6 If, upon the expiration of a period of suspension of more than 30 days, the Minister and the Contractor do not agree that performance of the work will be continued by the Contractor or upon the terms and conditions under which the Contractor will continue the work, the notice of suspension shall be deemed to be a notice of termination pursuant to GC41.

GC41 Termination of Contract

- 41.1 The Minister may terminate the contract at any time by giving a notice of termination in writing to the Contractor in accordance with GC11.
- 41.2 When a notice referred to in GC41.1 is received by the Contractor in accordance with GC11, he shall, subject to any conditions stipulated in the notice, forthwith cease all operations in performance of the contract.
- 41.3 If the contract is terminated pursuant to GC41.1, Her Majesty shall pay the Contractor, subject to GC41.4, an amount equal to
- 41.3.1 the cost to the contractor of all labour, plant and material supplied by him under the contract up to the date of termination in respect of a contract or part thereof for which a Unit Price Arrangement is stipulated in the contract, or
 - 41.3.2 the lesser of
 - 41.3.2.1 an amount, calculated in accordance with the Terms and Payment, that would have been payable to the Contractor had he completed the work, and
 - 41.3.2.2 an amount that is determined to be due to the Contractor pursuant to GC49 in respect of a contract or part thereof for which a Fixed Price Arrangement is stipulated in the contract
- less the aggregate of all amounts that were paid to the Contractor by Her Majesty and all amounts that are due to Her Majesty from the Contractor pursuant to the contract.
- 41.4 If Her Majesty and the Contractor are unable to agree about an amount referred to in GC41.3 that amount shall be determined by the method referred to in GC50.

GC42 Claims Against and Obligations of the Contractor or Subcontractor

- 42.1 Her Majesty may, in order to discharge lawful obligations of and satisfy claims against the Contractor or a subcontractor arising out of the performance of the contract, pay any amount that is due and payable to the Contractor pursuant to the contract directly to the obligees of and the claimants against the Contractor or the subcontractor but such amount if any, as is paid by Her Majesty, shall not exceed that amount which the Contractor would have been obliged to pay to



such claimant had the provisions of the Provincial or Territorial lien legislation, or, in the Province of Quebec, the law relating to privileges, been applicable to the work. Any such claimant need not comply with the provisions of such legislation setting out the steps by way of notice, registration or otherwise as might have been necessary to preserve or perfect any claim for lien or privilege which claimant might have had;

42.2 Her Majesty will not make any payment as described in GC42.1 unless and until that claimant shall have delivered to Her Majesty:

42.2.1 a binding and enforceable Judgment or Order of a court of competent jurisdiction setting forth such amount as would have been payable by the Contractor to the claimant pursuant to the provisions of the applicable Provincial or Territorial lien legislation, or, in the Province of Quebec, the law relating to privileges, had such legislation been applicable to the work; or

42.2.2 a final and enforceable award of an arbitrator setting forth such amount as would have been payable by the Contractor to the claimant pursuant to the provisions of the applicable Provincial or Territorial lien legislation, or, in the Province of Quebec, the law relating to privileges, had such legislation been applicable to the work; or

42.2.3 the consent of the Contractor authorizing a payment.

For the purposes of determining the entitlement of a claimant pursuant to GC42.2.1 and GC42.2.2, the notice required by GC42.8 shall be deemed to replace the registration or provision of notice after the performance of work as required by any applicable legislation and no claim shall be deemed to have expired, become void or unenforceable by reason of the claimant not commencing any action within the time prescribed by any applicable legislation.

42.3 The Contractor shall, by the execution of his contract, be deemed to have consented to submit to binding arbitration at the request of any claimant those questions that need be answered to establish the entitlement of the claimant to payment pursuant to the provisions of GC42.1 and such arbitration shall have as parties to it any subcontractor to whom the claimant supplied material, performed work or rented equipment should such subcontractor wish to be adjoined and the Crown shall not be a party to such arbitration and, subject to any agreement between the Contractor and the claimant to the contrary, the arbitration shall be conducted in accordance with the Provincial or Territorial legislation governing arbitration applicable in the Province or Territory in which the work is located.

42.4 A payment made pursuant to GC42.1 is, to the extent of the payment, a discharge of Her Majesty's liability to the Contractor under the contract and may be deducted from any amount payable to the Contractor under the contract.

42.5 To the extent that the circumstances of the work being performed for Her Majesty permit, the Contractor shall comply with all laws in force in the Province or Territory where the work is being performed relating to payment period, mandatory holdbacks, and creation and enforcement of mechanics' liens, builders' liens or similar legislation or in the Province of Quebec, the law relating to privileges.

42.6 The Contractor shall discharge all his lawful obligations and shall satisfy all lawful claims against him arising out of the performance of the work at least as often as the contract requires Her



Majesty to pay the Contractor.

- 42.7 The Contractor shall, whenever requested to do so by the Departmental Representative, make a statutory declaration deposing to the existence and condition of any obligations and claims referred to in GC42.6.
- 42.8 GC42.1 shall only apply to claims and obligations
- 42.8.1 the notification of which has been received by the Departmental Representative in writing before payment is made to the Contractor pursuant to TP4.10 and within 120 days of the date on which the claimant
- 42.8.1.1 should have been paid in full under the claimant's contract with the Contractor or subcontractor where the claim is for money that was lawfully required to be held back from the claimant; or
- 42.8.1.2 performed the last of the services, work or labour, or furnished the last of the material pursuant to the claimant's contract with the Contractor or subcontractor where the claim is not for money referred to in GC42.8.1.1, and
- 42.8.2 the proceedings to determine the right to payment of which, pursuant to GC42.2. shall have commenced within one year from the date that the notice referred to in GC42.8.1 was received by the Departmental Representative, and
- the notification required by GC42.8.1 shall set forth the amount claimed to be owing and the person who by contract is primarily liable.
- 42.9 Her Majesty may, upon receipt of a notice of claim under GC42.8.1, withhold from any amount that is due and payable to the Contractor pursuant to the contract the full amount of the claim or any portion thereof.
- 42.10 The Departmental Representative shall notify the Contractor in writing of receipt of any claim referred to in GC42.8.1 and of the intention of Her Majesty to withhold funds pursuant to GC42.9 and the Contractor may, at any time thereafter and until payment is made to the claimant, be entitled to post, with Her Majesty, security in a form acceptable to Her Majesty in an amount equal to the value of the claim, the notice of which is received by the Departmental Representative and upon receipt of such security Her Majesty shall release to the Contractor any funds which would be otherwise payable to the Contractor, that were withheld pursuant to the provisions of GC42.9 in respect of the claim of any claimant for whom the security stands.

GC43 Security Deposit – Forfeiture or Return

- 43.1 If
- 43.1.1 the work is taken out of the Contractor's hands pursuant to GC38,
- 43.1.2 the contract is terminated pursuant to GC41, or
- 43.1.3 the Contractor is in breach of or in default under the contract,



Her Majesty may convert the security deposit, if any, to Her own use.

- 43.2 If Her Majesty converts the contract security pursuant to GC43.1, the amount realized shall be deemed to be an amount due from Her Majesty to the Contractor under the contract.
- 43.3 Any balance of an amount referred to in GC43.2 that remains after payment of all losses, damage and claims of Her Majesty and others shall be paid by Her Majesty to the Contractor if, in the opinion of the Departmental Representative, it is not required for the purposes of the contract.

GC44 Departmental Representative's Certificates

44.1 On the date that

44.1.1 the work has been completed, and

44.1.2 the Contractor has complied with the contract and all orders and directions made pursuant thereto,

both to the satisfaction of the Departmental Representative, the Departmental Representative shall issue a Final Certificate of Completion to the Contractor.

44.2 If the Departmental Representative is satisfied that the work is substantially complete he shall, at any time before he issues a certificate referred to in GC44.1, issue an Interim Certificate of Completion to the Contractor, and

44.2.1 for the purposes of GC44.2 the work will be considered to be substantially complete,

44.2.1.1 when the work under the contract or a substantial part thereof is, in the opinion of the Departmental Representative, ready for use by Her Majesty or is being used for the purpose intended; and

44.2.1.2 when the work remaining to be done under the contract is, in the opinion of the Departmental Representative, capable of completion or correction at accost of not more than

44.2.1.2.1 -3% of the first \$500,000, and

44.2.1.2.2 -2% of the next \$500,000, and

44.2.1.2.3 -1% of the balance

of the value of the contract at the time this cost is calculated.

44.3 For the sole purpose of GC44.2.1.2, where the work or a substantial part thereof is ready for use or is being used for the purposes intended and the remainder of the work or a part thereof cannot be completed by the time specified in A2.1, or as amended pursuant to GC36, for reasons beyond the control of the Contractor or where the Departmental Representative and the Contractor agree not to complete a part of the work within the specified time, the cost of that part of the work



which was either beyond the control of the Contractor to complete or the Departmental Representative and the Contractor have agreed not to complete by the time specified shall be deducted from the value of the contract referred to GC44.2.1.2 and the said cost shall not form part of the cost of the work remaining to be done in determining substantial completion.

44.4 An Interim Certificate of Completion referred to in GC44.2 shall describe the parts of the work not completed to the satisfaction of the Departmental Representative and all things that must be done by the Contractor

44.4.1 before a Final Certificate of Completion referred to in GC44.1 will be issued, and

44.4.2 before the 12-month period referred to in GC32.1.2 shall commence for the said parts and all the said things.

44.5 The Departmental Representative may, in addition to the parts of the work described in an Interim Certificate of Completion referred to in GC44.2, require the Contractor to rectify any other parts of the work not completed to his satisfaction and to do any other things that are necessary for the satisfactory completion of the work.

44.6 If the contract or a part thereof is subject to a Unit Price Arrangement, the Departmental Representative shall measure and record the quantities of labour, plant and material, performed, used and supplied by the Contractor in performing the work and shall, at the request of the Contractor, inform him of those measurements.

44.7 The Contractor shall assist and co-operate with the Departmental Representative in the performance of his duties referred to in GC44.6 and shall be entitled to inspect any record made by the Departmental Representative pursuant to GC44.6.

44.8 After the Departmental Representative has issued a Final Certificate of Completion referred to in GC44.1, he shall, if GC44.6 applies, issue a Final Certificate of Measurement.

44.9 A Final Certificate of Measurement referred to in GC44.8 shall

44.9.1 contain the aggregate of all measurements of quantities referred to in GC44.6, and

44.9.2 be binding upon and conclusive between Her Majesty and the Contractor as to the quantities referred to therein.

GC45 Return of Security Deposit

45.1 After an Interim Certificate of Completion referred to in GC44.2 has been issued, Her Majesty shall, if the Contractor is not in breach of or in default under the contract, return to the Contractor all or any part of the security deposit that, in the opinion of the Departmental Representative, is not required for the purposes of the contract.

45.2 After a Final Certificate of Completion referred to in GC44.1 has been issued, Her Majesty shall return to the Contractor the remainder of any security deposit unless the contract stipulates otherwise.



- 45.3 If the security deposit was paid into the Consolidated Revenue Fund of Canada, Her Majesty shall pay interest thereon to the Contractor at a rate established from time to time pursuant to section 21(2) of the Financial Administration Act.

GC46 Clarification of Terms in GC47 to GC50

- 46.1 For the purposes of GC47 to GC50,
- 46.1.1 "Unit Price Table" means the table set out in the Articles of Agreement, and
- 46.1.2 "plant" does not include tools customarily provided by a tradesman in practicing his trade.

GC47 Additions or Amendments to Unit Price Table

- 47.1 Where a Unit Price Arrangement applies to the contract or a part thereof the Departmental Representative and the Contractor may, by an agreement in writing,
- 47.1.1 add classes of labour or material, and units of measurement, prices per unit and estimated quantities to the Unit Price Table if any labour, plant or material that is to be included in the Final Certificate of Measurement referred to in GC44.8 is not included in any class of labour, plant or material set out in the Unit Price Table; or
- 47.1.2 subject to GC47.2 and GC47.3, amend a price set out in the Unit Price Table for any class of labour, plant or material included therein if the Final Certificate of Measurement referred to in GC44.8 shows or is expected to show that the total quantity of that class of labour, plant or material actually performed, used or supplied by the Contractor in performing the work is
- 47.1.2.1 less than 85% of that estimated total quantity, or
- 47.1.2.2 in excess of 115% of that estimated total quantity.
- 47.2 In no event shall the total cost of an item set out in the Unit Price Table that has been amended pursuant to GC47.1.2.1 exceed the amount that would have been payable to the Contractor had the estimated total quantity actually been performed, used or supplied.
- 47.3 An amendment that is made necessary by GC47.1.2.2 shall apply only to the quantities that are in excess of 115%.
- 47.4 If the Departmental Representative and the Contractor do not agree as contemplated in GC47.1, the Departmental Representative shall determine the class and the unit of measurement of the labour, plant or material and, subject to GC47.2 and GC47.3, the price per unit therefore shall be determined in accordance with GC50.

GC48 Determination of Cost – Unit Price Table



- 48.1 Whenever, for the purposes of the contract, it is necessary to determine the cost of labour, plant or material, it shall be determined by multiplying the quantity of that labour, plant or material expressed in the unit set out in column 3 of the Unit Price Table by the price of that unit set out in column 5 of the Unit Price Table.

GC49 Determination of Cost – Negotiation

- 49.1 If the method described in GC48 cannot be used because the labour, plant or material is of a kind or class that is not set out in the Unit Price Table, the cost of that labour, plant or material for the purposes of the contract shall be the amount agreed upon from time to time by the Contractor and the Departmental Representative.
- 49.2 For the purposes of GC49.1, the Contractor shall submit to the Departmental Representative any necessary cost information requested by the Departmental Representative in respect of the labour, plant and material referred to in GC49.1

GC50 Determination of Cost – Failing Negotiation

- 50.1 If the methods described in GC47, GC48 or GC49 fail for any reason to achieve a determination of the cost of labour, plant and material for the purposes referred to therein, that cost shall be equal to the aggregate of
- 50.1.1 all reasonable and proper amounts actually expended or legally payable by the Contractor in respect of the labour, plant and material that falls within one of the classes of expenditure described in GC50.2 that are directly attributable to the performance of the contract,
 - 50.1.2 an allowance for profit and all other expenditures or costs, including overhead, general administration cost, financing and interest charges, and every other cost, charge and expenses, but not including those referred to in GC50.1.1 or GC50.1.3 or a class referred to in GC50.2, in an amount that is equal to 10% of the sum of the expenses referred to in GC50.1.1, and
 - 50.1.3 interest on the cost determined under GC50.1.1 and GC50.1.2, which interest shall be calculated in accordance with TP9,

provide that the total cost of an item set out in the Unit Price Table that is subject to the provisions of GC47.1.2.1 does not exceed the amount that would have been payable to the Contractor had the estimated total quantity of the said item actually be performed, used or supplied.

- 50.2 For purposes of GC50.1.1 the classes of expenditure that may be taken into account in determining the cost of labour, plant and material are,
- 50.2.1 payments to subcontractors;
 - 50.2.2 wages, salaries and travelling expenses of employees of the Contractor while they are actually and properly engaged on the work, other than wages, salaries, bonuses, living



and travelling expenses of personnel of the Contractor generally employed at the head office or at a general office of the Contractor unless they are engaged at the work site with the approval of the Departmental Representative,

- 50.2.3 assessments payable under any statutory authority relating to workmen's compensation, unemployment insurance, pension plan or holidays with pay;
- 50.2.4 rent that is paid for plant or an amount equivalent of the said rent if the plant is owned by the Contractor that is necessary for and used in the performance of the work, if the rent of the equivalent amount is reasonable and use of that plant has been approved by the Departmental Representative;
- 50.2.5 payments for maintaining and operating plant necessary for and used in the performance of the work, and payments for effecting such repairs thereto as, in the opinion of the Departmental Representative, are necessary to the proper performance of the contract other than payments for any repairs to the plant arising out of defects existing before its allocation to the work;
- 50.2.6 payments for material that is necessary for and incorporated in the work, or that is necessary for and consumed in the performance of the contract;
- 50.2.7 payments for preparation, delivery, handling, erection, installation, inspection protection and removal of the plant and material necessary for and used in the performance of the contract; and
- 50.2.8 any other payments made by the Contractor with the approval of the Departmental Representative that are necessary for the performance of the contract.

GC51 Records to be kept by Contractor

51.1 The Contractor shall

- 51.1.1 maintain full records of his estimated and actual cost of the work together with all tender calls, quotations, contracts, correspondence, invoices, receipts and vouchers relating thereto.
- 51.1.2 make all records and material referred to in GC5.1.1 available to audit and inspection by the Minister and the Deputy Receiver General for Canada or by persons acting on behalf of either of both of them, when requested;
- 51.1.3 allow any of the person referred to in GC51.1.2 to make copies of and to take extracts from any of the records and material referred to in GC51.1.1; and
- 51.1.4 furnish any person referred to in GC51.1.2 with any information he may require from time to time in connection with such records and material.

- 51.2 The records maintained by the Contractor pursuant to GC51.1.1 shall be kept intact by the Contractor until the expiration of two years after the date that a Final Certificate of Completion referred to in GC44.1 was issued or until the expiration of such other period of time as the



Minister may direct.

- 51.3 The Contractor shall cause all subcontractors and all other persons directly or indirectly controlled by or affiliated with the Contractor and all persons directly or indirectly having control of the Contractor to comply with GC51.1 and GC51.2 as if they were the Contractor.

GC52 Conflict of Interest

- 52.1 It is a term of this contract that no former public office holder who is not in compliance with the Conflict of Interest and Post-Employment Code for Public Office Holders shall derive a direct benefit from this contract.

GC53 Contractor Status

- 53.1 The Contractor shall be engaged under the contract as an independent contractor.
- 53.2 The Contractor and any employee of the said Contractor is not engaged by the contract as an employee, servant or agent of Her Majesty.
- 53.3 For the purposes of GC53.1 and GC53.2 the Contractor shall be solely responsible for any and all payments and deductions required to be made by law including those required for Canada or Quebec Pension Plans, Unemployment Insurance, Worker's Compensation or Income Tax.



GENERAL CONDITONS

- IC 1 Proof of Insurance**
- IC 2 Risk Management**
- IC 3 Payment of Deductible**
- IC 4 Insurance Coverage**

GENERAL INSUANCE COVERAGES

- GCI 1 Insured**
- GIC 2 Period of Insurance**
- GIC 3 Proof of Insurance**
- GIC 4 Notification**

COMMERCIAL GENERAL LIABILITY

- CGL 1 Scope of Policy**
- CGL 2 Coverages/Provisions**
- CGL 3 Additional Exposures**
- CGL 4 Insurance Proceeds**
- CGL 5 Deductible**

BUILDER'S RISK – INSTALLATION FLOATER – ALL RISKS

- BR 1 Scope of Policy**
- BR 2 Property Insured**
- BR 3 Insurance Proceeds**
- BR 4 Amount of Insurance**
- BR 5 Deductible**
- BR 6 Subrogation**
- BR 7 Exclusion Qualifications**

INSURER'S CERTIFICATE OF INSURANCE



General Conditions

IC 1 Proof of Insurance (02/12/03)

Within thirty (30) days after acceptance of the Contractor's tender, the Contractor shall, unless otherwise directed in writing by the Contracting Officer, deposit with the Contracting Officer an Insurer's Certificate of Insurance in the form displayed in this document and, if requested by the Contracting Officer, the originals or certified true copies of all contracts of insurance maintained by the Contractor pursuant to the Insurance Coverage Requirements shown hereunder.

IC 2 Risk Management (01/10/94)

The provisions of the Insurance Coverage Requirements contained hereunder are not intended to cover all of the Contractor's obligations under GC8 of the General Conditions "C" of the contract. Any additional risk management measures or additional insurance coverages the Contractor may deem necessary to fulfill its obligations under GC8 shall be at its own discretion and expense.

IC 3 Payment of Deductible (01/10/94)

The payment of monies up to the deductible amount made in satisfaction of a claim shall be borne by the Contractor.

IC 4 Insurance Coverage (02/12/03)

The Contractor has represented that it has in place and effect the appropriate and usual liability insurance coverage as required by these Insurance Conditions and the Contractor has warranted that it shall obtain, in a timely manner and prior to commencement of the Work, the appropriate and usual property insurance coverage as required by these Insurance Conditions and, further, that it shall maintain all required insurance policies in place and effect as required by these Insurance Conditions.



INSURANCE COVERAGE REQUIREMENTS

PART I GENERAL INSURANCE COVERAGES (GIC)

GCI 1 Insured (02/12/03)

Each insurance policy shall insure the Contractor, and shall include, as an Additional Named Insured, Her Majesty the Queen in right of Canada, represented by the National Research Council Canada.

GIC 2 Period of Insurance (02/12/03)

Unless otherwise directed in writing by the Contracting Officer or otherwise stipulated elsewhere in these Insurance Conditions, the policies required hereunder shall be in force and be maintained from the date of the contract award until the day of issue of the Departmental Representative's Final Certificate of Completion.

GIC 3 Proof of Insurance (01/10/94)

Within twenty five (25) days after acceptance of the Contractor's tender, the Insurer shall, unless otherwise directed by the Contractor, deposit with the Contractor an Insurer's Certificate of Insurance in the form displayed in the document and, if requested, the originals or certified true copies of all contracts of insurance maintained by the Contractor pursuant to the requirements of these Insurance Coverages.

GIC 4 Notification (01/10/94)

Each Insurance policy shall contain a provision that (30) days prior written notice shall be given by the Insurer to Her Majesty in the event of any material change in or cancellation of coverage. Any such notice received by the Contractor shall be transmitted forthwith to Her Majesty.

PART II COMMERCIAL GENERAL LIABILITY

CGL 1 Scope of Policy (01/10/94)

The policy shall be written on a form similar to that known and referred to in the insurance industry as IBC 2100 – Commercial General Liability policy (Occurrence form) and shall provide for limit of liability of not less than \$2,000,000 inclusive for Bodily Injury and Property Damage for any one occurrence or series of occurrences arising out of one cause. Legal or defence cost incurred in respect of a claim or claims shall not operate to decrease the limit of liability.

CGL 2 Coverages/Provisions (01/10/94)



The policy shall include but not necessarily be limited to the following coverages/provisions.

- 2.1 Liability arising out of or resulting from the ownership, existence, maintenance or use of premises by the Contractor and operations necessary or incidental to the performance of this contract.
- 2.2 "Broad Form" Property Damage including the loss of use of property.
- 2.3 Removal or weakening of support of any building or land whether such support be natural or otherwise.
- 2.4 Elevator liability (including escalators, hoists and similar devices).
- 2.5 Contractor's Protective Liability
- 2.6 Contractual and Assumed Liabilities un this contact.
- 2.7 Completed Operations Liability – The insurance, including all aspects of this Part II of these Insurance Conditions shall continue for a period of at least one (1) year beyond the date of the Departmental Representative's Final Certificate of Completion for the Completed Operations.
- 2.8 Cross Liability – The Clause shall be written as follows:

Cross Liability – The insurance as is afforded by this policy shall apply in respect to any claim or action brought against any one Insured by any other Insured. The coverage shall apply in the same manner and to the same extent as though a separate policy had been issued to each Insured. The inclusion herein of more than one Insured shall not increase the limit of the Insurer's liability.

- 2.9 Severability of Interests – The Clause shall be written as follows:

Severability of Interests – This policy, subject to the limits of liability stated herein, shall apply separately to each Insured in the same manner and to the same extent as if a separate policy had been issued to each. The inclusion herein of more than one insured shall not increase the limit of the Insurer's liability.

CGL 3 Additional Exposures (02/12/03)

The policy shall either include or be endorsed to include the following exposures of hazards if the Work is subject thereto:

- 3.1 Blasting
- 3.2 Pile driving and calsson work
- 3.3 Underpinning
- 3.4 Risks associated with the activities of the Contractor on an active airport



- 3.5 Radioactive contamination resulting from the use of commercial isotopes
- 3.6 Damage to the portion of an existing building beyond that directly associated with an addition, renovation or installation contract.
- 3.7 Marine risks associated with the contraction of piers, wharves and docks.

**CGL 4 Insurance Proceeds
(01/10/94)**

Insurance Proceeds from this policy are usually payable directly to a Claimant/Third Party.

**CGL 5 Deductible
(02/12/03)**

This policy shall be issued with a deductible amount of not more than \$10,000 per occurrence applying to Property Damage claims only.

**PART III
BUILDER'S RISK – INSTALLATION FLOATER – ALL RISKS**

**BR 1 Scope of Policy
(01/10/94)**

The policy shall be written on an "All Risks" basis granting coverages similar to those provided by the forms known and referred to in the insurance industry as "Builder's Risk Comprehensive Form" or "Installation Floater – All Risks".

**BR 2 Property Insured
(01/10/94)**

The property insured shall include:

- 2.1 The Work and all property, equipment and materials intended to become part of the finished Work at the site of the project while awaiting, during and after installation, erection or construction including testing.
- 2.2 Expenses incurred in the removal from the construction site of debris of the property insured, including demolition of damaged property, de-icing and dewatering, occasioned by loss, destruction or damage to such property and in respect of which insurance is provided by this policy.

**BR 3 Insurance Proceeds
(01/10/94)**

- 3.1 Insurance proceeds from this policy are payable in accordance with GC28 of the General Conditions "C" of the contract.
- 3.2 This policy shall provide that the proceeds thereof are payable to Her Majesty or as the Minister may direct.



- 3.3 The Contractor shall do such things and execute such documents as are necessary to effect payment of the proceeds.

BR 4 Amount of Insurance
(01/10/94)

The amount of insurance shall not be less than the sum of the contract value plus the declared value (if any) set forth in the contract documents of all material and equipment supplied by Her Majesty at the site of the project to be incorporated into and form part of the finished Work.

BR 5 Deductible
(02/12/03)

The Policy shall be issued with a deductible amount of not more than \$10,000.

BR 6 Subrogation
(01/10/94)

The following Clause shall be included in the policy:

"All rights of subrogation or transfer of rights are hereby waived against any corporation, firm, individual or other interest, with respect to which, insurance is provided by this policy".

BR 7 Exclusion Qualifications
(01/10/94)

The policy may be subject to the standard exclusions but the following qualifications shall apply:

- 7.1 Faulty materials, workmanship or design may be excluded only to the extent of the cost of making good thereof and shall not apply to loss or damage resulting therefrom.
- 7.2 Loss or damage caused by contamination by radioactive material may be excluded except for loss or damage resulting from commercial isotopes used for industrial measurements, inspection, quality control radiographic or photographic use.
- 7.3 Use and occupancy of the project or any part of section thereof shall be permitted where such use and occupancy is for the purpose for which the project is intended upon completion.



INSURER'S CERTIFICATE OF INSURANCE

(TO BE COMPLETED BY INSURER (NOT BOKER) AND DELIVERD TO NATIONAL RESEARCH COUNCIL CANADA WITH 30 DAYS FOLLOWING ACCEPTANCE OF TENDER)

CONTRACT

DESCRIPTION OF WORK	CONTRACT NUMBER	AWARD DATE
LOCATION		

INSURER

NAME
ADDRESS

BROKER

NAME
ADDRESS

INSURED

NAME OF CONTRACTOR
ADDRESS

ADDITIONAL INSURED

HER MAJESTY THE QUEEN IN RIGHT OF CANADA AS REPRESENTED BY THE NATIONAL RESEARCH COUNCIL CANADA

THIS DOCUENT CERTIFIES THAT THE FOLLOWING POLICES OF INSURANCE ARE AT PRESENT IN FORCE COVERING ALL OPERATIONS OF THE INSURE IN CONNECTION WITH THE CONTRACT MADE BETWEEN THE NAMED INSURED AND THE NATIONAL RESEARCH COUNCIL CANADA AND IN ACCORDANCE WITH THE INSURANCE CONDITIONS "E"

POLICY					
TYPE	NUMBER	INCEPTION DATE	EXPIRY DATE	LIMITS OF LIABILITY	DEDUCTIBLE
COMMERCIAL GENERAL LIABILITY					
BUILDERS RISK "AL RISKS"					
INSTALLATION FLOATER "ALL RISKS"					

THE INSURER AGREES TO NOTIFY THE NATIONAL RESEARCH COUNCIL CANADA IN WRITING 30 DAYS PRIOR TO ANY MATERIAL CHANGE IN OR CANCELLATION OF ANY POLICY OR COVERAGE SPECIFICALLY RELATED TO THE CONTRACT

NAME OF INSURER'S OFFICER OR AUTHORIZED EMPLOYEE	SIGNATURE	DATE:
		TELEPHONE NUMBER:

ISSUANCE OF THIS CERTIFIATE SHALL NOT LIMIT OR RESTRICT THE RIGHT OF THE NATIONAL RESEARCH COUNCIL CANADA TO REQUEST AT ANY TIME DUPLICATE COPIES OF SAID INSURANCE POLICIES



CS1 Obligation to provide Contract Security

- 1.1 The Contractor shall, at the Contractor's own expense, provide one or more of the forms of contract security prescribed in CS2.
- 1.2 The Contractor shall deliver to the Departmental Representative the contract security referred to in CS1.1 within 14 days after the date that the Contractor receives notice that the Contractor's tender or offer was accepted by Her Majesty.

CS2 Prescribed Types and Amounts of Contract Security

- 2.1 The Contractor shall deliver to the Departmental Representative pursuant to CS1
 - 2.1.1 a performance bond and a labour and material payment bond each in an amount that is equal to not less than 50% of the contract amount referred to in the Articles of Agreement, or
 - 2.1.2 a labour and material payment bond in an amount that is equal to not less than 50% of the contract amount referred to in the Articles of Agreement, and a security deposit in an amount that is equal to
 - 2.1.2.1 not less than 10% of the contract amount referred to in the Articles of Agreement where that amount does not exceed \$250,000, or
 - 2.1.2.2 \$25,000 plus 5% of the part of the contract amount referred to in the Articles of Agreement that exceeds \$250,000, or
 - 2.1.3 a security deposit in an amount prescribed by CS2.12 plus an additional amount that is equal to 10% of the contract amount referred to in the Articles of Agreement.
- 2.2 A performance bond and a labour and material payment bond referred to in CS2.1 shall be in a form and be issued by a bonding or surety company that is approved by Her Majesty.
- 2.3 The amount of a security deposit referred to in CS2.1.2 shall not exceed \$250,000 regardless of the contract amount referred to in the Articles of Agreement.
- 2.4 A security deposit referred to in CS2.1.2 and CS2.1.3 shall be in the form of
 - 2.4.1 a bill of exchange made payable to the Receiver General of Canada and certified by an approved financial institution or drawn by an approved financial institution on itself, or
 - 2.4.2 bonds of or unconditionally guaranteed as to principal and interest by the Government of Canada.
- 2.5 For the purposes of CS2.4
 - 2.5.1 a bill of exchange is an unconditional order in writing signed by the Contractor and addressed to an approved financial institution, requiring the said institution to pay, on demand, at a fixed or determinable future time a sum certain of money to, or to the order



of, the Receiver General for Canada, and

- 2.5.2 If a bill of exchange is certified by a financial institution other than a chartered bank then it must be accompanied by a letter or stamped certification confirming that the financial institution is in at least one of the categories referred to in CS2.5.3
- 2.5.3 an approved financial institution is
 - 2.5.3.1 any corporation or institution that is a member of the Canadian Payments Association,
 - 2.5.3.2 a corporation that accepts deposits that are insured by the Canada Deposit Insurance Corporation or the Régie de l'assurance-dépôts du Québec to the maximum permitted by law,
 - 2.5.3.3 a credit union as defined in paragraph 137(6)(b) of the *Income Tax Act*,
 - 2.5.3.4 a corporation that accepts deposits from the public, if repayment of the deposit is guaranteed by Her Majesty in right of a province, or
 - 2.5.3.5 The Canada Post Corporation.
- 2.5.4 the bonds referred to in CS2.4.2 shall be
 - 2.5.4.1 made payable to bearer, or
 - 2.5.4.2 accompanied by a duly executed instrument of transfer of the bonds to the Receiver General for Canada in the form prescribed by the Domestic Bonds of Canada Regulations, or
 - 2.5.4.3 registered, as to principal or as to principal and interest in the name of the Receiver General for Canada pursuant to the Domestic Bonds of Canada Regulations, and
 - 2.5.4.4 provided on the basis of their market value current at the date of the contract.



Contract Number / Numéro du contrat PR907755
Security Classification / Classification de sécurité UNCLASSIFIED

**SECURITY REQUIREMENTS CHECK LIST (SRCL)
LISTE DE VÉRIFICATION DES EXIGENCES RELATIVES À LA SÉCURITÉ (LVERS)**

PART A - CONTRACT INFORMATION / PARTIE A - INFORMATION CONTRACTUELLE

1. Originating Government Department or Organization / Ministère ou organisme gouvernemental d'origine NRC	2. Branch or Directorate / Direction générale ou Direction RPPM
3. a) Subcontract Number / Numéro du contrat de sous-traitance 6032	3. b) Name and Address of Subcontractor / Nom et adresse du sous-traitant Tender

4. Brief Description of Work / Brève description du travail
6032 S77 TENDER Steam to Hot Water Conversion
To install NEW Hot Water Heating System due to the De-Commissioning of the existing Steam Plant

5. a) Will the supplier require access to Controlled Goods?
Le fournisseur aura-t-il accès à des marchandises contrôlées? No / Non Yes / Oui

5. b) Will the supplier require access to unclassified military technical data subject to the provisions of the Technical Data Control Regulations?
Le fournisseur aura-t-il accès à des données techniques militaires non classifiées qui sont assujetties aux dispositions du Règlement sur le contrôle des données techniques? No / Non Yes / Oui

6. Indicate the type of access required / Indiquer le type d'accès requis

6. a) Will the supplier and its employees require access to PROTECTED and/or CLASSIFIED information or assets?
Le fournisseur ainsi que les employés auront-ils accès à des renseignements ou à des biens PROTÉGÉS et/ou CLASSIFIÉS?
(Specify the level of access using the chart in Question 7. c)
(Préciser le niveau d'accès en utilisant le tableau qui se trouve à la question 7. c) No / Non Yes / Oui

6. b) Will the supplier and its employees (e.g. cleaners, maintenance personnel) require access to restricted access areas? No access to PROTECTED and/or CLASSIFIED information or assets is permitted.
Le fournisseur et ses employés (p. ex. nettoyeurs, personnel d'entretien) auront-ils accès à des zones d'accès restreintes? L'accès à des renseignements ou à des biens PROTÉGÉS et/ou CLASSIFIÉS n'est pas autorisé. No / Non Yes / Oui

6. c) Is this a commercial courier or delivery requirement with **no** overnight storage?
S'agit-il d'un contrat de messagerie ou de livraison commerciale **sans** entreposage de nuit? No / Non Yes / Oui

7. a) Indicate the type of information that the supplier will be required to access / Indiquer le type d'information auquel le fournisseur devra avoir accès

Canada <input checked="" type="checkbox"/>	NATO / OTAN <input type="checkbox"/>	Foreign / Étranger <input type="checkbox"/>
---	---	--

7. b) Release restrictions / Restrictions relatives à la diffusion

No release restrictions Aucune restriction relative à la diffusion <input checked="" type="checkbox"/>	All NATO countries Tous les pays de l'OTAN <input type="checkbox"/>	No release restrictions Aucune restriction relative à la diffusion <input type="checkbox"/>
Not releasable À ne pas diffuser <input type="checkbox"/>		
Restricted to: / Limité à : <input type="checkbox"/>	Restricted to: / Limité à : <input type="checkbox"/>	Restricted to: / Limité à : <input type="checkbox"/>
Specify country(ies): / Préciser le(s) pays :	Specify country(ies): / Préciser le(s) pays :	Specify country(ies): / Préciser le(s) pays :

7. c) Level of information / Niveau d'information

PROTECTED A PROTÉGÉ A <input type="checkbox"/>	NATO UNCLASSIFIED NATO NON CLASSIFIÉ <input type="checkbox"/>	PROTECTED A PROTÉGÉ A <input type="checkbox"/>
PROTECTED B PROTÉGÉ B <input type="checkbox"/>	NATO RESTRICTED NATO DIFFUSION RESTREINTE <input type="checkbox"/>	PROTECTED B PROTÉGÉ B <input type="checkbox"/>
PROTECTED C PROTÉGÉ C <input type="checkbox"/>	NATO CONFIDENTIAL NATO CONFIDENTIEL <input type="checkbox"/>	PROTECTED C PROTÉGÉ C <input type="checkbox"/>
CONFIDENTIAL CONFIDENTIEL <input type="checkbox"/>	NATO SECRET NATO SECRET <input type="checkbox"/>	CONFIDENTIAL CONFIDENTIEL <input type="checkbox"/>
SECRET SECRET <input type="checkbox"/>	COSMIC TOP SECRET COSMIC TRÈS SECRET <input type="checkbox"/>	SECRET SECRET <input type="checkbox"/>
TOP SECRET TRÈS SECRET <input type="checkbox"/>		TOP SECRET TRÈS SECRET <input type="checkbox"/>
TOP SECRET (SIGINT) TRÈS SECRET (SIGINT) <input type="checkbox"/>		TOP SECRET (SIGINT) TRÈS SECRET (SIGINT) <input type="checkbox"/>



Contract Number / Numéro du contrat PR907755
Security Classification / Classification de sécurité UNCLASSIFIED

PART A (continued) / PARTIE A (suite)

8. Will the supplier require access to PROTECTED and/or CLASSIFIED COMSEC information or assets?
Le fournisseur aura-t-il accès à des renseignements ou à des biens COMSEC désignés PROTÉGÉS et/ou CLASSIFIÉS?
If Yes, indicate the level of sensitivity:
Dans l'affirmative, indiquer le niveau de sensibilité :

No / Non Yes / Oui

9. Will the supplier require access to extremely sensitive INFOSEC information or assets?
Le fournisseur aura-t-il accès à des renseignements ou à des biens INFOSEC de nature extrêmement délicate?

No / Non Yes / Oui

Short Title(s) of material / Titre(s) abrégé(s) du matériel :
Document Number / Numéro du document :

PART B - PERSONNEL (SUPPLIER) / PARTIE B - PERSONNEL (FOURNISSEUR)

10. a) Personnel security screening level required / Niveau de contrôle de la sécurité du personnel requis

<input checked="" type="checkbox"/> RELIABILITY STATUS COTE DE FIABILITÉ	<input type="checkbox"/> CONFIDENTIAL CONFIDENTIEL	<input type="checkbox"/> SECRET SECRET	<input type="checkbox"/> TOP SECRET TRÈS SECRET
<input type="checkbox"/> TOP SECRET-SIGINT TRÈS SECRET - SIGINT	<input type="checkbox"/> NATO CONFIDENTIAL NATO CONFIDENTIEL	<input type="checkbox"/> NATO SECRET NATO SECRET	<input type="checkbox"/> COSMIC TOP SECRET COSMIC TRÈS SECRET
<input type="checkbox"/> SITE ACCESS ACCÈS AUX EMBLEMES			

Special comments:
Commentaires spéciaux : _____

NOTE: If multiple levels of screening are identified, a Security Classification Guide must be provided.
REMARQUE : Si plusieurs niveaux de contrôle de sécurité sont requis, un guide de classification de la sécurité doit être fourni.

10. b) May unscreened personnel be used for portions of the work?
Du personnel sans autorisation sécuritaire peut-il se voir confier des parties du travail?
If Yes, will unscreened personnel be escorted?
Dans l'affirmative, le personnel en question sera-t-il escorté?

No / Non Yes / Oui

No / Non Yes / Oui

PART C - SAFEGUARDS (SUPPLIER) / PARTIE C - MESURES DE PROTECTION (FOURNISSEUR)

INFORMATION / ASSETS / RENSEIGNEMENTS / BIENS

11. a) Will the supplier be required to receive and store PROTECTED and/or CLASSIFIED information or assets on its site or premises?
Le fournisseur sera-t-il tenu de recevoir et d'entreposer sur place des renseignements ou des biens PROTÉGÉS et/ou CLASSIFIÉS?

No / Non Yes / Oui

11. b) Will the supplier be required to safeguard COMSEC information or assets?
Le fournisseur sera-t-il tenu de protéger des renseignements ou des biens COMSEC?

No / Non Yes / Oui

PRODUCTION

11. c) Will the production (manufacture, and/or repair and/or modification) of PROTECTED and/or CLASSIFIED material or equipment occur at the supplier's site or premises?
Les installations du fournisseur serviront-elles à la production (fabrication et/ou réparation et/ou modification) de matériel PROTÉGÉ et/ou CLASSIFIÉ?

No / Non Yes / Oui

INFORMATION TECHNOLOGY (IT) MEDIA / SUPPORT RELATIF À LA TECHNOLOGIE DE L'INFORMATION (TI)

11. d) Will the supplier be required to use its IT systems to electronically process, produce or store PROTECTED and/or CLASSIFIED information or data?
Le fournisseur sera-t-il tenu d'utiliser ses propres systèmes informatiques pour traiter, produire ou stocker électroniquement des renseignements ou des données PROTÉGÉS et/ou CLASSIFIÉS?

No / Non Yes / Oui

11. e) Will there be an electronic link between the supplier's IT systems and the government department or agency?
Disposera-t-on d'un lien électronique entre le système informatique du fournisseur et celui du ministère ou de l'agence gouvernementale?

No / Non Yes / Oui



PART C - (continued) / PARTIE C - (suite)

For users completing the form **manually** use the summary chart below to indicate the category(ies) and level(s) of safeguarding required at the supplier's site(s) or premises.

Les utilisateurs qui remplissent le formulaire **manuellement** doivent utiliser le tableau récapitulatif ci-dessous pour indiquer, pour chaque catégorie, les niveaux de sauvegarde requis aux installations du fournisseur.

For users completing the form **online** (via the Internet), the summary chart is automatically populated by your responses to previous questions.

Dans le cas des utilisateurs qui remplissent le formulaire **en ligne** (par Internet), les réponses aux questions précédentes sont automatiquement saisies dans le tableau récapitulatif.

SUMMARY CHART / TABLEAU RÉCAPITULATIF

Category Catégorie	PROTECTED PROTÉGÉ			CLASSIFIED CLASSIFIÉ			NATO				COMSEC					
	A	B	C	CONFIDENTIAL CONFIDENTIEL	SECRET	TOP SECRET TRÈS SECRET	NATO RESTRICTED NATO DIFFUSION RESTREINTE	NATO CONFIDENTIAL NATO CONFIDENTIEL	NATO SECRET	COSMIC TOP SECRET COSMIC TRÈS SECRET	PROTECTED PROTÉGÉ			CONFIDENTIAL CONFIDENTIEL	SECRET	TOP SECRET TRÈS SECRET
											A	B	C			
Information / Assets Renseignements / Biens Production																
IT Media / Support TI																
IT Link / Lien électronique																

12. a) Is the description of the work contained within this SRCL PROTECTED and/or CLASSIFIED?
La description du travail visé par la présente LVERS est-elle de nature PROTÉGÉE et/ou CLASSIFIÉE?

No / Non Yes / Oui

If Yes, classify this form by annotating the top and bottom in the area entitled "Security Classification".
Dans l'affirmative, classifiez le présent formulaire en indiquant le niveau de sécurité dans la case intitulée « Classification de sécurité » au haut et au bas du formulaire.

12. b) Will the documentation attached to this SRCL be PROTECTED and/or CLASSIFIED?
La documentation associée à la présente LVERS sera-t-elle PROTÉGÉE et/ou CLASSIFIÉE?

No / Non Yes / Oui

If Yes, classify this form by annotating the top and bottom in the area entitled "Security Classification" and indicate with attachments (e.g. SECRET with Attachments).
Dans l'affirmative, classifiez le présent formulaire en indiquant le niveau de sécurité dans la case intitulée « Classification de sécurité » au haut et au bas du formulaire et indiquez qu'il y a des pièces jointes (p. ex. SECRET avec des pièces jointes).



Contract Number / Numéro du contrat PR907755
Security Classification / Classification de sécurité UNCLASSIFIED

PART D - AUTHORIZATION / PARTIE D - AUTORISATION

13. Organization Project Authority / Chargé de projet de l'organisme

Name (print) - Nom (en lettres moulées) Allan Smith		Title - Titre Project Manager	Signature Smith, Allan <small>Digitally signed by Smith, Allan DN: cn=Smith, Allan, c=CA, o=GC, ou=NRC-CNRC, email=allan.smith@canada.ca Date: 2022.08.09 17:31:28 -04'00'</small>
Telephone No. - N° de téléphone 991-9873	Facsimile No. - N° de télécopieur	E-mail address - Adresse courriel allan.smith@nrc-cnrc.gc.ca	Date

14. Organization Security Authority / Responsable de la sécurité de l'organisme

Name (print) - Nom (en lettres moulées) Tori Pelletier		Title - Titre Analyst, Security in Contracting	Signature Pelletier, Tori <small>Digitally signed by Pelletier, Tori DN: cn=Pelletier, Tori, c=CA, o=GC, ou=NRC-CNRC, email=tori.pelletier@nrc- nrc.gc.ca Date: 2022.08.10 09:55:24 -04'00'</small>
Telephone No. - N° de téléphone	Facsimile No. - N° de télécopieur	E-mail address - Adresse courriel Tori.Pelletier@nrc-cnrc.gc.ca	Date

15. Are there additional instructions (e.g. Security Guide, Security Classification Guide) attached?
Des instructions supplémentaires (p. ex. Guide de sécurité, Guide de classification de la sécurité) sont-elles jointes?

No / Non Yes / Oui

16. Procurement Officer / Agent d'approvisionnement

Name (print) - Nom (en lettres moulées) Tania Backes		Title - Titre Procurement Officer	Signature
Telephone No. - N° de téléphone	Facsimile No. - N° de télécopieur	E-mail address - Adresse courriel tania.backes@nrc-cnrc.gc.ca	Date

17. Contracting Security Authority / Autorité contractante en matière de sécurité

Name (print) - Nom (en lettres moulées)		Title - Titre	Signature
Telephone No. - N° de téléphone	Facsimile No. - N° de télécopieur	E-mail address - Adresse courriel	Date