



RETURN BIDS TO:

Parks Canada Agency Bid Receiving Unit
National Contracting Services

Bid Fax: 1-855-983-1808

Bid Email: soumissionsami-bidsrpc@pc.gc.ca

This is the only acceptable email address for responses to the bid solicitation. Bids submitted by email directly to the Contracting Authority or to any other email address will not be accepted.

The maximum email file size is 15 megabytes. The Parks Canada Agency (PCA) is not responsible for any transmission errors. Emails with links to bid documents will not be accepted.

**REVISION 001 TO
INVITATION TO TENDER**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions remain the same.

Issuing Office:

**Parks Canada Agency
National Contracting Services
Halifax, Nova Scotia**

Title: Flat Roof Replacement, Laurier House National Historic Site	
Solicitation No.: 5P468-22-0088/A	Date: 19 August 2022
Amendment No.: 001	
Client Reference No.: N/A	
GETS Reference No.: PW-22-01003490	
Solicitation Closes: At: 14:00 On: 23 August 2022	Time Zone: EDT
F.O.B.: Plant: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other: <input type="checkbox"/>	
Address Enquiries to: Jaime Creaser	
Telephone No.: 902-266-8592	Fax No.: 1-855-983-1808
Email Address: Jaime.Creaser@pc.gc.ca	
Destination of Goods, Services, and Construction: See Herein	

TO BE COMPLETED BY THE BIDDER

Vendor/ Firm Name:	
Address:	
Telephone No.:	Fax No.:
Name of person authorized to sign on behalf of the Vendor/ Firm (type or print):	
Signature:	Date:

Solicitation No.:
5P468-22-0088/A

Amendment No.:
001

Contracting Authority:
Jaime Creaser

Client Reference No.:
N/A

Title:
Flat Roof Replacement, Laurier House National Historic Site

Amendment 001

This amendment is raised to distribute questions and answers from the optional site visit held on 11 August 2022.

1.0 Questions and Answers

Q1. Mechanical Room on Roof: please be more specific with respect to the paint removal technique / is sand (or other media) blasting acceptable?

A1. Use the technique as specified in 3.3.2 of Section 09 91 99 - Painting. Compressed air is acceptable mostly to remove the flaking paint, but without any media: "sandblasting" is not accepted. Precision with regards to 3.3.2.1: Do not use wire brushes aggressively and manually only - no power tools. This wire brush is to be made of brass wires; not steel wires. The goal is to preserve the galvanized coating undamaged.

Q2. Are anchors certified?

A2. No. Please see Roof Anchor note on drawing A002.

Q3. Are there stacks that are no longer in service and that only require to be cut at roof field level? (three (3) currently are capped)

A3. Should the stacks that are no longer in service, Parks may decide to cut at field level.

Q4. Lower roof: no access upon job showing. Please provide photos to compensate.

A4. See photos in folder DSP 001 5P468-22-0088.

Q5. Can we wait until March 2023 to do the work?

A5. The contract documents indicate March 31, 2023 as completion date. However, the vast majority of the specifications refer to products for which manufacturers' instructions preclude installation at low temperatures or even relatively low temperatures. Our assessment is that a substantial completion by mid-October will ensure compliance with manufacturer's instructions as well as ease project delivery.

ALL OTHER TERMS & CONDITIONS REMAIN UNCHANGED.