

Part 1 General

1.1 DESCRIPTION OF WORK

- .1 This Section includes but is not limited to the following:
 - .1 All sitework, demolition and removals as required to complete the work. All items to be verified prior to submission of a tender.

1.2 RELATED SECTIONS

- .1 Refer to Section 01 33 00 for Submittal Procedures.

1.3 SUBMISSIONS

- .1 Methodology:
 - .1 Provide methodology for carrying out the major components of the work.
 - .2 Provide submissions in accordance with Section 01 33 00.

1.4 PROTECTION

- .1 Prevent movement, settlement, or damage of adjacent structures. Provided bracing and shoring as required. In event of damage, immediately replace such items or make repairs to approval of a Departmental Representative and at no additional cost.
- .2 Prevent debris from entering harbour and creating navigational hazards.
- .3 All damage to existing structures, roadways, etc., not specified for removal to be repaired at the Contractor's cost to the satisfaction of the Departmental Representative.
- .4 Do not load or travel on any structures other than those designated for replacement. Capacity of existing structures is unknown.

1.5 MEASUREMENT FOR PAYMENT

- .1 Refer to Section 01 29 10 for measurement for payment.
- .2 Item shall include demolitions, selective demolitions, removals, transportation, disposal, environmental protective measures, and site cleanup.
- .3 The disposal of creosote timbers shall be paid as a separate item; see Section 01 29 10.

Part 2 Products

2.1 Not Used

Part 3 Execution

3.1 PREPARATION

- .1 Inspect site and verify with the Departmental Representative the items which are designated for removal and items to be preserved.

- .2 Do not disturb adjacent structures designated to remain in place.

3.2 REMOVAL

- .1 Remove/demolish items indicated. These items include but are not limited to:
 - .1 Remove of existing navigational light is by others.
 - .2 Fully demolish Structure 403 Pier.
 - .3 Partially demolish Structure 403 Marginal Wharf to approximately El. +1.3 meters.
 - .4 Local trimming and removals of the timbers crib as required to facilitate construction of the new wharf (i.e., Deadman placement).
- .2 At end of each day's work, leave work in safe condition so no part is in danger of toppling or failing.
- .3 Excavate to extents and dimensions indicated on the drawings.
- .4 Do not leave existing or new structure open or exposed to the elements at the end of each day. This is of particular importance regarding wave exposure.

3.3 DISPOSAL OF MATERIAL

- .1 See Section 01 74 21 for disposal requirements for creosote/treated timbers and excess soils.

3.4 RESTORATION

- .1 Upon completion of work, remove debris, trim surfaces, and leave work site clean.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work. Match condition of adjacent, undisturbed areas.

END OF SECTION