


GENERAL NOTES:

1. ELECTRICAL ITEMS SHOWN DOTTED ARE EXISTING AND SHALL REMAIN OR BE RELOCATED AS NOTED. ITEMS MARKED WITH ASTERISK (\*) SHALL BE DISCONNECTED AND REMOVED.
2. ELECTRICAL CONTRACTOR SHALL EXTEND, RE-ROUTE, RE-WIRE AND RECONNECT ALL ELECTRICAL ITEMS AS CONFLICTING WITH RENOVATION.
3. ALL EXTERIOR WALL PENETRATIONS TO BE MADE WATER-PROOF AND FIRE-PROOF WITH DOW CORNING RTV FOAM OR CONSULTANT APPROVED EQUIVALENT.
4. ALL CONFLICTING WIRING DEVICES AND CONDUIT IN CSB AND ATB BUILDINGS REQUIRED TO REMAIN IN USE FOR ANY REASON SHALL BE RE-ROUTED, ALTERED AND/OR DIVERTED BY ELECTRICAL CONTRACTOR IN AN APPROVED MANNER. ANY BRANCH CIRCUIT WIRING FOR ANY SYSTEM NO LONGER REQUIRED TO REMAIN IN USE SHALL BE REMOVED, OR IF THIS IS NOT POSSIBLE RENDERED PERMANENTLY IN ACCESSIBLE AND COMPLETELY DISCONNECTED FROM ITS SOURCE, CAP EXISTING WIRING/CONDUIT BELOW GRADE AND LABEL WITH PERMANENT SYSTEM.
5. PROVIDE 21mm THICK PLYWOOD BACKBOARD FOR NEW EQUIPMENT MOUNTED ON WALLS.
6. TURN OVER ALL SALVAGED ITEMS TO OWNER AT DESIGNATED LOCATION BY DEPARTMENTAL REPRESENTATIVE.
7. ELECTRICAL CONTRACTOR SHALL ARRANGE WITH NEWFOUNDLAND & LABRADOR HYDRO, OWNERS AND CONSULTANT FOR SWITCHING OVER OF EXISTING U/G POWER SERVICE TO NEW U/G SERVICE FOR PROPER PHASING OF ALL WORK DURING AFTER HOURS OPERATION. MINIMIZE SERVICE INTERRUPTION. NOTE: ANY SHUTDOWN BEYOND 8 HOURS THE CONTRACTOR TO PROVIDE TEMPORARY PORTABLE POWER CONNECTION (GENERATOR) TO POWER UP THE LOAD AND PAY ALL ASSOCIATED RENTALS, UTILIZATION/OPERATIONAL, MATERIAL AND LABOUR FEES AS REQUIRED TO KEEP THE POWER OPERATIONAL.
8. ELECTRICAL CONTRACTOR SHALL VISIT THE SITE TO DETERMINE THE REQUIRED WORK.

SYMBOL LEGEND:

- POLE LIGHT
- 120V POWER RECEPTACLE
- HYDRO POLE
- PAD MOUNTED TRANSFORMER
- ELECTRICITY METER
- ED DENOTES EXISTING TO BE DISCONNECTED AND REMOVED
- E DENOTES EXISTING TO REMAIN



3	ISSUED FOR CONSTRUCTION	JUL 29 2022
2	100% REVIEW SUBMISSION	JUN 30 2022
1	99% REVIEW SUBMISSION	MAY 27 2022
0	60% REVIEW SUBMISSION	MAR 31 2022

revisions	date
-----------	------

project Wabush Service Upgrade – Wabush Airport

Wabush Airport Terminal Building (ATB)

drawing design

EXISTING ELECTRICAL SITE PLAN

designed HCC conçu

date

drawn dessin

date

approved HCC approuvé

date


Tender Soumission

PWGSC Project Manager Administrateur de projets TPSGC

project number no. du projet

R1111141.001

drawing no. no. du dessin



APPROX. NORTH

