




PLUMBING FIXTURE SCHEDULE									
No.	FIXTURE TYPE	TRIM			PIPE SIZE				DESCRIPTION
		STOPS	SUPPLY	TRAP	DCW	DHW	SAN	VENT	
P1	B.F. 4.8L TANK WATER CLOSET	—	—	—	13	—	75	38	c/w SLOWCLOSE SEAT & LINED TANK
P2	WALL HUNG BASIN	—	—	—	13	13	32	32	c/w THERMOSTATIC MIXING VALVE, WALL CARRIER.
P2a	SINGLE BOWL STAINLESS STEEL KITCHEN SINK	—	—	—	13	13	38	38	—
P3	EYE/FACE WASH/SHOWER	—	—	—	32	32	32	32	c/w FIXTURE MANUFACTURER'S MIXING VALVE, GAUGE & STAINLESS STEEL VALVE CABINET.
H8	HOSE BIBB	—	—	—	20	—	—	—	—
NOTE: —PLASTIC 'P' TRAPS WILL NOT BE ACCEPTED IN PLACE OF CHROME PLATED TRAPS (NO EXCEPTIONS) —ALL PLUMBING FIXTURES SHALL BE BY ONE MANUFACTURER. —ALL STOPS SHALL BE BY ONE MANUFACTURER. —ALL SUPPLIES SHALL BE BY ONE MANUFACTURER. —REFER TO SPECIFICATIONS FOR FIXTURE CONSTRUCTION/PERFORMANCE/ACCESSORY REQUIREMENTS.									




1 DOMESTIC HOT WATER TANK DETAIL  
SCALE : N.T.S.




2 TYPICAL EMERGENCY EYEWASH / SHOWER DETAIL  
SCALE : N.T.S.




3 WATER ENTRANCE DETAIL  
SCALE : N.T.S.



4 CATCH BASIN DETAIL  
SCALE : N.T.S.



5 WATER HAMMER ARRESTOR DETAIL  
SCALE : N.T.S.



6 ELECTRONIC TRAP PRIMER UNIT DETAIL  
SCALE : N.T.S.



3	ISSUED FOR TENDER	04/14 2022
2	ISSUED FOR RS4 99% SUBMISSION	10/30 2020
1	ISSUED FOR RS4 66% SUBMISSION	02-28 2020
0	ISSUED FOR RS3 SUBMISSION	08-17 2018
revisions		date

project project

SEWAGE TREATMENT UPGRADES  
SPRINGHILL INSTITUTION  
SPRINGHILL, NS

drawing dessin

PLUMBING DETAILS  
& SCHEDULES

designed	MJM	conçu
date	2018-08-17	
drawn	CC	dessiné
date	2018-08-17	
approved	MJM	approuvé
date	2018-08-17	
Tender		Soumission
PWGSC Project Manager	Administrateur de projets TP50C	
project number		no. du projet
	R.061876.001	
drawing no.		no. du dessin
	M04	