






- INSTALLATION OF GEOTEXTILE SILT FENCE
1. EXCAVATE A 100x100 TRENCH IN A CRESCENT SHAPE ACROSS THE FLOW PATH WITH ENDS POINTING UPSLOPE
 2. DRIVE STURDY STAKES, SPACED 3000 APART, INTO THE GROUND ALONG THE DOWNSLOPE SIDE OF THE TRENCH.
 3. INSTALL THE FILTER FABRIC FROM A CONTINUOUS ROLL AND CUT TO REQUIRED LENGTH. THE FILTER FABRIC SHOULD BE STAPLED TO THE UPSTREAM SIDE OF THE STAKES, EXTENDING THE BOTTOM 200 INTO THE TRENCH.
 4. BACKFILL AND COMPACT THE SOIL INTO THE TRENCH OVER THE FILTER FABRIC.



SCALE : 1:20



SCALE : 1:20



3	ISSUED FOR TENDER	04/14/2022
2	ISSUED FOR RS4 99% SUBMISSION	10/30/2020
1	ISSUED FOR RS4 66% SUBMISSION	02/28/2020
0	ISSUED FOR RS3 SUBMISSION	08/17/2018

SEWAGE TREATMENT UPGRADES
SPRINGHILL INSTITUTION
SPRINGHILL, NS

MANHOLE DETAILS

designed	GMG	conçu
date	2018-09-11	
drawn	ASA	dessiné
date	2018-09-11	
approved	PP	approuvé
date	2018-09-11	
tender		soumission

project number: R.061876.001
no. du projet

drawing no.: C22
no. du dessin