

- NOTE:**
- CONTRACTOR TO REVIEW EQUIPMENT INSTALLATION MANUALS PRIOR TO THE START OF CONSTRUCTION TO CONFIRM ON-SITE REQUIREMENTS.
 - EXACT LOCATION AND DIMENSIONS OF CORE DRILLED HOLES SHALL BE CONFIRMED BY THE CONTRACTOR TO ENSURE PROPER INSTALLATION OF PIPE PENETRATION SEALS.
 - FOLLOW MANUFACTURERS INSTRUCTIONS FOR EQUIPMENT OFF LOADING, STORAGE AND INSTALLATION, REFER TO SPECIFICATIONS.
 - REFER TO DRAWING M03 FOR WATER SERVICE LINES FOR FINE SCREEN SYSTEM AND WASHER COMPACTOR. CONTRACTOR RESPONSIBLE FOR CONNECTIONS TO EQUIPMENT.
 - EXACT LOCATION OF ULTRASONIC LEVEL SENSORS TO BE AS RECOMMENDED PER SCREEN AND PARSHALL FLUME MANUFACTURERS.
 - EACH 38mm Ø UNDERGROUND CONDUIT TO INCLUDE A 9mm Ø SAMPLING TUBING WITH PIPE SEALANT, AS PER MANUFACTURER'S RECOMMENDATIONS. SPARE TUBING TO BE COILED AT EACH END AND CAPPED TO PREVENT DEBRIS FROM ENTERING. TUBING TO BE FASTENED TO CHANNEL WALL AS REQUIRED (REFER TO SPECIFICATIONS).

revisions	date
3	ISSUED FOR TENDER 04/14/2022
2	ISSUED FOR RS4 99% SUBMISSION 10/28/2020
1	ISSUED FOR RS4 66% SUBMISSION 02-28/2020
0	ISSUED FOR RS3 SUBMISSION 08-17/2018

**SEWAGE TREATMENT UPGRADES
SPRINGHILL INSTITUTION
SPRINGHILL, NS**

**HEADWORKS CHANNEL
PLAN AND SECTION**

designed SML	conçu
date 2022-04-14	
drawn SML	dessiné
date 2022-04-14	
approved PP	approuvé
date 2022-04-14	
Tender	Soumission
PWSC Project Manager	Administrateur de projets TPSC
project number	no. du projet
R.061876.001	
drawing no.	no. du dessin
M01	

