



**RETURN BIDS TO:**

Parks Canada Agency Bid Receiving Unit  
National Contracting Services

**Bid Fax:** 1-855-983-1808

**Bid Email:** [soumissionsami-bidsrpc@pc.gc.ca](mailto:soumissionsami-bidsrpc@pc.gc.ca)

This is the only acceptable email address for responses to the bid solicitation. Bids submitted by email directly to the Contracting Authority or to any other email address will not be accepted.

The maximum email file size is 15 megabytes. The Parks Canada Agency (PCA) is not responsible for any transmission errors. Emails with links to bid documents will not be accepted.

**REVISION 002 TO A  
INVITATION TO TENDER**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions remain the same.

**Issuing Office:**

Parks Canada Agency  
National Contracting Services  
Calgary, AB

<b>Title:</b> Waskesiu Storm Drain Improvements Phase 2 – Prince Albert National Park	
<b>Solicitation No.:</b> 5P468-22-0129/A	<b>Date:</b> September 23, 2022
<b>Amendment No.:</b> 002	
<b>Client Reference No.:</b>	
<b>GETS Reference No.:</b> PW-22-01006613	

<b>Solicitation Closes:</b> <b>At:</b> 2:00 PM <b>On:</b> September 27, 2022	<b>Time Zone:</b> MDT
--	--------------------------

<b>F.O.B.:</b> Plant: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other: <input type="checkbox"/>	
<b>Address Enquiries to:</b> Jen Maheu	
<b>Telephone No.:</b> 587-432-8458	<b>Fax No.:</b> 1-855-983-1808
<b>Email Address:</b> <a href="mailto:jennifer.maheu@pc.gc.ca">jennifer.maheu@pc.gc.ca</a>	
<b>Destination of Goods, Services, and Construction:</b> See Herein	

**TO BE COMPLETED BY THE BIDDER**

<b>Vendor/ Firm Name:</b>	
<b>Address:</b>	
<b>Telephone No.:</b>	<b>Fax No.:</b>
<b>Name of person authorized to sign on behalf of the Vendor/ Firm (type or print):</b>	
<b>Signature:</b>	<b>Date:</b>

**Solicitation No.:**  
5P468-22-0129/A

**Amendment No.:**  
002

**Contracting Authority:**  
Jen Maheu

Ver.02.08.21

**Client Reference No.:**

**Title:**  
Waskesiu Storm Drain Improvements Phase 2 – Prince Albert National Park

---

## **Amendment 002**

This amendment is raised to distribute the answers to bidder questions.

### **A. QUESTIONS & ANSWERS**

**Q1** Please provide construction details for the Electrical Kiosk Pad. It is noted on drawing 10/12 but there is not detail on how to construct it.

**A1** Pad will be 22mm thick slab with 15M 300 on center each way on two 2.4 - 200 diameter. Piles with 2 15M rebar full depth.

**Q2** Please provide a specification for the “Water Proofing Membrane” and the “Xypex Waterproofing” noted to be applied to the Insulated Manhole on drawing 8/12.

**A2** Xypex Modified – two coats applied for water proofing.

**Q3** Please clarify if the contractor will be responsible to reinstall the sidewalk, curb and unit pavers where they are disrupted from construction.

**A3** Yes. Contractor also required to coordinate and locate private utilities and Park Owned fibre optic lines prior to construction. Contact information will be provided during preconstruction meeting.

**ALL OTHER TERMS & CONDITIONS REMAIN UNCHANGED.**