

# Addendum Addenda

No./No
2

Project Description / Description de projet		
M7 Remplacement du refroidisseur et des pompes à chaleur		
Project No./No de projet	Departmental Representative / représentant ministériel	Date
5988	Al MacKenzie	27-Sep-2022
Solicitation No./N° de sollicitation		
22-58045		
Notice: This addendum shall form part of the tender documents and all conditions shall apply and be read in conjunction with the original plans and specifications.		
Nota: Cet addenda fait partie intégrale des dossiers d'appel; toutes les conditions énoncées doivent être lues et appliquées en conjonction avec les plans et les devis originaux.		

- | Item No | Description  |
|---------|--|
| 2.1     | <p><b><u>Questions and Answers</u></b></p> <p>2.1.1. Question - Is the current roof under warranty, if not, is there a preferred roofer for the NRC?</p> <p>2.1.1. Answer - No the roof is not under warranty. The roofing sub-contractor is up to the discretion of the General Contractor and they must hold a valid RELIABILITY STATUS, granted or approved by CISD/PWGSC.</p> <p>2.1.2. Question - Is the 20-tonne ceiling crane available for use by contractors to lift the heat pumps onto the upper level?</p> <p>2.1.2. Answer - The NRC hoist/Crane can be used by the contractor however it is NRC policy that it must be certified before and after it's use by the contractor. DymoRam is the preferred company to perform these certifications.</p> <p>2.1.3. Question - Are we permitted to work regular hours?</p> <p>2.1.3. Answer - Yes</p> <p>2.1.4. Question - Will the required fire alarm bypass be performed and costs related be by NRC?</p> <p>2.1.4. - Answer - NRC Personnel will perform all necessary fire alarm bypasses at no cost to the contractor.</p> <p>2.1.5. Question - The Crawlspace works is deemed confined space. Will the contractor or client be providing the rescue plan and attendant?</p> <p>2.1.5. Answer - This space will only be considered confined if the contractor brings something into that area that would have the potential to change the environment of the space, in which case it should be considered a confined space and the contractor will be responsible for their own rescue plan. Outside of that a "buddy" system should be implemented while working in that space.</p> |
| 2.2     | <p><b><u>Alternate Materials</u></b></p> <p>2.2.1. Chilled Water Buffer Tank, equipment tag number 07PVE04 - Amtrol, model number - CWBT200-3-125 is an acceptable alternative.</p>  |

2.2.2. Expansion Tank, equipment tag number 07PVE05, Amtrol, model number - AX-100V as well as Taco, model number - CX215-125 are acceptable alternatives.

2.2.3. Pumps, equipment tag numbers 07CWP01 & 02 - Taco, model number - KV2009D is an acceptable alternative. Contractor is responsible to ensure that the pump selection matches the performance criteria.

**End**