



RETURN BIDS TO:
RETOURNER LES SUBMISSION À :
Parks Canada Agency Bid Receiving Unit
National Contracting Services

Bid Fax: 1-855-983-1808

Bid Email: soumissionsami-bidsrpc@pc.gc.ca

This is the only acceptable email address for responses to bid solicitation. Bids submitted by email directly to the Contracting Authority or to any other email address may not be accepted.

The maximum email file size is 15 megabytes. PCA is not responsible for any transmission errors. Emails with links to bid documents will not be accepted.

REVISION 002 TO A INVITATION TO TENDER

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the offer remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'offre demeurent les mêmes.

Issuing Office - Bureau de distribution :
Parks Canada Agency
National Contracting Services
Gatineau, Qc

Title - Sujet : Fort Henry Masonry Redoubt Recapitalization, Fort Henry National Historic Site		
Solicitation No. - N° de l'invitation : 5P468-22-0135/A	Date : October 25, 2022	
Amendment No. - N° de modification : 002		
Client Reference No. - N° de référence du client : 2261		
GETS Reference No. N° de référence de SEAG : PW-20-01006999		
Solicitation Closes - L'invitation prend fin : At - à : 2:00 PM On - le : November 10, 2022		Time Zone - Fuseau horaire EST - HNE
F.O.B. - F.A.B. : Plant - Usine : <input type="checkbox"/> Destination : <input checked="" type="checkbox"/> Other - Autre : <input type="checkbox"/>		
Address Enquiries to - Adresser toutes demande de renseignements à : Christine Piché		
Telephone No. - N° de telephone : 873-355-8841	Fax No. -N° de télécopieur : 1-855-983-1808	Email Address - Courriel : Christine.piche@pc.gc.ca
Destination of Goods, Services, and Construction - Destination des biens, services, et construction : See Herein		
TO BE COMPLETED BY THE BIDDER - À REMPLIR PAR LE SOUMISSIONNAIRE		
Vendor/ Firm Name - Nom du fournisseur/ de l'entrepreneur :		
Address - Adresse :		
Telephone No. - N° de telephone :	Fax No. - N° de télécopieur :	
Name of person authorized to sign on behalf of the Vendor/Firm Nom de la personne autorisée a signer au nom du fournisseur/ de l'entrepreneur		
Signature :	Date :	

AMENDMENT 002

This amendment is raised to:

- A) Answer questions from bidders;
- B) Addition of a Solicitation Attachment document.

A. QUESTIONS AND ANSWERS

Q10 Please add a cash allowance to remove and reinstall electrical conduit to facilitate masonry restoration work.

A10 A cash allowance will not be provided for the removal and reinstatement of conduits. All work is visible on the walls.

Q11 Please provide extension for the closing date at least for two weeks.

A11 Refer to Addendum #1.

Q12 Regarding the loop cover and frame, please advise where these loop cover are located? Could you provide more pictures of it?

A12 Loop hole locations are shown on the plans, they are all numbered and prefaced with an "L", the appearance and details are shown on dwg S503

Q13 Please advise are interior jambs, soffits, aprons and stools to be restored in this contract?

A13 Yes, windows where interior trim etc. are to be restored are identified in "Section 08 06 00 INTERVENTION SCHEDULE WORK SHEETS"

Q14 Refer to drawing S504, is iron window bar restoration work to be included in the contract?

A14 Yes, scope of work illustrated on S504 is to be included in the contract.

Q15 Refer to drawing S505, is shutter restoration work to be included in the contract?

A15 Yes, scope of work is illustrated on S505 is to be included in the contract.

Q16 Please confirm that for wood windows from RW1-93 to RW1-102 we have to remove, restore and reinstall existing louvred vents (refer to Section 08 06 00).

A16 Windows requiring restoration of louvred vents are indicated on "Section 08 06 00 INTERVENTION SCHEDULE WORK SHEETS"

Q17 As per 3/S206 elevation the grouted anchors are spaced at 400mm O.C. in alternate directions. The spacing of the same anchors according to corner anchor's note on S402 drawing is 1200mm c/c at each direction. What spacing should be quoted? Do we have to install these grout anchors for two corners only?

A17 Anchors are to be installed at the two corners (Grid D & Grid A) of the Redoubt. Refer to revised drawings S203, S206 & S402 issued with Addendum #2.

Solicitation No. - N° de l'invitation :
5P468-22-0135/A

Amd. No. - N° de la modif. :
002

Contracting Authority - Autorité contractante :
Christine Piché

Client Ref. No. - N° de réf. du client :
2261

Title – Titre :
Fort Henry Masonry Redoubt Recapitalization, Fort Henry National Historic Site

- Q18 As per S/601 - photo #23 - We can see something like membrane or paint on the top of the redoubt wall. Do we have to remove it before chinking of the joints?
- A18 All masonry to be cleaned prior to commencement of work and after masonry work is completed. Refer to Spec 04 03 01.13 Period Masonry Cleaning issued with Addendum #2.
- Q19 Do we have to clean the masonry on the top of redoubt (zone of chinking) & caponier roof?
- A19 All masonry to be cleaned prior to commencement of work and after masonry work is completed. Refer to Spec 04 03 01.13 Period Masonry Cleaning issued with Addendum #2
- Q20 There is a lot of white/brown precipitate deposits on exterior stone masonry but we didn't find any specifications related to specific cleaning (abrasive type cleaning, etc.) of heritage masonry except low pressure water cleaning in repointing and mortaring sections.
- A20 Refer to Spec 04 03 01.13 Period Masonry Cleaning issued with Addendum #2
- Q21 Due to current workload and request from our sub-contractors, could you please extend the tender closing to 3 November 2022?
- A21 Refer to Addendum #1.

B. ADDITION OF A SOLICITATION ATTACHEMENT DOCUMENTS

Refer to documents below uploaded on October 25, 2022:

- **04 03 01.13- Period Masonry Cleaning**
- **S203 + 1 + ADD2 + BLOCK 11 EXT ELEV**
- **S206 + 1 + ADD2 + BLOCK 2 EXT ELEV**
- **S402 + 2 + ADD2 + MASONRY REPAIR SECTIONS**

ALL OTHER TERMS & CONDITIONS REMAIN UNCHANGED