

Annex B - Pricing Table					
Contract #					
Purchase Request No:		R000125682			
Client Reference No:		PR57940 - 1000407779			
Department:		Capeiris Border Services Agency			
Destination:		Various			
Requirement:		Cellular Booster Installation			
Item	Product / Service Code	Product / Service Description	Qty	Unit Price D.D.P. Destination	Extended Price
A		B	C	D	E = C x D
CBSA - St. Stephen 3rd Bridge Border Crossing, Building 1					
1		Supply & Install Nextivity Cell-Fi QUATRA 1000 Networked Smart Booster, NU, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 1	1	\$0.00	\$0.00
2		Supply & Install Nextivity Cell-Fi QUATRA 1000 Networked Smart Booster, CU, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 1	4	\$0.00	\$0.00
3		Supply & Install QUATRA Wideband MIMO Antenna (Quatra 1000) with 2x N-Female, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 1	1	\$0.00	\$0.00
4		Supply & Install 600 Coax Cable, 50ohm from the MIMO Antenna to the Networked Smart Booster, NU, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 1	2	\$0.00	\$0.00
5		Supply & Install Cat5e FT6 White from the Networked Smart Booster, NU to the Networked Smart Booster, CU, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 1	4	\$0.00	\$0.00
6		Supply & Install Surge Protector c/w L Bracket, #6 Green, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 1	2	\$0.00	\$0.00
7		Supply & Install Str Tinned Grnd Kit for LMR600 2-Hole Lug 3Ft Lead, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 1	2	\$0.00	\$0.00
8		Supply & Install (1) 10' Mast to install the Antenna c/w grounding, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 1	1	\$0.00	\$0.00
9		Terminate & test the above-mentioned cabling per plans, specs & industry standards, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 1	1	\$0.00	\$0.00
CBSA - St. Stephen 3rd Bridge Border Crossing, Building 2					
1		Supply & Install Nextivity Cell-Fi QUATRA 1000 Networked Smart Booster, NU, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 2	1	\$0.00	\$0.00
2		Supply & Install Nextivity Cell-Fi QUATRA 1000 Networked Smart Booster, CU, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 2	4	\$0.00	\$0.00
3		Supply & Install QUATRA Wideband MIMO Antenna (Quatra 1000) with 2x N-Female, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 2	1	\$0.00	\$0.00
4		Supply & Install 600 Coax Cable, 50ohm from the MIMO Antenna to the Networked Smart Booster, NU, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 2	2	\$0.00	\$0.00
5		Supply & Install Cat5e FT6 White from the Networked Smart Booster, NU to the Networked Smart Booster, CU, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 2	4	\$0.00	\$0.00
6		Supply & Install Surge Protector c/w L Bracket, #6 Green, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 2	2	\$0.00	\$0.00
7		Supply & Install Str Tinned Grnd Kit for LMR600 2-Hole Lug 3Ft Lead, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 2	2	\$0.00	\$0.00
8		Supply & Install 10' Mast to install the Antenna c/w grounding, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 2	1	\$0.00	\$0.00
9		Supply & Install Core drilling to install (1) 2" Sleeve, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 2	1	\$0.00	\$0.00
10		Terminate & test the above-mentioned cabling per plans, specs & industry standards, CBSA - St. Stephen 3rd Bridge Border Crossing, Building 2	1	\$0.00	\$0.00
CBSA - Fosterville					
1		Supply & Install Nextivity Cell-Fi QUATRA 1000 Networked Smart Booster, NU - CBSA - Fosterville	1	\$0.00	\$0.00
2		Supply & Install Nextivity Cell-Fi QUATRA 1000 Networked Smart Booster, CU - CBSA - Fosterville	1	\$0.00	\$0.00
3		Supply & Install QUATRA Wideband MIMO Antenna (Quatra 1000) with 2x N-Female - CBSA - Fosterville	1	\$0.00	\$0.00
4		Supply & Install 600 Coax Cable, 50ohm from the MIMO Antenna to the Networked Smart Booster, NU - CBSA - Fosterville	2	\$0.00	\$0.00
5		Supply & Install Cat5e FT6 White from the Networked Smart Booster, NU to the Networked Smart Booster, CU - CBSA - Fosterville	1	\$0.00	\$0.00
6		Supply & Install Surge Protector c/w L Bracket, #6 Green - CBSA - Fosterville	2	\$0.00	\$0.00
7		Supply & Install (2) Str Tinned Grnd Kit for LMR600 2-Hole Lug 3Ft Lead - CBSA - Fosterville	2	\$0.00	\$0.00
8		Supply & Install (1) 56-foot DMX medium duty tower complete with CBS-07 concrete base stubs, top plate, rotor plate, 2 model 244A cast aluminum mast clamps and all necessary hardware - CBSA - Fosterville	1	\$0.00	\$0.00
9		Supply & Install (1) SURECONX 3-METER (10-FT) 16-GAUGE ANTENNA MAST PIPE c/w with Grounding & Grounding Rod - CBSA - Fosterville	1	\$0.00	\$0.00
10		Digging a hole to install Cell booster tower - CBSA - Fosterville	1	\$0.00	\$0.00
11		Terminate & test the above-mentioned cabling per plans, specs & industry standards - CBSA - Fosterville	1	\$0.00	\$0.00
Technical Authority:		Kim Shirley kim.shirley@cbsa-asfc.ca 343-553-1768	Sub-Total / CAD funds		\$0.00
			Tax (NB 15.00%)		\$0.00
			Total		\$0.00