



Notes

- Layout of Downhill Bent to follow procedure of Geometrical Layout Draw No. 4
- For Precast Beams & Columns see drawings for details
- 8" Chamfer on exposed edges
- Concrete: Footings - 3,000 p.s.i. (at 28 days)
Cast in Place Plugs - 3,000 p.s.i. (at 28 days)

REVISIONS				NAME		DATE	
DEPARTMENT OF PUBLIC WORKS CANADA DEVELOPMENT ENGINEERING BRANCH STRUCTURES DIVISION LENS SNOWSHED T.C.H. MILLER GLACIER NATIONAL PARK DOWNHILL BENT LINE C							
CONCRETE DETAILS							
JOB SUPERVISOR	S. STAMER	DESIGN	J.C.B.	DRAWN	T.D.	CHECK	T.D.
APPROVED	DATE: 11/1/74	TRACED	C.M.P.	OTHER			
CHIEF STRUCTURES DIVISION APPROVED: <i>[Signature]</i> DATE: 11/1/74				PROJECT NO. SD-104			
CHIEF ENGINEER				SHEET 8 of 18			