

SOLICITATION NUMBER: 1000246894

Job showing (**mandatory**): Tuesday December 20th, 2022 at 9h00 AM

TENDER CLOSING DATE: FRIDAY JANUARY 06TH, 2023 AT 2:00 PM (14H)

Health Canada (TUNNEY'S PASTURE)

Sir Frederick Banting (SFB) & Laboratory Centre for Disease Control (LCDC) buildings

New roof exterior staircases (one per building) Design and Specifications



Health
Canada

Santé
Canada


ADDENDUM No.01

DRAWING LEGEND




DENOTES EXTENTS (AS REQUIRED), FOR REMOVAL OF EXISTING GRAVEL BALLAST, ROOF MEMBRANE AND RIGID INSULATION. SEE DRAWING NOTE 1 BELOW.

[TO BE REPLACED BY] DENOTES EXTENTS (AS REQUIRED), FOR REMOVAL OF SNOW AND ROOF STONE BALLAST TO EXPOSE TEXTILE MEMBRANE ON TOP OF ROOFING ISOLATION (ROOFING TYPE: STONE BALLAST REVERSE MEMBRANE) FOR A ZERO ROOF PENETRATION INSTALLATION.



POWDER-COAT FINISH FOR METAL ITEMS FABRICATED FROM SHAPES AND PLATES AAMA 621, CLEAR ANODIZED (SILVER) COLOR.

[TO BE REPLACED BY] POWDER-COAT FINISH FOR **ALUMINUM** FABRICATED (standard AAMA 621) CLEAR ANODIZED (SILVER) COLOR



~~HIGH DENSITY POLYISOCYANURATE RIGID INSULATION BOARD. THICKNESS TO MATCH EXISTING.~~



~~ROOFING MEMBRANE (REPAIR MEMBRANE TYPE) TO MATCH EXISTING.~~

NOT APPLICABLE

SOLICITATION NUMBER: 1000246894

Job showing (**mandatory**): Tuesday December 20th, 2022 at 9h00 AM

TENDER CLOSING DATE: FRIDAY JANUARY 06TH, 2023 AT 2:00 PM (14H)

Health Canada (TUNNEY'S PASTURE)

Sir Frederick Banting (SFB) & Laboratory Centre for Disease Control (LCDC) buildings

New roof exterior staircases (one per building) Design and Specifications



Health
Canada

Santé
Canada

ADDENDUM No.01

DRAWING NOTES

05 DENOTES NEW METAL STAIR ASSEMBLY. STAIR ASSEMBLY TO BE PREFINISHED AS PER **[PC-01]** IN LEGEND ABOVE, UNLESS NOTED OTHERWISE.

[TO BE REPLACED BY] DENOTES NEW **ALUMINUM** STAIRCASE ASSEMBLY TO BE PREFINISHED CLEAR ANODIZED (SILVER) COLOR AS PER [PC-01] IN LEGEND ABOVE

06 NEW PREFABRICATED GUARDRAIL & RUBBER MAT ASSEMBLY.

[TO BE REPLACED BY] NEW PREFABRICATED ALUMINUM GUARDRAIL & ROOF WEIGHTED STEEL BASEPLATE ASSEMBLY

07 MIN. 610mm x 610mm PRECAST CONCRETE PAVERS.

[TO BE REPLACED BY] 610mm x 610mm x 50.8mm thick PRECAST CONCRETE PAVERS

END of ADDENDUM No.01

SOLICITATION NUMBER: 1000246894

Job showing (**mandatory**): Tuesday December 20th, 2022 at 9h00 AM

TENDER CLOSING DATE: FRIDAY JANUARY 06TH, 2023 AT 2:00 PM (14H)

Health Canada (TUNNEY'S PASTURE)

Sir Frederick Banting (SFB) & Laboratory Centre for Disease Control (LCDC) buildings

New roof exterior staircases (one per building) Design and Specifications



Health
Canada

Santé
Canada

ADDENDUM No.01

LÉGENDE DU DESSIN



INDIQUE L'ENTENDUE (COMME REQUIS) DE BALLAST EN GRAVIER, DE REVÊTEMENT D'ÉTANCHÉITÉ DE TOITURE, ET D'ISOLANT RIGIDE EXISTANTS À ENLEVER. VOIR LA NOTE DE DESSIN 01 DESSOUS.

[À REMPLACER PAR] INDIQUE LES ÉTENDUES DES TRAVAUX (AU BESOIN) POUR L'ENLÈVEMENT DE LA NEIGE ET DU BALLAST EN PIERRE DU TOIT AFIN D'EXPOSER LA MEMBRANE EN TEXTILE AU-DESSUS DE L'ISOLATION DE LA TOITURE (TYPE DE TOITURE : MEMBRANE INVERSE) POUR UNE INSTALLATION SANS PÉNÉTRATION

PC-01

SE SERVIR D'UN ENDUIT DE POUDRE, DE COULEUR ASSORTIE À UN FINI ANODISÉ (ARGENTÉ) CONFORME À AAMA 621, POUR FINIR LES ARTICLE FABRIQUÉ DE TÔLE OU PROFILES CREUX

[À REMPLACER PAR] ALUMINIUM AVEC FINITION EN POUDRE FABRIQUÉ (standard AAMA 621) COULEUR ANODISÉE TRANSPARENTE (ARGENT)

~~PI-01~~

~~PANNEAU ISOLANT RIGIDE DE POLYISOCYANURATE RIGIDE À HAUTE DENSITÉ. ÉPAISSEUR ASSORTIE AUX CONDITIONS EXISTANTES.~~

NON-APPLICABLE

SOLICITATION NUMBER: 1000246894

Job showing (**mandatory**): Tuesday December 20th, 2022 at 9h00 AM

TENDER CLOSING DATE: FRIDAY JANUARY 06th, 2023 AT 2:00 PM (14H)

Health Canada (TUNNEY'S PASTURE)

Sir Frederick Banting (SFB) & Laboratory Centre for Disease Control (LCDC) buildings

New roof exterior staircases (one per building) Design and Specifications



Health
Canada

Santé
Canada

ADDENDUM No.01

NOTES DU DESSIN

05 NOUVEL ESCALLIER PRÉFABRIQUÉS EN MÉTAL À MOINS D'INDICATION CONTRAIRE. L'ESCALIER (ET SES COMPOSANTES DOIT ÊTRE PRÉFINI SELON **[PC-01]** TEL QU'INDIQUÉ DANS LA LÉGENDE.

[À REMPLACER PAR] INDIQUE UN NOUVEL ESCALIER EN ALUMINIUM FINITION DE COULEUR ANODISÉE CLAIRE (ARGENT) SELON [PC-01] DANS LA LÉGENDE CI-DESSUS

06 NOUVEAUX GARDE-CORPS PRÉFABRIQUÉ ET TAPIS DE CAOUTCHOU.

[À REMPLACER PAR] NOUVEAU GARDE-CORPS PRÉFABRIQUÉ EN ALUMINIUM ET ENSEMBLE DE PLAQUES DE BASE EN ACIER LESTÉ DE TOITURE

07 DALLES DE BÉTON PRÉFABRIQUÉES DE 610mm x 610mm.

[À REMPLACER PAR]
PAVÉS EN BÉTON PRÉFABRIQUÉ 610 mm x 610 mm x 50,8 mm d'épaisseur

FIN de l'ADDENDUM No.01