



RETURN BIDS TO:

Parks Canada Agency Bid Receiving Unit
National Contracting Services

Bid Fax: 1-855-983-1808

Bid Email: soumissionsami-bidsrpc@pc.gc.ca

This is the only acceptable email address for responses to bid solicitation. Bids submitted by email directly to the Contracting Authority or to any other email address will not be accepted.

The maximum email file size is 15 megabytes. Parks Canada Agency (PCA) is not responsible for any transmission errors. Emails with links to bid documents will not be accepted.

**REVISION 002 TO A
INVITATION TO TENDER**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions remain the same.

Issuing Office:

Parks Canada Agency
National Contracting Services
Cornwall, Ontario, K6H 6S2

Title: Highway Renovations, Gulf Shore Parkway, PEI	
Solicitation No.: 5P468-22-0223/A	Date: January 20, 2023
Amendment No.: 002	
Client Reference No.: RPA2407	
GETS Reference No.: PW-22-01018284	

Solicitation Closes: At: 2:00 PM On: January 26, 2023	Time Zone: HNA - AST
--	--------------------------------

F.O.B.: Plant: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other: <input type="checkbox"/>	
Address Enquiries to: Sheldon Lalonde	
Telephone No.: 343-585-3836	Fax No.: 1-855-983-1808
Email Address: sheldon.lalonde@pc.gc.ca	
Destination of Goods, Services, and Construction: See Herein – Voir aux présentes	

TO BE COMPLETED BY THE BIDDER

Vendor/ Firm Name:	
Address:	
Telephone No.:	Email Address:
Name of person authorized to sign on behalf of the Vendor/ Firm (type or print):	
Signature:	Date:

Amendment 002

This amendment is raised to:

A. Solicitation Closing Date

The closing date for tender 5P468-22-0223/A is extended from **January 24, 2023** to **January 26, 2023**.

B. Site Visit Information

1. Site Visit Attendees

Vendor
Delway
Birt & MacKay Backhoe Services
Island Coastal
Chapman Brothers

C. Questions and Answers

Q1: Has Parks Canada Agency consulted granite suppliers about availability?

A1: PCA has not contacted any supplier.

Q2: Will temporary scales be required for all borrow sources?

A2: Successful bidder shall supply as per specification.

Q3: Will PCA accept the certification of permanent scales located at quarries?

A3: Yes.

Q4: Has PCA determined a priority timeframe for protection?

A4: No timeframe has been predetermined by PCA. However, bidders should be aware of the species at risk window as indicated within the BIA.

In addition, the harbour authority at North Lake will begin pumping sand into the containment cell as of April 6th. Successful bidder should prepare this site prior to pumping operations.

Q5: Can PCA provide a breakdown of rip rap quantities for each location?

A5: Approximate rip rap quantities by location are as follows:

R-25 Rip rap:

Covehead - 1400t
Stanhope - 200t
Dalvay - 2200t

Total - 3800t

R-500 Rip rap:

Covehead - 3750t
Stanhope - 700t
Dalvay - 11100t

Total - 15,550t

Q6: Will the directional sign located at Dalvay have to be removed prior to commencement of work?

A6: Sign is anticipated to lie outside of the limits of work.

Q7: There is small section of scour located at the northeast crash block. Will the Contractor have to reinstate?

A7: Contractor is not required to repair.

Q8: Regarding the Gulf Shore Parkway project number 5P468-22-0223/A, the latest appendix states that the embankment at the Dalvay Corner is to be buried with sand from North Lake. Has this sand been secured by Parks Canada or is the property of Parks Canada and the contractor will only be responsible for the trucking and placement of the sand. Is this the only source of sand that will be accepted for fill the total quantity on the unit price table in the tender document?

A8: The sand source has been secured by Parks Canada. Contractor shall work with the North Lake Harbour Authority to remove the sand from the containment cell. Moreover, this source has been tested and is considered the only acceptable source.

D. Tender Package

Revisions to the Specifications:

1. ADD: Section 01 14 00 – Work Restrictions

1.3.2 In the event that damage occurs to the Gulf Shore Parkway at either the Covehead Bridge or Dalvay Beach areas during construction, a quantity of 50 tonnes of Asphalt Type 'B' – seal coat has been carried to assist the contractor with repairs. Should quantities due to construction damage exceed the quantities herein, all additional quantities shall be deemed the contractor's responsibility and shall be repaired at the owner's expense.

E. Solicitation Revisions

Delete: **Appendix 1 – Combined Price Form**, in its entirety

Replace with: **Appendix 1 – Combined Price Form** (rev.012023), See attached

Note: Canada requires the attached revised Appendix 1 - Price Form to be used and received before the solicitation closing date and time. Failure to submit the revised Appendix 1 Price Form will result in your bid being deemed non-responsive.

Changes are shown in red.

ALL OTHER TERMS & CONDITIONS REMAIN UNCHANGED.

APPENDIX 1 - COMBINED PRICE FORM (rev.012023)

- 1) The prices per unit will govern in establishing the Total Extended Amount. Any arithmetical errors in this Appendix will be corrected by Canada.
- 2) Canada may reject the bid if any of the prices submitted do not reasonably reflect the cost of performing the part of the work to which that price applies.
- 3) Bidders are reminded that it is their responsibility to include in their bid all work as described in the drawings and specifications.

LUMP SUM TABLE

The Lump Sum Amount designates Work to which a Lump Sum Arrangement applies.

- (a) Work included in the Lump Sum Amount represents all work not included in the unit price table.
- (b) Pricing for work not accounted for in the Unit Price Table including but not limited to Mobilization, De-Mobilization, Insurance, Bonds, Permits, etc. is to be included in the Lump Sum Table.

Item No.	Specification Reference	Class of Labour, Plant or Material	Unit of Measure-ment	Estimated Quantity	Estimated Total Price applicable tax(es) extra
1	01 25 20	Mobilization / Demobilization	Lump Sum	1	\$
2	02 41 13.14	Asphalt Pavement Removal	Lump Sum	1	\$
3	01 35 00.06	Special Procedure for Traffic Control	Lump Sum	1	\$
4	01 35 43	Environmental Procedures	Lump Sum	1	\$
5	01 50 00	Temporary Facilities and Controls	Lump Sum	1	\$
6	31 23 33.01	Excavating, Trenching and Backfilling – Common Excavation	Lump Sum	1	\$
7	32 17 23	Pavement Markings	Lump Sum	1	\$
8		Other Items Not Included in the Unit Price Table	Lump Sum	1	\$
LUMP SUM AMOUNT (LSA) Excluding applicable tax(es)					\$

UNIT PRICE TABLE

The Unit Price Table designates Work to which a Unit Price Arrangement applies.

- (a) Work included in each item is as described in the referenced specification section.
- (b) The Price per Unit shall not include any amounts for Work that is not included in that unit price Item.

Item No.	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity	Price per Unit applicable tax(es) extra	Estimated Total Price applicable tax(es) extra
1	31 23 33.01	Beach Sand	tonne	20000	\$	\$
2	31 37 00	R-25 Rip Rap	tonne	3800	\$	\$
3	31 37 00	R-500 Rip Rap	tonne	15550	\$	\$
4	31 37 00	Sandstone Rock	tonne	1200	\$	\$
5	32 11 16.01	Select Borrow	tonne	3100	\$	\$
6	32 11 23	Aggregate Base Courses – Class “A” Gravel	tonne	480	\$	\$
7	32 12 16	Asphalt Paving - Type “A” Base Coat	tonne	25	\$	\$
8	32 12 16	Asphalt Paving – Type “B” Seal Coat	tonne	120	\$	\$
9	32 91 19	Topsoil and Finish Grading	square metre	1200	\$	\$
10	32 92 19.16	Hydraulic Seeding and Dry Mulch	square metre	1200	\$	\$
11	33 42 13	Pipe Culverts – HDPE Pipe	metre	4	\$	\$
12	34 71 13.25	Vehicle W-Beam Guiderail	metre	50	\$	\$
TOTAL EXTENDED AMOUNT (TEA) Excluding applicable tax(es)					\$	
TOTAL BID AMOUNT (LSA +TEA) Excluding applicable tax(es)					\$	