

RPPM A1 (841x594)

<u>P</u>	(NPT)
	SPIRAX SARCO
	STR1
	FT14-4.5
	DN20
	FOR DRIP LEG
	STR2
	FT14-4.5
	DN40
	FOR STEAM COILS

GENERAL DRAWING NOTES:

- 1. FOR CLARITY, ONLY LOWER PORTION OF 09AHU03 AND RELEVANT PIPING ARE SHOWN IN THE PLANS.
- 2. SCHEDULE ALL WORK TO MINIMIZE THE DOWNTIME OF THE AIR HANDLING UNIT. 3. WORK DESCRIBED IN DEMOLITION NOTES AND NEW INSTALLATION NOTES 1 TO 6 INCLUSIVE SHOULD BE
- CARRIED AS SOON AS POSSIBLE AFTER CONTRACT AWARD. 4. WORK DESCRIBED IN NEW WORK NOTES ? TO ? INCLUSIVE SHOULD BE CARRIED OUT AFTER THE NEW HEATING COIL IS RECEIVED.
- 5. A WEEKEND SHUT-DOWN OF 09AHU03 WILL BE SCHEDULED FOR INSTALLATION OF THE NEW HEATING COL INSIDE THE UNIT. THE REST OF PIPING, INSULATION, CONTROL AND COMMISSIONING SHOULD BE COMPLETED WHILE THE UNIT IS RUNNING.

DEMOLITION NOTES: (

- 1. REMOVE ALL ACM (ASBESTOS CONTAINED MATERIAL) LOCATED IN MECHANICAL ROOM B43. REFER TO DESIGNATED SUBSTANCES REPORT AND SPECIFICATION FOR DETAILS.
- 2. REMOVE DISCONNECTED STEAM PRE-HEAT COIL C/W ALL RELATED STEAM AND CONDENSATE PIPING AS SHOWN. CAP STEAM AND CONDENSATE PIPE AT MAIN.
- 3. REMOVE EXISTING FILTER RACK TO MAKE ROOM FOR NEW PRE-HEAT COIL.
- 4. REMOVE EXISTING ACCESS DOOR, RELOCATE TO NEW LOCATION ON THE OUTSIDE AIR DUCTWORK, REFER TO DETAIL 3 FOR NEW LOCATION.
- 5. RELOCATE EXISTING BAS DIFFERENTIAL PRESSURE SENSOR TO NEW FILTER RACK LOCATION.

NEW WORK NOTES:

- 1. RELOCATE EXISTING ACCESS DOOR TO NEW LOCATION SHOWN. PROVIDE SUPPORT UNDER OUTSIDE AIR DUCTWORK IN SHADED AREA TO SUPPORT MAINTENANCE PERSONAL TO ACCESS THE FILTER RACK. CONTRACTOR TO SUBMIT STRUCTURAL SUPPORT SHOP DRAWING STAMPED BY PROFESSIONAL ENGINEER FOR APPROVAL.
- 2. PROVIDE NEW FILTERS RACK C/W FILTERS FOR SIX (6) 610x610x50 (mm) MERV 13 FILTERS. FILTERS TO BE CAMFILL AQ13 OR APPROVED ÉQUAL.
- 3. PROVIDE SHEET METAL ISOLATION PLATES AROUND THE NEW FILTER RACK TO BLOCK AIR FLOW AROUND THE FILTER RACK. ISOLATION PLATES SHOULD BE INSULATED AS PER SPEC.
- 4. INSTALL BAS DIFFERENTIAL PRESSURE SENSOR AT THE NEW FILTER RACK LOCATION.
- 5. INSULATE FRESH AIR DUCTWORK UPSTREAM OF AIR HANDLING UNIT INSIDE THE MECHANICAL ROOM AS PER SPEC
- 6. AFTER THE NEW FILTERS ARE INSTALLED, BALANCE SUPPLY AIR FLOW TO 4250 L/s (9000 CFM) BY REPLACING/ADJUSTING SUPPLY FAN PULLEYS. BALANCE EXHAUST AIR FLOW TO KEEP HIGH BAY ROOM 141 UNDER A NEGATIVE PRESSURE OF -25 PA COMPARE TO OUTSIDE.
- PROVIDE NEW PRE-HEAT FACE & BYPASS STEAM COIL. REFER TO SCHEDULE FOR COIL SPECS. SUPPORT THE COIL USING SUPPORT LEGS FABRICATED WITH ANGLE STEEL ON BOTH ENDS AND IN THE MIDDLE OF COIL. CONTRACTOR TO SUBMIT STRUCTURAL SUPPORT SHOP DRAWING STAMPED BY PROFESSIONAL ENGINEER FOR APPROVAL.
- PROVIDE SHEET METAL ISOLATION PLATES AROUND THE NEW PRE-HEAT COIL TO BLOCK AIR FLOW AROUND THE COIL. ISOLATION PLATES SHOULD BE INSULATED AS PER SPEC.
- PROVIDE NEW STEAM PIPE C/W ALL VALVES AND ACCESSORIES. REFER TO PIPING DIAGRAM FOR DETAILS. INSULATE ALL NEW AND EXISTING STEAM PIPE INSIDE THE MECHANICAL ROOM AS PER SPEC, INCLUDING INSIDE THE AIR HANDLING UNIT.
- PROVIDE NEW CONDENSATE PIPE C/W ALL VALVES AND ACCESSORIES. REFER TO PIPING DIAGRAM AND 10. SCHEDULE FOR DETAILS. INSULATE ALL NEW AND EXISTING CONDENSATE PIPE INSIDE THE MECHANICAL ROOM AS PER SPEC, INCLUDING PIPE INSIDE THE AIR HANDLING UNIT.
- AFTER THE PRE-HEAT COIL IS INSTALLED, BALANCE SUPPLY AIR FLOW AGAIN TO 4250 L/s (9000 CFM). BALANCE EXHAUST AIR FLOW TO KEEP HIGH BAY ROOM 141 UNDER A NEGATIVE PRESSURE OF -25 PA COMPARE TO OUTSIDE.

BAS NOTES AND SEQUENCE OF OPERATION:

- ALL BAS WORK SHALL BE CARRIED OUT BY AINSWORTH CANADA, CONTACT: ARRON DOBSON, (613)247-7938, EMAIL: AARON.DOBSON@AINSWORTH.COM
- 2. IN SUMMER MODE, BAS SYSTEM SHALL CLOSE MAIN STEAM VALVE V1. MAIN STEAM VALVE V1 SHALL BE ON/OFF, NOT MODULATING VALVE, WITH SLOW ACTING ACTUATOR, WITH A MINIMUM OPEN TO CLOSED AND CLOSED TO OPEN TIME OF THREE (3) MINUTES.
- 3. IN WINTER MODE, BAS SYSTEM SHALL OPEN MAIN STEAM VALVE V1, AND MODULATE FACE & BYPASS DAMPER TO MAINTAIN DISCHARGE AIR TEMPERATURE SET POINT. 4. EXISTING CONTROL VALVE TO RE-HEAT COIL SHALL BE CLOSED UNDER NORMAL OPERATION.
- 5. IF DISCHARGE AIR TEMPERATURE REMAINS LOWER THAN SET POINT FOR MORE THAN 30 MINUTES, WITH PRE-HEAT COIL RUNNING AT 100% CAPACITY, BAS SYSTEM SHALL MODULATE CONTROL VALVE TO RE-HEAT COIL TO MAINTAIN DISCHARGE AIR TEMPERATURE SET POINT.
- 6. BAS SYSTEM SHALL MONITOR THE DIFFERENTIAL PRESSURE ACROSS FILTER AND GENERATE AN ALARM WHEN DIFFERENTIAL PRESSURE REACHES 250 Pa. (1" W. C.)

		National Research Council Canada	Conseil national de recherches Canada
MECHA	ANICAL DRAWING SYMBOLS LEGEND	Real Property Planning and Management Branch	Planification et gestion des biens immobiliers
	TYPICAL EXISTING TYPICAL NEW		
	TYPICAL DEMOLITION / REMOVALS		
	MEDIUM PRESSURE STEAM SUPPLY MEDIUM PRESSURE CONDENSATE RETURN	GENERAL NOTES • CONTRACTOR TO VERIFY ALL DIMENSIONS AND	
	PIPE UP		
	PIPE DOWN	CLEARANCES ON SITE PRIOR TO REPORT ANY DISCREPANCIES AND DEPARTMENTAL REPRESENTATIVE.	
_	CAP CONTINUE	CONTRACTOR MUST VISIT THE SIT THEMSELF WITH THE SCOPE OF T	
'		PROJECT COMMENCEMENT.	
- *	REDUCER - ECCENTRIC (BOTTOM FLAT) GATE VALVE	 ALL TRADES TO COORDINATE WOF APPROVAL OF DEPARTMENTAL RE ANY CONFLICTS AND/OR INTERFE 	PRESENTATIVE TO AVOID
	GLOBE VALVE	ANY AND ALL REQUIRED SHUTDO	WNS SHALL BE
必 必	2-WAY CONTROL VALVE (PNEUMATIC) 2-WAY CONTROL VALVE (ELECTRONIC)	• INSTALLATION OF ALL SYSTEMS S	HALL BE IN ACCORDANCE
	STRAINER	WITH APPLICABLE CODES AND STCONTRACTOR TO BE RESPONSIBLE	
V1 ⊗	SWING CHECK VALVE (15" TYPE) STEAM TRAP	AND REPAIR OF ANY DAMAGE CA	USED BY WORK.
M	FLEXIBLE CONNECTION	 CONTRACTOR SHALL PREVENT TH DEBRIS BEYOND AREA OF WORK SURFACES AT COMPLETION. 	
	SPRING LOADED VACUUM BREAKER PRESSURE GAUGE		
♥	ACTUATOR		
		Image: state of the state	ZM By: Par: Date imprimée Iditions and be responsible I'etat des liéux et en ing no. BC projet ULES
		Z M drawn dessiné sca	AUG 2023
		ZM checked vérifié she	AS NOTED et feuille 1 of/de 1
		JWG approved approuvé W.C	
		FG	
		dwg.no.	dessin no.